

MITIGATION OF WATERLOGGING IN DISTRICT RAHIMYAR KHAN

Bill of Quantities

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
1. 2-L Manthar Drain (RD 0+000 to 31+568)						
I. Earthwork						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	616487.5			
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	174315.0			
3	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft.					
	a) 500 ft	1000 Cft	20640.0			
	b) 1000 ft	1000 Cft	2970.0			
	c) 1250 ft	1000 Cft	8792.5			
	d) 1500 ft	1000 Cft	1215.0			
	e) 2000 ft	1000 Cft	18740.0			
	f) 4250 ft	1000 Cft	54772.5			
4	Making boundary or service roads, including dag-belling, leveling and dressing:ii) in ploughed land: a) from 10.0 ft. to 20.0 ft. (3 to 6 m) wide	1 -Chain	410.0			
5	Jungle clearance and removing within 100 ft. light	1000 Sft	315680.0			
II. Data Board						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	24.5			
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.5			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.0			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortor ratio 1:3	100 Cft	81.7			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.7			
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.7			
8	Writing letter or figures per letter per inch height	1 No	500.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.3			
iii. RD Marks						
1	Precast reinfoced cement concrete type "C" 1:2:4.	1 Cft	55.0			
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	125.8			
3	Carriage of consignment job upto 5 KMs Average	1 No	32.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	32.0			
5	Preparing surface and painting with emulation paint 3 coat.	100 Sft	112.0			
6	Writing letter or firgures per letter per inch height (three figure each side).	1 No	320.0			
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	48.4			
				Total Cost		

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
iv. Culverts						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	6406.1			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	361.0			
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	12000.7			
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a)	Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	2556.2			
b)	Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	1444.0			
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	2739.8			
6	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 80mm dia (3 inch)	1 Rft	13.5			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
7	Providing and laying sub-base course of stone product of approved quality and grade, including placing, mixing, spreading and compaction of sub-base material to required depth, camber, grade to achieve 100% maximum modified AASHO dry density, including carriage of all material to site of work except gravel and aggregate. Crushed stone aggregate.	100 Cft	480.0			
8	Providing and laying base course of crushed stone aggregate of approved quality and grade, and supply and spreading of stone screening, including placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHO dry density, including carriage of all materials to site of work except gravel and aggregate.	100 Cft	480.0			
9	Providing and laying road edging of 3" (75 mm) wide and 9" (225 mm) deep brick on end, complete in all respects	1 Rft	120.0			
10	Providing surface treatment of roads, including supply of bitumen and bajri/crushed stone aggregate of approved quality, including cleaning of road surface, heating, spraying bitumen, spreading bajri and rolling etc. complete including carriage of all material to site of work except bajri/crushed stone aggregate for which supply within 5.0 km is included in the rate.					
a	1st coat 35 lbs. bitumen, and 4 Cft. bajri of nominal size 1" (25 mm) per 100 sq. feet or 1.72 Kg bitumen and 0.017 cu. metre bajri per square metre.	100 Sft	960.0			
b	2nd coat 18 lbs. bitumen, and 2 Cft. bajri of nominal size ½" (13 mm) per 100 sq. feet or 1.23 Kg bitumen and 0.008 cu. metre bajri per square metre.	100 Sft	960.0			
c	3rd coat 14 lbs. bitumen, and 1.5 Cft. bajri of nominal size ¼" (6 mm) per 100 sq. feet or 0.69 Kg bitumen and 0.005 cubic metre bajri per square metre.	100 Sft	960.0			
11	Dismantling and removing road pavement, etc., including screening and stacking of byproducts up to one chain lead (30 metre).	100 Cft	960.0			
12	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	6480.0			
14	Rehandling of earthwork: Up to a lead of 50 ft. (15 m).	1000 Cft	6480.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
15	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	346.6			
ii	RCC 1:1.5:3	100 Cft	3360.2			
iii	Base	100 Cft	585.6			
iii	T.S.T	100 Cft	72.0			
				Total Cost		
v. Water Course						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	1867.6			
2	Extra for slush or Daldal including dewatering.	1000 Cft	1867.6			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
a)	Nominal mix ratio 1:4:8	100 Cft	257.2			
b)	Nominal mix ratio 1:2:4	100 Cft	34.0			
4	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	6109.0			
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a)	Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	1266.9			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
b)	Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	769.4			
6	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	751.3			
7	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	80.0			
8	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Lft	189.5			
9	Providing and placing poly sulphide joint sealent 1" wide and 1" deep.	1 Lft	70.0			
10	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	4000.0			
11	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	246.9			
ii	PCC 1:2:4	100 Cft	29.9			
iii	RCC 1.1.5.3	100 Cft	1710.5			
				Total Cost:		
vi. Stone Pitching						
1	Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000 Cft	476.4			
2	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons.	100 Cft	476.4			
3	Formation dressing and preparing subgrade, on slope	100 Sft	735.4			
4	Formation dressing and preparing subgrade, in bed.	100 Sft	130.5			
5	Providing and laying graded bajri 1/8" to 1/2" size on slope.	100 Cft	242.7			
6	Providing and laying graded bajri 1/2" to 2" size on slope.	100 Cft	242.7			
7	Providing and laying graded bajri 1/8" to 1/2" size on level.	100 Cft	43.1			
8	Providing and laying graded bajri 1/2" to 2" size on level.	100 Cft	43.1			
9	Providing and laying stone for top layer only, on slope.	100 Cft	735.4			
10	Providing and laying stone for top layer only, on Level	100 Cft	130.5			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
11	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc or 150 Cft of timber by truck or by any other means owned by the contractor, lead 275 Km.	100 Cft	1682.2			
				Total Cost		
vii. VRB Repair						
1	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	100 Cft	157.9			
2	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60)	100 Kg	1999.5			
3	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	499.9			
4	Providing and fixing 4" dia P.V.C pipe.	1 Rft	12.0			
5	Borrowpit excavation undressed lead upto 100 ft (30 metre). Ordinary soil	1000 Cft	3710.0			
6	Cement plaster 1:3 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	694.5			
7	Providing and laying R.C.C. pipe sewers, moulded with cement concrete 4000 psi conforming to ASTM Specification C-76-20, Class II. Wall B, including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade, jointing with rubber ring, cutting pipes where necessary, testing, etc., complete. 610 mm (24") i/d	1 Rft	96.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
8	Dismantling cement concrete reinforced, separating reinforcement from concrete, cleaning and straightening the same.	100 Cft	307.0			
9	Credit old material	1 Kg	82.0			
Total Cost:						
viii. Tube Well room						
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m)and lift upto 5' (1.5 m) (b) in ordinary soil.1)By Manual	1000 Cft	2179.6			
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextaror equivalent@specified suspension concentrate (SC), MixingAbility-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for10-years complete in all respect.as approved by the Engineer Incharge.	1 Sft	2034.0			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
a)	Nominal mix ratio 1:4:8	100 Cft	422.4			
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	1260.2			
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythenesheet 500 gauge 1½" thick (40 mm).	100 Sft	258.0			
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	480.0			
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	600.0			
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	1163.6			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a)	Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:2:4)	1 Cft	616.7			
b)	Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	73.6			
11	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	4141.8			
12	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	128.0			
13	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	160.0			
14	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	196.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
15	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	382.3			
16	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	398.3			
17	Supplying and filling sand under floor or plugging in wells.	100 Cft	163.8			
18	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	195.8			
19	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	b) Nominal mix ratio 1:2:4	100 Cft	183.4			
20	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	2273.2			
21	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	458.1			
22	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	1959.5			
23	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	52.0			
24	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	8.0			
25	Making top khurra on roof 2' x 2' x 6".	1 No	4.0			
26	Distempering:- 3 coat	100 Sft	2041.1			
27	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	690.2			
28	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	356.0			
29	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, revitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	1339.8			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
30	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.					
a)	20mm (3/4") i/d.	1 Rft	240.0			
b)	25 mm (1") i/d	1 Rft	120.0			
c)	50 mm (2") i/d	1 Rft	60.0			
31	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pipe/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated.					
a)	3/0.74mm (3/0.029").	1 Rft	720.0			
b)	7/0.74mm (7/0.029").	1 Rft	240.0			
32	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only) (a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).	1 Rft	160.0			
33	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.					
a)	10 x 10 cm (4" x 4").	1 Each	4.0			
b)	17.5 x 10 cm (7" x 4").	1 Each	4.0			
c)	22.5 x 10 cm (9" x 4").	1 Each	4.0			
34	Supply and erection of switches 5 amp. Piano Type.	1 Each	80.0			
35	Supply and erection of ceiling rose, bakelite.	1 Each	16.0			
36	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	8.0			
37	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	4.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
38	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessed/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	4.0			
39	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	24.0			
40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaidd DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole (ii) 15-100 Amp (10 KA,15KA)	1 No	8.0			
41	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaidd DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	4.0			
42	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	12.0			
43	Supply and erection of bakelite button holder shade, large size	1 No	12.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
44	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	405.6			
ii	PCC 1:2:4	100 Cft	161.4			
iii	RCC 1:2.4	100 Cft	607.5			
iv	DPC 1:2.4	100 Cft	28.4			
				Total Cost		
2. 3-L Manthar Drain (RD 0+000 to 18+007)						
i. Earthwork						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daladal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	590424.9			
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	112011.0			
3	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft.					
	a) 500 ft	1000 Cft	4055.7			
	b) 750 ft	1000 Cft	4805.0			
	c) 1250 ft	1000 Cft	20505.0			
	d) 3000 ft	1000 Cft	1237.5			
	e) 4500 ft	1000 Cft	15772.5			
	f) 6750 ft	1000 Cft	4869.3			
4	Making boundary or service roads, including dag-belling, leveling and dressing:ii) in ploughed land: a) from 10.0 ft. to 20.0 ft. (3 to 6 m) wide	1 - Chain	255.0			
5	Jungle clearance and removing within 100 ft. light	1000 Sft	180070.0			
				Total Cost:		
ii. Data Board						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	24.5			
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.5			
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.0			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.7			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.7			
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.7			
8	Writing letter or figures per letter per inch height	1 No	500.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.3			
				Total Cost:		
iii. RD Marks:						
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	31.0			
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	70.7			
3	Carriage of consignment job upto 5 KMs Average	1 No	18.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	18.0			
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	63.0			
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	180.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	27.2			
				Total Cost:		
iv. Stone Pitching						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	355.5			
2	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons.	100 Cft	355.5			
3	Formation dressing and preparing subgrade, on slope	100 Sft	681.7			
4	Formation dressing and preparing subgrade, in bed.	100 Sft	126.0			
5	Providing and laying graded bajri 1/8" to 1/2" size on slope.	100 Cft	224.9			
6	Providing and laying graded bajri 1/2" to 2" size on slope.	100 Cft	224.9			
7	Providing and laying graded bajri 1/8" to 1/2" size on level.	100 Cft	41.6			
8	Providing and laying graded bajri 1/2" to 2" size on level.	100 Cft	41.6			
9	Providing and laying stone for top layer only, on slope.	100 Cft	681.7			
10	Providing and laying stone for top layer only, on Level	100 Cft	126.0			
11	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc or 150 Cft of timber by truck or by any other means owned by the contractor, lead 275 Km.	100 Cft	1449.1			
				Total Cost:		
v. VRB Repair						
1	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	100 Cft	136.8			
2	Cement plaster 1:3 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Cft	848.0			
				Total Cost:		
vi. Tube Well room						

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil. 1) By Manual	1000 Cft	1089.8			
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextar or equivalent @ specified suspension concentrate (SC), Mixing Ability-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for 10-years complete in all respect as approved by the Engineer Incharge.	1 Sft	1017.0			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	211.2			
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	630.1			
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythene sheet 500 gauge 1½" thick (40 mm).	100 Sft	129.0			
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	240.0			
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	300.0			
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	581.8			
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:2:4)	1 Cft	308.3			
10	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	36.8			
11	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	2070.9			
12	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	64.0			
13	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	80.0			
14	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8"and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	98.0			
15	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	191.1			
16	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	199.1			
17	Supplying and filling sand under floor or plugging in wells.	100 Cft	81.9			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
18	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	97.9			
19	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) b) Nominal mix ratio 1:2:4	100 Cft	91.7			
20	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	1136.6			
21	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	229.0			
22	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	979.8			
23	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	26.0			
24	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	4.0			
25	Making top khurra on roof 2' x 2' x 6".	1 No	2.0			
26	Distempering:- 3 coat	100 Sft	1020.5			
27	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	345.1			
28	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	178.0			
29	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, revitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	669.9			
30	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.					
	a) 20mm (3/4") i/d.	1 Rft	120.0			
	b) 25 mm (1") i/d	1 Rft	60.0			
	c) 50 mm (2") i/d	1 Rft	30.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
31	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated.					
	a) 3/0.74mm (3/0.029").	1 Rft	360.0			
	b) 7/0.74mm (7/0.029").	1 Rft	120.0			
32	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only) (a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).	1 Rft	80.0			
33	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.					
	a) 10 x 10 cm (4" x 4").	1 Each	2.0			
	b) 17.5 x 10 cm (7" x 4").	1 Each	2.0			
	c) 22.5 x 10 cm (9" x 4").	1 Each	2.0			
34	Supply and erection of switches 5 amp. Piano Type.	1 Each	40.0			
35	Supply and erection of ceiling rose, bakelite.	1 Each	8.0			
36	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	4.0			
37	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	2.0			
38	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessded/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	2.0			
39	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screwes,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	12.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaid DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole (ii) 15-100 Amp (10 KA,15KA)	1 No	4.0			
41	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABB S WITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaid DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	2.0			
42	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	6.0			
43	Supply and erection of bakelite button holder shade, large size	1 No	6.0			
44	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	202.8			
ii	PCC 1:2:4	100 Cft	80.7			
iii	RCC 1.2.4	100 Cft	303.7			
iv	DPC 1.2.4	100 Cft	14.2			
				Total Cost:		
3. 4-L Manthar Drain (RD 0+000 to 17+700)						
I. Earthwork						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, dal dal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	203524.5			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	262075.5			
3	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft.					
	a) 500 ft	1000 Cft	3727.5			
	b) 750 ft	1000 Cft	5270.0			
	c) 4500 ft	1000 Cft	109947.5			
	d) 5500 ft	1000 Cft	70367.5			
4	Borrowpit excavation undressed lead upto 100 ft (30 metre) in a) ordinary soil with a) 500 ft	1000 Cft	60633.0			
5	Making boundary or service roads, including dag-belling, leveling and dressing:ii) in ploughed land: a) from 10.0 ft. to 20.0 ft. (3 to 6 m) wide	1 - Chain	215.0			
6	Jungle clearance and removing within 100 ft. light	1000 Sft	177000.0			
ii. Data Board:						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	24.5			
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.5			
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.0			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.7			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.7			
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.7			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
8	Writing letter or figures per letter per inch height	1 No	500.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.3			
iii. RD Marks:						
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	31.0			
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	70.7			
3	Carriage of consignment job upto 5 KMs Average	1 No	18.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	18.0			
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	63.0			
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	180.0			
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	27.2			
				Total Cost:		
iv. Stone Pitching						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	312.6			
2	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons.	100 Cft	312.6			
3	Formation dressing and preparing subgrade, on slope	100 Sft	525.1			
4	Formation dressing and preparing subgrade, in bed.	100 Sft	129.5			
5	Providing and laying graded bajri 1/8" to 1/2" size on slope.	100 Cft	173.3			
6	Providing and laying graded bajri 1/2" to 2" size on slope.	100 Cft	173.3			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
7	Providing and laying graded bajri 1/8" to 1/2" size on level.	100 Cft	42.7			
8	Providing and laying graded bajri 1/2" to 2" size on level.	100 Cft	42.7			
9	Providing and laying stone for top layer only, on slope.	100 Cft	525.1			
10	Providing and laying stone for top layer only, on Level	100 Cft	129.5			
11	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc or 150 Cft of timber by truck or by any other means owned by the contractor, lead 275 Km.	100 Cft	1207.5			
				Total Cost		
4. Pattan Minara Drain (RD 0+000 to 23+000)						
i. Earthwork						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	2110200.0			
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	680530.0			
3	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft.					
	a) Lead 500 feet	1000 Cft	8217.5			
	b) Lead 1750 ft	1000 Cft	58687.5			
	c) Lead 2750 ft	1000 Cft	75040.0			
4	Making boundary or service roads, including dag-belling, leveling and dressing:ii) in ploughed land: a) from 10.0 ft. to 20.0 ft. (3 to 6 m) wide	1 - Chain	95.0			
6	Jungle clearance and removing within 100 ft. light	1000 Sft	460000.0			
ii. Data Board						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	24.5			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.5			
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.0			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.7			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.7			
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.7			
8	Writing letter or figures per letter per inch height	1 No	500.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.3			
iii. RD Marks						
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	39.6			
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	90.4			
3	Carriage of consignment job upto 5 KMs Average	1 No	23.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	23.0			
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	80.5			
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	230.0			
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	34.8			
				Total Cost		
iv. Stone Pitching						

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
1	Dismantling stone or spawl pitching and apron in silted condition.	100 Cft	93240.0			
2	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinery. (rates includes 100ft lead)	1000 Cft	129745.5			
3	Supply and dumping at site, without boat, including handling of materials within three chains (90 m)	100 Cft	126000.0			
4	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons.	100 Cft	3745.5			
3	Formation dressing and preparing subgrade, on slope	100 Sft	72754.4			
4	Formation dressing and preparing subgrade, in bed.	100 Sft	12167.0			
4	Providing and laying graded bajri 1/8" to 1/2" size on slope.	100 Cft	24008.9			
5	Providing and laying graded bajri 1/2" to 2" size on slope.	100 Cft	24008.9			
6	Providing and laying graded bajri 1/8" to 1/2" size on level.	100 Cft	4015.1			
7	Providing and laying graded bajri 1/2" to 2" size on level.	100 Cft	4015.1			
8	Providing and laying stone for top layer only, on slope.	100 Cft	72754.4			
9	Providing and laying stone for top layer only, on Level	100 Cft	12167.0			
10	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc or 150 Cft of timber by truck or by any other means owned by the contractor, lead 275 Km.	100 Cft	152322.1			
				Total Cost		
v. Water Course						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	1418.0			
2	Extra for slush or Daldal including dewatering.	1000 Cft	1418.0			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	140.1			
	b) Nominal mix ratio 1:2:4	100 Cft	17.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
4	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	4515.8			
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	1063.0			
	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	442.2			
6	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	551.0			
7	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	40.0			
8	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	180.2			
9	Providing and placing poly sulphide joint sealent 1" wide and 1" deep.	1 Rft	50.0			
10	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	2000.0			
11	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	134.5			
ii	PCC 1:2:4	100 Cft	15.0			
iii	RCC 1.1.5.3	100 Cft	1264.4			
				Total Cost:		

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
vi. VRB Repair						
1	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	100 Cft	966.7			
2	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars): Deformed bars (Grade-60)	100 Kg	2080.0			
3	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	520.0			
4	Providing and fixing 4" dia P.V.C pipe.	1 Rft	6.0			
5	Borrowpit excavation undressed lead upto 100 ft (30 metre). Ordinary soil	1000 Cft	8490.0			
6	Cement plaster 1:3 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Cft	3936.0			
7	Providing and laying R.C.C. pipe sewers, moulded with cement concrete 4000 psi conforming to ASTM Specification C-76-20, Class II. Wall B, including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade, jointing with rubber ring, cutting pipes where necessary, testing, etc., complete. 610 mm (24") i/d	1 Rft	48.0			
8	Dismantling cement concrete reinforced, separating reinforcement from concrete, cleaning and straightening the same.	100 Cft	384.0			
9	Credit old material	1 Kg	768.0			
				Total Cost:		
vii. Tube Well room						

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil. 1) By Manual	1000 Cft	3814.2			
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextaror equivalent @ specified suspension concentrate (SC), Mixing Ability-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for 10-years complete in all respect as approved by the Engineer Incharge.	1 Sft	3559.5			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)		0.0			
	a) Nominal mix ratio 1:4:8	100 Cft	739.3			
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	2205.3			
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythene sheet 500 gauge 1½" thick (40 mm).	100 Sft	451.5			
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	840.0			
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	1050.0			
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	2036.3			
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:2:4)	1 Cft	1079.2			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
10	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	128.9			
11	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	7248.1			
12	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	224.0			
13	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	280.0			
14	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	343.0			
15	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	668.9			
16	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	696.9			
17	Supplying and filling sand under floor or plugging in wells.	100 Cft	286.6			
18	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	342.6			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
19	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) b) Nominal mix ratio 1:2:4	100 Cft	321.0			
20	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	3978.1			
21	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	801.6			
22	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	3429.1			
23	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	91.0			
24	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	14.0			
25	Making top khurra on roof 2' x 2' x 6".	1 No	7.0			
26	Distempering:- 3 coat	100 Sft	3571.9			
27	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	1207.9			
28	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	623.0			
29	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, revitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	2344.7			
30	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.					
	a) 20mm (3/4") i/d.	1 Rft	420.0			
	b) 25 mm (1") i/d	1 Rft	210.0			
	c) 50 mm (2") i/d	1 Rft	105.0			
31	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated.					
	a) 3/0.74mm (3/0.029").	1 Rft	1260.0			
	b) 7/0.74mm (7/0.029").	1 Rft	420.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
32	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only) (a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).	1 Rft	280.0			
33	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.					
	a) 10 x 10 cm (4" x 4").	1 Each	7.0			
	b) 17.5 x 10 cm (7" x 4").	1 Each	7.0			
	c) 22.5 x 10 cm (9" x 4").	1 Each	7.0			
34	Supply and erection of switches 5 amp. Piano Type.	1 Each	140.0			
35	Supply and erection of ceiling rose, bakelite.	1 Each	28.0			
36	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	14.0			
37	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	7.0			
38	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessded/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	7.0			
39	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaids DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	42.0			
40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaids DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole (ii) 15-100 Amp (10 KA,15KA)	1 No	14.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
41	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaid DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	7.0			
42	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	21.0			
43	Supply and erection of bakelite button holder shade, large size	1 No	21.0			
44	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	709.7			
ii	PCC 1:2:4	100 Cft	282.5			
iii	RCC 1.2.4	100 Cft	1063.1			
iv	DPC 1.2.4	100 Cft	49.7			
				Total Cost:		
5. Manthar Drain (RD 0+000 to 140+000)						
I. Earthwork						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinery. (rates includes 100ft lead)	1000 Cft	15023937.5			
2	Transportation of earth all types when the total distance, including the lead covered in the item of work.					
	Lead 500 ft	1000 Cft	12747.5			
	Lead 1000 ft	1000 Cft	5975.0			
3	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	2113837.5			
4	Making boundary or service roads, including dag-belling, leveling and dressing:ii) in ploughed land: a) from 10.0 ft. to 20.0 ft. (3 to 6 m) wide	1 - Chain	720.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
6	Jungle clearance and removing within 100 ft. light	1000 Sft	2800000.0			
ii. Data Board						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	24.5			
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.5			
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.0			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.7			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.7			
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.7			
8	Writing letter or figures per letter per inch height	1 No	500.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.3			
iii. RD Marks						
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	242.5			
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	554.1			
3	Carriage of consignment job upto 5 KMs Average	1 No	141.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	141.0			
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	493.5			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	1410.0			
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	213.4			
				Total Cost		
iv. Culverts						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	1489.6			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	132.0			
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	4803.0			
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	1073.0			
	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	528.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	944.0			
6	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 80mm dia (3 inch)	1 Rft	6.0			
7	Providing and laying R.C.C. pipe sewers, moulded with cement concrete 4000 psi conforming to Specification C-76-20, Class II. Wall B, including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade, jointing with rubber ring,cutting pipes where necessary, testing, etc., complete. 24 inch internal dia	1 Rft	48.0			
8	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	5400.0			
9	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	5400.0			
10	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	126.7			
ii	RCC 1:1.5:3	100 Cft	1344.8			
				Total Cost		
v. VRB Repair						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and rammiing lead upto one chain (30 m) and lift upto 5 ft. (1.5 m). in ordinary soil Wing walls.	1000 Cft	1776.0			
2	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1: 4: 8.	100 Cft	73.5			
3	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	100 Cft	2414.1			
4	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60)	100 Kg	61091.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a)	Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects.Type B (nominal mix 1:1.5:3)	1 Cft	13743.3			
b)	Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	192.0			
6	Providing and fixing 4" dia P.V.C pipe.	1 Rft	30.0			
7	Providing and fixing Neoprene bearing pad with laminated steel plate top and bottom. Size (14" x 9" x 1.75")	Cu. Inch	304.6			
8	Borrowpit excavation undressed lead upto 100 ft (30 metre). Ordinary soil	1000 Cft	30345.0			
9	Cement plaster 1:3 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Cft	5976.0			
10	Providing and laying R.C.C. pipe sewers, moulded with cement concrete 4000 psi conforming to ASTM Specification C-76-20, Class II. Wall B, including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade, jointing with rubber ring, cutting pipes where necessary, testing, etc., complete. 610 mm (24") i/d	1 Rft	320.0			
11	Providing and laying sub base course.	100 Cft	2100.0			
12	Providing and laying base course.	100 Cft	2100.0			
13	Providing surface treatment to roads, including supply of bitumen and bujri /crushed stone aggregate of approved quality, including cleaning of road surface, heating and spraying bitumen, spreading bajri and rolling with road roller (including its operation cost, fuel and hire charges, etc.) etc. complete including carriage of all materials to site of work except bajjri/crushed stone aggregate.	100 Sft	2800.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
14	Dismantling cement concrete reinforced, separating reinforcement from concrete, cleaning and straightening the same.	100 Cft	11823.8			
15	Credit old material	1 Kg	-23647.5			
				Total cost:		
vi. Pump House No: 3 (Manthar Drain at 0+000 RD)						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	60639.4			
2	Extra for slush or Daldal including dewatering.	1000 Cft	60639.4			
	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
3	a) Nominal mix ratio 1:4:8	100 Cft	2087.7			
4	b) Nominal mix ratio 1:2:4	100 Cft	1164.4			
5	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars).Deformed Bars (Grade 60)	100 Kg	117054.5			
	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
6	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	16160.1			
7	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	9852.1			
8	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	6041.9			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
9	Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sand blinded.	100 Sft	1758.2			
10	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	1758.2			
11	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	144.0			
12	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	12.0			
13	Making top khurra on roof 2' x 2' x 6".	1 No	6.0			
14	Providing and fixing windows consisting of M.S. box section frame 2"x1½", (50x40mm) leaves frame 1½"x1" (40x25mm) box section frame for glazing 3/8"x3/8" (10x10mm) using 16 SWG sheet 'U' shaped rubber supported with 1"x1/8" (25x3mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section ½"x½" (13x13mm) of 16 SWG for fixing 24 SWG wire gauze on outer side by means of ¾"x1/8" (20x3mm) M.S. flat and screws including grill of M.S. flat ½"x1/8" (13x3mm) or ¼"x¼" (6x6mm) square bar with independent frame of ½"x½" (13x13mm) box section of 16 SWG i/c all C.P. fitting and painting 3 coats complete in all respect.	1 Sft	607.9			
15	Making and fixing steel grated door with 1/16" thick 1.5mm) sheeting, including angle iron frame 2"x2"x3/8" (50x50x10 mm) and ¾" (20 mm) square bars 4" (100 mm)	1 Sft	196.0			
16	Distempering:- 2 coats	100 Sft	5921.9			
17	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	5355.0			
18	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	356.0			
19	Providing and fixing 1¼x1¼"x3/16" (31x31x5 mm) angle" iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	1 No	99.0			
21	Providing and fixing trash rack as per drawing	1 Sft	1368.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
22	Providing and laying Tuff Pavers, having 7000PSI ,crushing strength of approved manufa cturer, over 2"to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope . complete in all respect. (50% Grey / 50% Coloured) 60-mm thick	1 Sft	2738.8			
23	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	738.4			
24	1½"(40 mm) thick mosaic flooring, consisting of ½ " mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1"(25 mm) thick floor of 1:2:4 cement concrete, including rubbing and polishing complete with finishing :-using grey cement	100 Sft	1758.2			
25	Mosaic dado or skirting with one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over ½"(13 mm) thick cement plaster 1:3, including rubbing and polishing, complete with finishing:(a) using grey cement: i) 1/2"(13 mm) thick	100 Sft	112.8			
26	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels(a) Size 1½" x 3/8" (40 x 10 mm)	1 Rft	900.3			
27	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	473.5			
28	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.					
	a) 20mm (3/4") i/d.	1 Rft	500.0			
	b) 25 mm (1") i/d	1 Rft	300.0			
29	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated.					
	a) 3/0.74mm (3/0.029").	1 Rft	1000.0			
	b) 7/0.74mm (7/0.029").	1 Rft	500.0			
30	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.					
	b) 17.5 x 10 cm (7" x 4").	1 Each	10.0			
31	Supply and erection of switches 5 amp. Piano Type.	1 Each	50.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
32	Supply and erection of backlite button holder shade, large size.	1 Each	15.0			
33	Supply and erection of ceiling rose, bakelite.	1 Each	15.0			
34	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screws,necessary wire completb) Double Pole(iii) 6-63 Amp (10 KA)	1 No	1.0			
35	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	10.0			
36	Providing and fixing Pakistan Energy Label NEECA approved Copper winded wall bracket Fan i/c the cost of necessary cable and hardware for connection as approved and directed by Engineer Incharge.ii) 24" Sweep dia	1 Each	10.0			
37	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	15.0			
	Stone Pitching Work					
38	Earthwork in excavation of drains in irrigation channels through excavator / draglines in all kind of soil and conditions	1000 Cft	275894.2			
39	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	10945.4			
40	Formation dressing and preparing subgrade, on slope	100 Sft	6058.7			
41	Formation dressing and preparing subgrade, in bed.	100 Sft	594.7			
42	Providing & laying graded bajri 1/8" to 1/2" gauge on slope (including carriage).	100 Cft	2001.6			
43	Providing & laying graded bajri 1/2" to 2" gauge on slope (including carriage).	100 Cft	2001.6			
44	Providing & laying graded bajri 1/8" to 1/2" gauge on level (including carriage).	100 Cft	196.4			
45	Providing & laying graded bajri 1/2" to 2" gauge on level (including carriage).	100 Cft	196.4			
46	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	6058.7			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
47	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	594.7			
48	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 275Km.(From Sakhi Sarwar)	100 Cft	47639.5			
				Total Cost		
vii. Tube Well room						
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m)and lift upto 5' (1.5 m) (b) in ordinary soil.1)By Manual	1000 Cft	2724.5			
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextaror equivalent@specified suspension concentrate (SC), MixingAbility-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for10-years complete in all respect.as approved by the Engineer Incharge.	1 Sft	2542.5			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	528.1			
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	1575.2			
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythensheet 500 gauge 1½" thick (40 mm).	100 Sft	322.5			
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	600.0			
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	750.0			
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	1454.5			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects.Type B (nominal mix 1:2:4)	1 Cft	770.8			
10	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	92.0			
11	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	5177.2			
12	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	160.0			
13	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	200.0			
14	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8"and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	245.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
15	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	477.8			
16	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	497.8			
17	Supplying and filling sand under floor or plugging in wells.	100 Cft	204.7			
18	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	244.7			
19	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) b) Nominal mix ratio 1:2:4	100 Cft	229.3			
20	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	2841.5			
21	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	572.6			
22	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	2449.4			
23	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	65.0			
24	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	10.0			
25	Making top khurra on roof 2' x 2' x 6".	1 No	5.0			
26	Distempering:- 3 coat	100 Sft	2551.4			
27	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	862.8			
28	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	445.0			
29	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, revitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	1674.8			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
30	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.		0.0			
	a) 20mm (3/4") i/d.	1 Rft	300.0			
	b) 25 mm (1") i/d	1 Rft	150.0			
	c) 50 mm (2") i/d	1 Rft	75.0			
31	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated.					
	a) 3/0.74mm (3/0.029").	1 Rft	900.0			
	b) 7/0.74mm (7/0.029").	1 Rft	300.0			
32	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only) (a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).	1 Rft	200.0			
33	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.					
	a) 10 x 10 cm (4" x 4").	1 Each	5.0			
	b) 17.5 x 10 cm (7" x 4").	1 Each	5.0			
	c) 22.5 x 10 cm (9" x 4").	1 Each	5.0			
34	Supply and erection of switches 5 amp. Piano Type.	1 Each	100.0			
35	Supply and erection of ceiling rose, bakelite.	1 Each	20.0			
36	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	10.0			
37	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	5.0			
38	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessded/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	5.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
39	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screwes,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	30.0			
40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaid DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole (ii) 15-100 Amp (10 KA,15KA)	1 No	10.0			
41	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaid DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	5.0			
42	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)singl rod (40 watts) with one choke and one starter.	1 No	15.0			
43	Supply and erection of bakelite button holder shade, large size	1 No	15.0			
44	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	506.9			
ii	PCC 1:2:4	100 Cft	201.8			
iii	RCC 1.2.4	100 Cft	759.3			
iv	DPC 1.2.4	100 Cft	35.5			
				Total Cost:		

6. Khanpur Drain (RD 0+000 to 84+000)

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
i. Earthwork						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, dal dal and under water) including its disposal and preperation of working pad for operation of machinery. (rates includes 100ft lead)	1000 Cft	10154747.5			
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	4167935.0			
3	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft.					
	a) 500 ft	1000 Cft	100405.0			
	b) 750 ft	1000 Cft	9912.5			
	c) 1000 ft	1000 Cft	24562.5			
	d) 1250 ft	1000 Cft	33180.0			
	e) 1500 ft	1000 Cft	79555.0			
	f) 2500 ft	1000 Cft	53390.0			
	g) 3750 ft	1000 Cft	187560.0			
4	Making boundary or service roads, including dag-belling, leveling and dressing:ii) in ploughed land: a) from 10.0 ft. to 20.0 ft. (3 to 6 m) wide	1 - Chain	45.0			
5	Jungle clearance and removing within 100 ft. light	1000 Sft	1680000.0			
ii. Data Board:						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	24.5			
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.5			
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.0			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortor ratio 1:3	100 Cft	81.7			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.7			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.7			
8	Writing letter or figures per letter per inch height	1 No	500.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.3			
iii. RD Marks:						
1	Precast reinfoced cement concrete type "C" 1:2:4.	1 Cft	146.2			
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	334.1			
3	Carriage of consignment job upto 5 KMs Average	1 No	85.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	85.0			
5	Preparing surface and painting with emulation paint 3 coat.	100 Sft	297.5			
6	Writing letter or firgures per letter per inch height (three figure each side).	1 No	850.0			
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	128.7			
				Total Cost :		
iv. VRB Repair						
1	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	100 Cft	976.3			
2	Cement plaster 1:3 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Cft	4140.0			
				Total Cost :		
7. D-1 Drain (RD 0+000 to 38+250)						
i. Earthwork						

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinery. (rates includes 100ft lead)	1000 Cft	19380715.8			
2	Transportation of earth all types when the total distance, including the lead covered in the item of work.					
	b) Lead 500 feet	1000 Cft	10945.8			
3	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	5396103.8			
4	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	390.0			
ii. Data Board						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	24.5			
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.5			
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.0			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortor ratio 1:3	100 Cft	81.7			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.7			
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.7			
8	Writing letter or figures per letter per inch height	1 No	500.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
	DPC	100 Cft	4.3			
iii. RD Marks:						
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	67.1			
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	153.3			
3	Carriage of consignment job upto 5 KMs Average	1 No	39.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	39.0			
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	136.5			
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	390.0			
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	59.0			
Total Cost :						
iv. Water Course						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	17228.0			
2	Extra for slush or Daldal including dewatering.	1000 Cft	17228.0			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	1464.4			
	b) Nominal mix ratio 1:2:4	100 Cft	187.0			
4	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	44509.4			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	10355.4			
	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	4481.1			
6	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	6197.9			
7	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	440.0			
8	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	1425.4			
9	Providing and placing poly sulphide joint sealent 1" wide and 1" deep.	1 Rft	450.0			
10	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	22000.0			
11	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	1405.9			
ii	PCC 1:2:4	100 Cft	164.6			
iii	RCC 1:1.5:3	100 Cft	12462.6			
				Total Cost:		
v. Culverts						

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	91276.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	1441.5			
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	71072.0			
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	17924.7			
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	5766.0			
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	16855.6			
6	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 80mm dia (3 inch)	1 Rft	60.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
7	Providing and laying sub-base course of stone product of approved quality and grade, including placing, mixing, spreading and compaction of sub-base material to required depth, camber, grade to achieve 100% maximum modified AASHO dry density, including carriage of all material to site of work except gravel and aggregate. Crushed stone aggregate.	100 Cft	480.0			
8	Providing and laying base course of crushed stone aggregate of approved quality and grade, and supply and spreading of stone screening, including placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHO dry density, including carriage of all materials to site of work except gravel and aggregate.	100 Cft	480.0			
9	Providing and laying road edging of 3" (75 mm) wide and	1 Rft	160.0			
10	Providing surface treatment of roads, including supply of bitumen and bajri/crushed stone aggregate of approved quality, including cleaning of road surface, heating, spraying bitumen, spreading bajri and rolling etc. complete including carriage of all material to site of work except bajri/crushed stone aggregate for which supply within 3 miles (5.0 km) is included in the rate.					
a	1st coat 35 lbs. bitumen, and 4 Cft. bajri of nominal size 1" (25 mm) per 100 sq. feet or 1.72 Kg bitumen and 0.017 cu. metre bajri per square metre..	100 Sft	960.0			
b	2nd coat 18 lbs. bitumen, and 2 Cft. bajri of nominal size ½" (13 mm) per %sft or 1.23 Kg bitumen and 0.008 cu. metre bajri per sq. metre.	100 Sft	960.0			
c	3rd coat 14 lbs. bitumen, and 1.5 Cft. bajri of nominal size ¼" (6 mm) per %sft or 0.69 Kg bitumen and 0.005 cubic metre bajri per sq. metre.	100 Sft	960.0			
11	Dismantling and removing road pavement, etc., including screening and stacking of byproducts upto one chain lead (30 metre).	100 Cft	960.0			
12	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	9600.0			
13	Rehandling of earthwork: Upto a lead of 50 ft. (15 m).	1000 Cft	54240.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
14	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	1383.8			
ii	RCC 1:1.5:3	100 Cft	19900.2			
iii	Base	100 Cft	585.6			
iii	T.S.T	100 Cft	72.0			
				Total Cost		
vii. Pump House No: 4 (D-1 Drain at RD 0+100)						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	44596.8			
2	Extra for slush or Daldal including dewatering.	1000 Cft	44596.8			
	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
3	a) Nominal mix ratio 1:4:8	100 Cft	971.8			
4	b) Nominal mix ratio 1:2:4	100 Cft	501.7			
5	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	63787.4			
	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
6	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	9101.7			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
7	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect Type B (Nominal Mix 1:1.5:3)	1 Cft	5073.3			
8	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	5294.2			
9	Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sand blinded.	100 Sft	997.5			
10	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	997.5			
11	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	111.0			
12	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	6.0			
13	Making top khurra on roof 2' x 2' x 6".	1 No	6.0			
14	Providing and fixing windows consisting of M.S. box section frame 2"x1½", (50x40mm) leaves frame 1½"x1" (40x25mm) box section frame for glazing 3/8"x3/8" (10x10mm) using 16 SWG sheet 'U' shaped rubber supported with 1"x1/8" (25x3mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section ½"x1½" (13x13mm) of 16 SWG for fixing 24 SWG wire gauze on outer side by means of ¾"x1/8" (20x3mm) M.S. flat and screws including grill of M.S. flat ½"x1/8" (13x3mm) or ¼"x¼" (6x6mm) square bar with independent frame of ½"x1½" (13x13mm) box section of 16 SWG i/c all C.P. fitting and painting 3 coats complete in all respect.	1 Sft	367.9			
15	Making and fixing steel grated door with 1/16" thick 1.5mm) sheeting, including angle iron frame 2"x2"x3/8" (50x50x10 mm) and ¾" (20 mm) square bars 4" (100 mm)	1 Sft	176.0			
16	Distempering:- 2 coats	100 Sft	3581.6			
17	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	3896.5			
18	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	336.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
19	Providing and fixing 1¼x1¼"x3/16" (31x31x5 mm) angle" iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	1 No	64.0			
20	Providing/fixing stair railing consisting of M.S. Box section size 1-1/2"x3" of 16 SWG welded with M.S. flat 1"x1/8" continuously and welded over M.S. square bars 5/8"x5/8"punched in M.S. flat 2 ¾' high @ 5½" c/c fixed in steps of stair I/C painting 3 coats complete.	1 Rft	71.9			
21	Providing and fixing trash rack as per drawing	1 Sft	368.0			
22	Providing and layingTuff Pavers, having 7000PSI ,crushing strength of approved manufa cturer, over2"to3" sand cushion i/c grouting withsand in joints i/c finishing to require slope . complete in all respect. (50% Grey / 50% Coloured) 60-mm thick	1 Sft	1682.8			
23	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	419.0			
24	1½"(40 mm) thick mosaic flooring, consisting of ½ " mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1"(25 mm) thick floor of 1:2:4 cement concrete, including rubbing and polishing complete with finishing :-using grey cement	100 Sft	997.5			
25	Mosaic dado or skirting with one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over ½"(13 mm) thick cement plaster 1:3, including rubbing and polishing, complete with finishing:(a) using grey cement: i) 1/2"(13 mm) thick	100 Sft	72.1			
26	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels(a) Size 1½" x 3/8" (40 x 10 mm)	1 Rft	519.2			
27	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	236.7			
28	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.					
	a) 20mm (3/4") i/d.	1 Rft	150.0			
	b) 25 mm (1") i/d	1 Rft	150.0			
29	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and caping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated.					

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
	a) 3/0.74mm (3/0.029").	1 Rft	500.0			
	b) 7/0.74mm (7/0.029").	1 Rft	300.0			
30	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.					
	b) 17.5 x 10 cm (7" x 4").	1 Each	5.0			
31	Supply and erection of switches 5 amp. Piano Type.	1 Each	35.0			
32	Supply and erection of backlite button holder shade, large size.	1 Each	10.0			
33	Supply and erection of ceiling rose, bakelite.	1 Each	10.0			
34	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaids DBs and Panels i/c the cost of screws,necessary wire completb) Double Pole(iii) 6-63 Amp (10 KA)	1 No	1.0			
35	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaids DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	5.0			
36	Providing and fixing Pakistan Energy Label NEECA approved Copper winded wall bracket Fan i/c the cost of necessary cable and hardware for connection as approved and directed by Engineer Incharge.ii) 24" Sweep dia	1 Each	6.0			
37	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)singl rod (40 watts) with one choke and one starter.	1 No	10.0			
	<u>Lining Portion</u>					
38	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	34138.4			
39	Compaction of earth work with power Road Roller, i.c ploughing mixing, moistening earth to optimum moisture content in layer etc; complete 90 % maximum modified AASHO dry denisty	1000 Cft	34138.4			
40	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed off undressed within 50 ft. (15 m) lead:- ordinary Soil	1000 Cft	5910.3			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
	Cement plaster 1.5" (40 mm) thick ratio 1:6:-					
41	a) In bed	100 Sft	1100.0			
42	b) On slope	100 Sft	1540.0			
	Cement concrete lining, using washed screened and graded stone aggregate:-					
43	a) In bed, ratio 1:2:4	100 Cft	376.8			
44	b) On slope, ratio 1:2:4	100 Cft	527.5			
45	Providing and placing cement, sand and bituminous joint sealant in ratio 1:2:3, 1/2" wide, 1" deep.	1 Rft	264.0			
46	Bitumen coating to plastered or cement concrete surface:- 10 lbs. per 100 Sft.	100 Sft	132.0			
	Stone Pitching Work					
47	Earthwork in excavation of drains in irrigation channels through excavator / draglines in all kind of soil and conditions	1000 Cft	10137.2			
48	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	10137.2			
49	Formation dressing and preparing subgrade, on slope	100 Sft	3737.1			
50	Formation dressing and preparing subgrade, in bed.	100 Sft	631.2			
51	Providing & laying graded bajri 1/8" to 1/2" gauge on slope (including carriage).	100 Cft	1233.6			
52	Providing & laying graded bajri 1/2" to 2" gauge on slope (including carriage).	100 Cft	1233.6			
53	Providing & laying graded bajri 1/8" to 1/2" gauge on level (including carriage).	100 Cft	208.3			
54	Providing & laying graded bajri 1/2" to 2" gauge on level (including carriage).	100 Cft	208.3			
55	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	3738.2			
56	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	631.2			
57	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 275Km.(From Sakhi Sarwar)	100 Cft	33005.5			
				Total Cost		
viii. Inlets						
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil. By Manual	1000 Cft	14140.8			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	1744.5			
	b) Nominal mix ratio 1:2:4	100 Cft	180.4			
3	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	2798.9			
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	2377.1			
	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	823.5			
5	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	9601.9			
6	Providing and laying dry, hand packed stone apron as per drawing	100 Cft	4464.8			
7	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	4880.0			
8	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	1674.7			
i	PCC 1:2:4	100 Cft	158.7			
ii	RCC 1:1.5:3	100 Cft	2688.5			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
iii	Dry Hand Pack Stone	100 Cft	6027.5			
				Total Cost:		
ix. Tube Well room						
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil. 1) By Manual	1000 Cft	6538.7			
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextaror equivalent @ specified suspension concentrate (SC), Mixing Ability-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for 10-years complete in all respect as approved by the Engineer Incharge.	1 Sft	6102.0			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	0.0 1267.3			
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	3780.5			
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythene sheet 500 gauge 1½" thick (40 mm).	100 Sft	774.0			
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	1440.0			
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	1800.0			
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	3490.8			
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:2:4)	1 Cft	1850.0			
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	220.9			
10	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	12425.3			
11	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	384.0			
12	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	480.0			
13	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8"and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	588.0			
14	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	1146.8			
15	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	1194.8			
16	Supplying and filling sand under floor or plugging in wells.	100 Cft	491.3			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
17	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	587.3			
18	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) b) Nominal mix ratio 1:2:4	100 Cft	550.3			
19	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	6819.7			
20	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	1374.2			
21	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	5878.5			
22	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	156.0			
23	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	24.0			
24	Making top khurra on roof 2' x 2' x 6".	1 No	12.0			
25	Distempering:- 3 coat	100 Sft	6123.2			
26	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	2070.7			
27	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	1068.0			
28	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, revitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	4019.5			
29	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.					
	a) 20mm (3/4") i/d.	1 Rft	720.0			
	b) 25 mm (1") i/d	1 Rft	360.0			
	c) 50 mm (2") i/d	1 Rft	180.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
30	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated. a) 3/0.74mm (3/0.029").	1 Rft	2160.0			
	b) 7/0.74mm (7/0.029").	1 Rft	720.0			
31	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only) (a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).	1 Rft	480.0			
32	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.					
	a) 10 x 10 cm (4" x 4").	1 Each	12.0			
	b) 17.5 x 10 cm (7" x 4").	1 Each	12.0			
	c) 22.5 x 10 cm (9" x 4").	1 Each	12.0			
33	Supply and erection of switches 5 amp. Piano Type.	1 Each	240.0			
34	Supply and erection of ceiling rose, bakelite.	1 Each	48.0			
35	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	24.0			
36	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	12.0			
37	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessed/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	12.0			
38	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaids DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	72.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
39	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaid DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole (ii) 15-100 Amp (10 KA,15KA)	1 No	24.0			
40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABB S WITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaid DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	12.0			
41	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	36.0			
42	Supply and erection of bakelite button holder shade, large size	1 No	36.0			
43	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	1216.7			
ii	PCC 1:2:4	100 Cft	484.3			
iii	RCC 1.2.4	100 Cft	1822.4			
iv	DPC 1.2.4	100 Cft	85.1			
				Total Cost :		
8. D-1 Sub Drain (RD 0+000 to 13+250)						
I. Earthwork						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, dal dal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	4710315.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	2201861.3			
3	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft. a) Lead 500 feet	1000 Cft	17267.5			
4	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	130.0			
ii. Data Board:						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	24.5			
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.5			
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.0			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.7			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.7			
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.7			
8	Writing letter or figures per letter per inch height	1 No	500.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.3			
iii. RD Marks:						
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	22.4			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	51.1			
3	Carriage of consignment job upto 5 KMs Average	1 No	13.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	13.0			
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	45.5			
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	130.0			
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	19.7			
				Total Cost		
iv. Water Course						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	6436.1			
2	Extra for slush or Daldal including dewatering.	1000 Cft	6436.1			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	529.7			
	b) Nominal mix ratio 1:2:4	100 Cft	68.0			
4	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	16212.1			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	3788.5			
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	1615.5			
6	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	2288.9			
7	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	160.0			
8	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	518.0			
9	Providing and placing poly sulphide joint sealent 1" wide and 1" deep.	1 Rft	160.0			
10	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	8000.0			
11	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	508.5			
ii	PCC 1:2:4	100 Cft	59.8			
iii	RCC 1.1.5.3	100 Cft	4539.4			
				Total Cost:		
v. Culverts						

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	36435.2			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	510.0			
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	26990.4			
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	6956.8			
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	2040.0			
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	7707.6			
6	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 80mm dia (3 inch)	1 Rft	22.5			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
7	Providing and laying sub-base course of stone product of approved quality and grade, including placing, mixing, spreading and compaction of sub-base material to required depth, camber, grade to achieve 100% maximum modified AASHO dry density, including carriage of all material to site of work except gravel and aggregate. Crushed stone aggregate.	100 Cft	180.0			
8	Providing and laying base course of crushed stone aggregate of approved quality and grade, and supply and spreading of stone screening, including placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHO dry density, including carriage of all materials to site of work except gravel and aggregate.	100 Cft	180.0			
9	Providing and laying road edging of 3" (75 mm) wide and	1 Rft	60.0			
10	Providing surface treatment of roads, including supply of bitumen and bajri/crushed stone aggregate of approved quality, including cleaning of road surface, heating, spraying bitumen, spreading bajri and rolling etc. complete including carriage of all material to site of work except bajri/crushed stone aggregate for which supply within 3 miles (5.0 km) is included in the rate.					
a)	1st coat 35 lbs. bitumen, and 4 Cft. bajri of nominal size 1" (25 mm) per 100 sq. feet or 1.72 Kg bitumen and 0.017 cu. metre bajri per square metre..	100 Sft	360.0			
b)	2nd coat 18 lbs. bitumen, and 2 Cft. bajri of nominal size ½" (13 mm) per %sft or 1.23 Kg bitumen and 0.008 cu. metre bajri per sq. metre.	100 Sft	360.0			
c)	3rd coat 14 lbs. bitumen, and 1.5 Cft. bajri of nominal size ¼" (6 mm) per %sft or 0.69 Kg bitumen and 0.005 cubic metre bajri per sq. metre.	100 Sft	360.0			
11	Dismantling and removing road pavement, etc., including screening and stacking of byproducts upto one chain lead (30 metre).	100 Cft	360.0			
12	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	3200.0			
13	Rehandling of earthwork: Upto a lead of 50 ft. (15 m).	1000 Cft	20960.0			
14	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
i	PCC 1:4:8	100 Cft	489.6			
ii	RCC 1:1.5:3	100 Cft	7557.3			
iii	Base	100 Cft	219.6			
iii	T.S.T	100 Cft	27.0			
				Total Cost		
vi. Stone Pitching						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	269.3			
2	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons.	100 Cft	269.3			
3	Formation dressing and preparing subgrade, on slope	100 Sft	480.7			
4	Formation dressing and preparing subgrade, in bed.	100 Sft	126.0			
5	Providing and laying graded bajri 1/8" to 1/2" size on slope.	100 Cft	158.6			
6	Providing and laying graded bajri 1/2" to 2" size on slope.	100 Cft	158.6			
7	Providing and laying graded bajri 1/8" to 1/2" size on level.	100 Cft	41.6			
8	Providing and laying graded bajri 1/2" to 2" size on level.	100 Cft	41.6			
9	Providing and laying stone for top layer only, on slope.	100 Cft	480.7			
10	Providing and laying stone for top layer only, on Level	100 Cft	126.0			
11	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc or 150 Cft of timber by truck or by any other means owned by the contractor, lead 275 Km.	100 Cft	1091.5			
				Total Cost		
vii. Inlets						
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m)and lift upto 5' (1.5 m) (b) in ordinary soil. By Manual	1000 Cft	3514.7			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	463.4			
	b) Nominal mix ratio 1:2:4	100 Cft	48.1			
3	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	746.4			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	625.5			
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	216.0			
5	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	2524.5			
6	Providing and laying dry, hand packed stone apron as per drawing	100 Cft	950.0			
7	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	1280.0			
8	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	444.9			
i	PCC 1:2:4	100 Cft	42.3			
ii	RCC 1:1.5:3	100 Cft	706.9			
iii	Dry Hand Pack Stone	100 Cft	1282.5			
				Total Cost		
viii. Tube Well room						

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil. 1) By Manual	1000 Cft	544.9			
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextaror equivalent @ specified suspension concentrate (SC), Mixing Ability-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for 10-years complete in all respect as approved by the Engineer Incharge.	1 Sft	508.5			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	105.6			
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	315.0			
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythene sheet 500 gauge 1½" thick (40 mm).	100 Sft	64.5			
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	120.0			
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	150.0			
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	290.9			
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:2:4)	1 Cft	154.2			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	18.4			
11	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	1035.4			
12	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	32.0			
13	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	40.0			
14	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	49.0			
15	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	95.6			
16	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	99.6			
17	Supplying and filling sand under floor or plugging in wells.	100 Cft	40.9			
18	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	48.9			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
19	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) b) Nominal mix ratio 1:2:4	100 Cft	45.9			
20	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	568.3			
21	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	114.5			
22	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	489.9			
23	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	13.0			
24	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	2.0			
25	Making top khurra on roof 2' x 2' x 6".	1 No	1.0			
26	Distempering:- 3 coat	100 Sft	510.3			
27	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	172.6			
28	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	89.0			
29	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, revitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	335.0			
30	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.					
	a) 20mm (3/4") i/d.	1 Rft	60.0			
	b) 25 mm (1") i/d	1 Rft	30.0			
	c) 50 mm (2") i/d	1 Rft	15.0			
31	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated.					
	a) 3/0.74mm (3/0.029").	1 Rft	180.0			
	b) 7/0.74mm (7/0.029").	1 Rft	60.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
32	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only) (a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).	1 Rft	40.0			
33	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.					
	a) 10 x 10 cm (4" x 4").	1 Each	1.0			
	b) 17.5 x 10 cm (7" x 4").	1 Each	1.0			
	c) 22.5 x 10 cm (9" x 4").	1 Each	1.0			
34	Supply and erection of switches 5 amp. Piano Type.	1 Each	20.0			
35	Supply and erection of ceiling rose, bakelite.	1 Each	4.0			
36	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	2.0			
37	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	1.0			
38	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessded/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	1.0			
39	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	6.0			
40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaidd DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole (ii) 15-100 Amp (10 KA,15KA)	1 No	2.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
41	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaid DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	1.0			
42	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	3.0			
43	Supply and erection of bakelite button holder shade, large size	1 No	3.0			
44	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	101.4			
ii	PCC 1:2:4	100 Cft	40.4			
iii	RCC 1.2.4	100 Cft	151.9			
iv	DPC 1.2.4	100 Cft	7.1			
				Total Cost :		
9. D-2 Drain (RD 0+000 to 12+615)						
I. Earthwork						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	2187776.7			
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	1607647.4			
3	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft.					
	a) 500 ft	1000 Cft	1752.5			
	b) 750 ft	1000 Cft	16955.0			
	c) 3000 ft	1000 Cft	97028.3			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
7	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	104.0			
ii. Data Board:						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	24.5			
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.5			
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.0			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.7			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.7			
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.7			
8	Writing letter or figures per letter per inch height	1 No	500.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.3			
iii. RD Marks:						
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	22.4			
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	51.1			
3	Carriage of consignment job upto 5 KMs Average	1 No	13.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	13.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	45.5			
6	Writing letter or firgures per letter per inch height (three figure each side).	1 No	130.0			
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	19.7			
				Total Cost		
iv. Water Course						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	12395.4			
2	Extra for slush or Daldal including dewatering.	1000 Cft	12395.4			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	1410.7			
	b) Nominal mix ratio 1:2:4	100 Cft	187.0			
4	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	35906.2			
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	7756.1			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	4212.6			
6	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	4687.7			
7	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	440.0			
8	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	1098.7			
9	Providing and placing poly sulphide joint sealent 1" wide and 1" deep.	1 Rft	380.0			
10	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	22000.0			
11	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	1354.3			
ii	PCC 1:2:4	100 Cft	164.6			
iii	RCC 1.1.5.3	100 Cft	10053.7			
				Total Cost		
v. Culverts						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	29518.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	768.0			
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	29348.9			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	6711.0			
	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	3072.0			
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	6537.3			
6	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 80mm dia (3 inch)	1 Rft	31.5			
7	Providing and laying sub-base course of stone product of approved quality and grade, including placing, mixing, spreading and compaction of sub-base material to required depth, camber, grade to achieve 100% maximum modified AASHO dry density, including carriage of all material to site of work except gravel and aggregate. Crushed stone aggregate.	100 Cft	300.0			
8	Providing and laying base course of crushed stone aggregate of approved quality and grade, and supply and spreading of stone screening, including placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHO dry density, including carriage of all materials to site of work except gravel and aggregate.	100 Cft	300.0			
9	Providing and laying road edging of 3" (75 mm) wide and	1 Rft	60.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
10	Providing surface treatment of roads,including supply of bitumen and bajri/crushed stone aggregate of approved quality,including cleaning of road surface,heating,spraying bitumen,spreading bajri and rollingetc.complete including carriageof all material stosite of work excep tbajri/crushed stone aggregate for which supplywithin 3miles(5.0km)isincluded in the rate.					
a	1st coat 35 lbs. bitumen, and 4 Cft. bajri of nominal size 1" (25 mm) per 100 sq. feet or 1.72 Kg bitumen and 0.017 cu.metre bajri per square metre..	100 Sft	600.0			
b	2nd coat 18 lbs. bitumen, and 2 Cft. bajri of nominal size ½" (13 mm) per %sft or 1.23 Kg bitumen and 0.008 cu. metre bajri per sq.metre.	100 Sft	600.0			
c	3rd coat 14 lbs. bitumen, and 1.5 Cft. bajri of nominal size ¼" (6 mm) per %sft or 0.69 Kg bitumen and 0.005 cubic metre bajri per sq.metre.	100 Sft	600.0			
11	Dismantling and removing road pavement, etc.,including screening and stacking of byproducts upto one chain lead (30 metre).	100 Cft	600.0			
12	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	4000.0			
13	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	30880.0			
14	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	737.3			
ii	RCC 1:1.5:3	100 Cft	8217.7			
iii	Base	100 Cft	366.0			
iii	T.S.T	100 Cft	45.0			
				Total Cost		
vii. Pump House No: 5 (D-2 Drain at RD 0+100)						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	25000.8			
2	Extra for slush or Daldal including dewatering.	1000 Cft	25000.8			
	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
3	a) Nominal mix ratio 1:4:8	100 Cft	733.7			
4	b) Nominal mix ratio 1:2:4	100 Cft	432.5			
5	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars).Deformed Bars (Grade 60)	100 Kg	40723.1			
	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
6	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	5753.3			
7	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	3296.2			
8	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	3466.0			
9	Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sand blinded.	100 Sft	648.8			
10	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	648.8			
11	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	46.0			
12	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	4.0			
13	Making top khurra on roof 2' x 2' x 6".	1 No	4.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
14	Providing and fixing windows consisting of M.S. box section frame 2"x1½", (50x40mm) leaves frame 1½"x1" (40x25mm) box section frame for glazing 3/8"x3/8" (10x10mm) using 16 SWG sheet 'U' shaped rubber supported with 1"x1/8" (25x3mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section ½"x½" (13x13mm) of 16 SWG for fixing 24 SWG wire gauze on outer side by means of ¾"x1/8" (20x3mm) M.S. flat and screws including grill of M.S. flat ½"x1/8" (13x3mm) or ¼"x¼" (6x6mm) square bar with independent frame of ½"x½" (13x13mm) box section of 16 SWG i/c all C.P. fitting and painting 3 coats complete in all respect.	1 Sft	271.9			
15	Making and fixing steel grated door with 1/16" thick 1.5mm) sheeting, including angle iron frame 2"x2"x3/8" (50x50x10 mm) and ¾" (20 mm) square bars 4" (100 mm)	1 Sft	176.0			
16	Distempering:- 2 coats	100 Sft	2528.6			
17	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	2362.3			
18	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	168.0			
19	Providing and fixing 1½"x1¼"x3/16" (31x31x5 mm) angle" iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	1 No	28.0			
21	Providing and fixing trash rack as per drawing	1 Sft	184.0			
22	Providing and laying Tuff Pavers, having 7000PSI ,crushing strength of approved manufa cturer, over 2"to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope . complete in all respect. (50% Grey / 50% Coloured) 60-mm thick	1 Sft	1417.7			
23	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	272.5			
24	1½"(40 mm) thick mosaic flooring, consisting of ½ " mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1"(25 mm) thick floor of 1:2:4 cement concrete, including rubbing and polishing complete with finishing :-using grey cement	100 Sft	648.8			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
25	Mosaic dado or skirting with one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1/2"(13 mm) thick cement plaster 1:3, including rubbing and polishing, complete with finishing:(a) using grey cement: i) 1/2"(13 mm) thick	100 Sft	53.4			
26	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels(a) Size 1 1/2" x 3/8" (40 x 10 mm)	1 Rft	389.8			
27	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	173.3			
28	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.					
	a) 20mm (3/4") i/d.	1 Rft	100.0			
	b) 25 mm (1") i/d	1 Rft	100.0			
29	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated.					
	a) 3/0.74mm (3/0.029").	1 Rft	250.0			
	b) 7/0.74mm (7/0.029").	1 Rft	200.0			
30	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.					
	b) 17.5 x 10 cm (7" x 4").	1 Each	3.0			
31	Supply and erection of switches 5 amp. Piano Type.	1 Each	20.0			
32	Supply and erection of backlite button holder shade, large size.	1 Each	5.0			
33	Supply and erection of ceiling rose, bakelite.	1 Each	5.0			
34	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screws,necessary wire completb) Double Pole(iii) 6-63 Amp (10 KA)	1 No	1.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
35	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screwes,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	2.0			
36	Providing and fixing Pakistan Energy Label NEECA approved Copper winded wall bracket Fan i/c the cost of necessary cable and hardware for connection as approved and directed by Engineer Incharge.ii) 24" Sweep dia	1 Each	4.0			
37	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	5.0			
38	<u>Lining Portion</u> Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	10698.5			
39	Compaction of earth work with power Road Roller, i.c ploughing mixing, moistening earth to optimum moisture content in layer etc; complete 90 % maximum modified AASHO dry denisty	1000 Cft	10698.5			
40	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed off undressed within 50 ft. (15 m) lead:- ordinary Soil	1000 Cft	4319.9			
	Cement plaster 1.5" (40 mm) thick ratio 1:6:-					
41	a) In bed	100 Sft	700.0			
42	b) On slope	100 Sft	1168.0			
	Cement concrete lining, using washed screened and graded stone aggregate:-					
43	a) In bed, ratio 1:2:4	100 Cft	239.8			
44	b) On slope, ratio 1:2:4	100 Cft	400.0			
45	Providing and placing cement, sand and bituminous joint sealant in ratio 1:2:3, 1/2" wide, 1" deep.	1 Rft	186.8			
46	Bitumen coating to plastered or cement concrete surface:- 10 lbs. per 100 Sft.	100 Sft	93.4			
47	<u>Stone Pitching Work</u> Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000 Cft	6208.7			
48	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	6208.7			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
49	Formation dressing and preparing subgrade, on slope	100 Sft	2589.9			
50	Formation dressing and preparing subgrade, in bed.	100 Sft	524.7			
51	Providing & laying graded bajri 1/8" to 1/2" gauge on slope (including carriage).	100 Cft	854.7			
52	Providing & laying graded bajri 1/2" to 2" gauge on slope (including carriage).	100 Cft	854.7			
53	Providing & laying graded bajri 1/8" to 1/2" gauge on level (including carriage).	100 Cft	173.1			
54	Providing & laying graded bajri 1/2" to 2" gauge on level (including carriage).	100 Cft	173.1			
55	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	2590.0			
56	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	173.1			
57	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 275Km.(From Sakhi Sarwar)	100 Cft	20947.2			
				Total Cost		
viii. Inlets						
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil. By Manual	1000 Cft	12209.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	1730.9			
	b) Nominal mix ratio 1:2:4	100 Cft	180.4			
3	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	2798.9			
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	2314.1			
	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	796.5			
5	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	9331.9			
6	Providing and laying dry, hand packed stone apron as per drawing	100 Cft	2649.9			
14	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	4720.0			
15	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	1661.6			
i	PCC 1:2:4	100 Cft	158.7			
ii	RCC 1:1.5:3	100 Cft	2612.9			
iii	Dry Hand Pack Stone	100 Cft	3577.4			
				Total Cost		
10. D-3 Drain (RD 0+000 to 12+524)						
i. Earthwork						
1	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed off and dressed within 50 ft. (15 m) lead:- (In Banks)	1000 Cft	1671902.1			
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	1638852.1			
3	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft.					
	a) 500 ft	1000 Cft	10467.5			
	b) 750 ft	1000 Cft	23965.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
	c) 1000 ft	1000 Cft	5747.5			
4	Borrowpit excavation undressed lead upto 100 ft (30 metre) in a) ordinary soil with	1000 Cft				
	a) 1 mile	1000 Cft	159193.8			
7	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	130.0			
ii. Data Board:						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	24.5			
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.5			
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.0			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.7			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.7			
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.7			
8	Writing letter or figures per letter per inch height	1 No	500.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
	DPC	100 Cft	4.3			
iii. RD Marks:						
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	22.4			
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	51.1			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
3	Carriage of consignment job upto 5 KMs Average	1 No	13.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	13.0			
5	Preparing surface and painting with emulation paint 3 coat.	100 Sft	45.5			
6	Writing letter or firgures per letter per inch height (three figure each side).	1 No	130.0			
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	19.7			
				Total Cost		
iv. Water Course						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	15395.3			
2	Extra for slush or Daldal including dewatering.	1000 Cft	15395.3			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	1785.0			
	b) Nominal mix ratio 1:2:4	100 Cft	238.0			
4	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	45010.3			
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	9694.2			
	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	5309.2			
6	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	5822.7			
7	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	560.0			
8	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	1373.8			
9	Providing and placing poly sulphide joint sealent 1" wide and 1" deep.	1 Rft	470.0			
10	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	28000.0			
11	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	1713.6			
ii	PCC 1:2:4	100 Cft	209.4			
iii	RCC 1.1.5.3	100 Cft	12602.9			
				Total Cost:		
v. Culverts						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	21204.3			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	564.5			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	22179.1			
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	5135.0			
	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	2258.0			
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	4909.3			
6	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 80mm dia (3 inch)	1 Rft	22.5			
7	Providing and laying sub-base course of stone product of approved quality and grade, including placing, mixing, spreading and compaction of sub-base material to required depth, camber, grade to achieve 100% maximum modified AASHO dry density, including carriage of all material to site of work except gravel and aggregate. Crushed stone aggregate.	100 Cft	350.0			
8	Providing and laying base course of crushed stone aggregate of approved quality and grade, and supply and spreading of stone screening, including placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHO dry density, including carriage of all materials to site of work except gravel and aggregate.	100 Cft	350.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
9	Providing and laying road edging of 3" (75 mm) wide and	1 Rft	100.0			
10	Providing surface treatment of roads,including supply of bitumen and bajri/crushed stone aggregate of approved quality,including cleaning of road surface,heating,spraying bitumen,spreading bajri and rollingetc.complete including carriageof all material stosite of work excep tbajjri/crushed stone aggregate for which supplywithin 3miles(5.0km)isincluded in the rate.					
a	1st coat 35 lbs. bitumen, and 4 Cft. bajri of nominal size 1" (25 mm) per 100 sq. feet or 1.72 Kg bitumen and 0.017 cu.metre bajri per square metre..	100 Sft	700.0			
b	2nd coat 18 lbs. bitumen, and 2 Cft. bajri of nominal size ½" (13 mm) per %sft or 1.23 Kg bitumen and 0.008 cu. metre bajri per sq.metre.	100 Sft	700.0			
c	3rd coat 14 lbs. bitumen, and 1.5 Cft. bajri of nominal size ¼" (6 mm) per %sft or 0.69 Kg bitumen and 0.005 cubic metre bajjri per sq.metre.	100 Sft	700.0			
11	Dismantling and removing road pavement, etc.,including screening and stacking of byproducts upto one chain lead (30 metre).	100 Cft	600.0			
12	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	6400.0			
13	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	24812.8			
14	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	541.9			
ii	RCC 1:1.5:3	100 Cft	6210.2			
iii	Base	100 Cft	427.0			
iii	T.S.T	100 Cft	52.5			
				Total Cost		
vi. Pump House No: 6 (D-3 Drain at RD 0+100)						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	21403.8			
2	Extra for slush or Daldal including dewatering.	1000 Cft	21403.8			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
3	a) Nominal mix ratio 1:4:8	100 Cft	736.1			
4	b) Nominal mix ratio 1:2:4	100 Cft	432.5			
5	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars).Deformed Bars (Grade 60)	100 Kg	40760.5			
	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
6	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	5794.5			
7	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	3263.4			
8	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	3489.5			
9	Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sand blinded.	100 Sft	648.8			
10	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	648.8			
11	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with `B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Sft	46.0			
12	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d	1 No	4.0			
13	Making top khurra on roof 2' x 2' x 6".	1 No	4.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
14	Providing and fixing windows consisting of M.S. box section frame 2"x1½", (50x40mm) leaves frame 1½"x1" (40x25mm) box section frame for glazing 3/8"x3/8" (10x10mm) using 16 SWG sheet 'U' shaped rubber supported with 1"x1/8" (25x3mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section ½"x½" (13x13mm) of 16 SWG for fixing 24 SWG wire gauze on outer side by means of ¾"x1/8" (20x3mm) M.S. flat and screws including grill of M.S. flat ½"x1/8" (13x3mm) or ¼"x¼" (6x6mm) square bar with independent frame of ½"x½" (13x13mm) box section of 16 SWG i/c all C.P. fitting and painting 3 coats complete in all respect.	1 Sft	271.9			
15	Making and fixing steel grated door with 1/16" thick 1.5mm) sheeting, including angle iron frame 2"x2"x3/8" (50x50x10 mm) and ¾" (20 mm) square bars 4" (100 mm)	1 Sft	176.0			
16	Distempering:- 2 coats	100 Sft	2528.6			
17	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	2362.3			
18	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	168.0			
19	Providing and fixing 1¼x1¼"x3/16" (31x31x5 mm) angle" iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	1 No	28.0			
21	Providing and fixing trash rack as per drawing	1 Sft	184.0			
22	Providing and laying Tuff Pavers, having 7000PSI ,crushing strength of approved manufa cturer, over 2"to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope . complete in all respect. (50% Grey / 50% Coloured) 60-mm thick	1 Sft	1417.7			
23	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	272.5			
24	1½"(40 mm) thick mosaic flooring, consisting of ½ " mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1"(25 mm) thick floor of 1:2:4 cement concrete, including rubbing and polishing complete with finishing :-using grey cement	100 Sft	648.8			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
25	Mosaic dado or skirting with one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over ½"(13 mm) thick cement plaster 1:3, including rubbing and polishing, complete with finishing:(a) using grey cement: i) 1/2"(13 mm) thick	100 Sft	53.4			
26	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels(a) Size 1½" x 3/8" (40 x 10 mm)	1 Rft	389.8			
27	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	176.6			
28	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.					
	a) 20mm (3/4") i/d.	1 Rft	100.0			
	b) 25 mm (1") i/d	1 Rft	100.0			
29	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated.					
	a) 3/0.74mm (3/0.029").	1 Rft	250.0			
	b) 7/0.74mm (7/0.029").	1 Rft	200.0			
30	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.					
	b) 17.5 x 10 cm (7" x 4").	1 Each	3.0			
31	Supply and erection of switches 5 amp. Piano Type.	1 Each	20.0			
32	Supply and erection of backlite button holder shade, large size.	1 Each	5.0			
33	Supply and erection of ceiling rose, bakelite.	1 Each	5.0			
34	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screws,necessary wire completb) Double Pole(iii) 6-63 Amp (10 KA)	1 No	1.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
35	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screwes,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	2.0			
36	Providing and fixing Pakistan Energy Label NEECA approved Copper winded wall bracket Fan i/c the cost of necessary cable and hardware for connection as approved and directed by Engineer Incharge.ii) 24" Sweep dia	1 Each	4.0			
37	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	5.0			
38	<u>Lining Portion</u> Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	14034.9			
39	Compaction of earth work with power Road Roller, i.c ploughing mixing, moistening earth to optimum moisture content in layer etc; complete 90 % maximum modified AASHO dry denisty	1000 Cft	14034.9			
40	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed off undressed within 50 ft. (15 m) lead:- ordinary Soil	1000 Cft	4319.9			
	Cement plaster 1.5" (40 mm) thick ratio 1:6:-					
41	a) In bed	100 Cft	700.0			
42	b) On slope	100 Cft	1168.0			
	Cement concrete lining, using washed screened and graded stone aggregate:-					
43	a) In bed, ratio 1:2:4	100 Cft	239.8			
44	b) On slope, ratio 1:2:4	100 Cft	400.0			
45	Providing and placing cement, sand and bituminous joint sealant in ratio 1:2:3, 1/2" wide, 1" deep.	1 Rft	186.8			
46	Bitumen coating to plastered or cement concrete surface:- 10 lbs. per 100 Sft.	100 Sft	93.4			
47	<u>Stone Pitching Work</u> Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000 Cft	6208.7			
48	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	6208.7			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
49	Formation dressing and preparing subgrade, on slope	100 Sft	3457.1			
50	Formation dressing and preparing subgrade, in bed.	100 Sft	524.7			
51	Providing & laying graded bajri ⅛" to ½"gauge on slope (including carriage).	100 Cft	1140.9			
52	Providing & laying graded bajri ½" to 2" gauge on slope (including carriage).	100 Cft	1140.9			
53	Providing & laying graded bajri ⅛" to ½"gauge on level (including carriage).	100 Cft	173.1			
54	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	173.1			
55	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	3457.3			
56	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	173.1			
57	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 275Km.(From Sakhi Sarwar)	100 Cft	21997.2			
				Total Cost		
vii. Inlets						
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m)and lift upto 5' (1.5 m) (b) in ordinary soil. By Manual	1000 Cft	11890.3			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	1730.9			
	b) Nominal mix ratio 1:2:4	100 Cft	180.4			
3	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	2798.9			
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	2314.1			
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	796.5			
5	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	9331.9			
6	Providing and laying dry, hand packed stone apron as per drawing	100 Cft	2331.2			
14	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	4720.0			
15	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	1661.6			
i	PCC 1:2:4	100 Cft	158.7			
ii	RCC 1:1.5:3	100 Cft	2612.9			
iii	Dry Hand Pack Stone	100 Cft	3147.2			
				Total Cost		
11. 1-L of D-1 Drain (RD 0+000 to 2+697)						
i. Earthwork						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, dalad and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	307260.4			
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	392780.1			
3	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft. c) 1000 ft	1000 Cft	11732.8			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
3	Borrowpit excavation undressed lead upto 100 ft (30 metre) in a) ordinary soil with a) 1000 ft	1000 Cft 1000 Cft	97969.5			
4	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	30.0			
ii. Data Board:						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	24.5			
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.5			
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.0			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.7			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.7			
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.7			
8	Writing letter or figures per letter per inch height	1 No	500.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
	DPC	100 Cft	4.3			
iii. RD Marks:						
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	5.2			
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	11.8			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
3	Carriage of consignment job upto 5 KMs Average	1 No	3.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	3.0			
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	10.5			
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	30.0			
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	4.5			
Total Cost						
iv. Water Course						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	1949.3			
2	Extra for slush or Daldal including dewatering.	1000 Cft	1949.3			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	458.8			
	b) Nominal mix ratio 1:2:4	100 Cft	68.0			
4	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	9117.5			
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	1761.1			
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	1278.1			
6	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	986.2			
7	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	160.0			
8	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	213.6			
9	Providing and placing poly sulphide joint sealent 1" wide and 1" deep.	1 Rft	90.0			
10	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	8000.0			
11	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	440.4			
ii	PCC 1:2:4	100 Cft	59.8			
iii	RCC 1.1.5.3	100 Cft	2552.9			
				Total Cost:		
v. Culverts						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	11161.2			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	252.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	10673.3			
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	2549.8			
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	1008.0			
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	2884.8			
6	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 80mm dia (3 inch)	1 Rft	13.5			
7	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	11520.0			
18	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	241.9			
ii	RCC 1:1.5:3	100 Cft	2988.5			
				Total Cost		
vi. Inlets						

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil. By Manual	1000 Cft	4728.7			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	695.1			
	b) Nominal mix ratio 1:2:4	100 Cft	72.1			
3	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	1119.6			
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	938.3			
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	324.0			
5	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	3786.8			
6	Providing and laying dry, hand packed stone apron as per drawing	100 Cft	881.6			
7	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	1920.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
8	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	667.3			
i	PCC 1:2:4	100 Cft	63.5			
ii	RCC 1:1.5:3	100 Cft	1060.3			
iii	Dry Hand Pack Stone	100 Cft	1190.2			
				Total Cost		
vii. Stone Pitching						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	148.5			
2	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons.	100 Cft	148.5			
3	Formation dressing and preparing subgrade, on slope	100 Sft	422.7			
4	Formation dressing and preparing subgrade, in bed.	100 Sft	126.0			
5	Providing and laying graded bajri 1/8" to 1/2" size on slope.	100 Cft	139.5			
6	Providing and laying graded bajri 1/2" to 2" size on slope.	100 Cft	139.5			
7	Providing and laying graded bajri 1/8" to 1/2" size on level.	100 Cft	41.6			
8	Providing and laying graded bajri 1/2" to 2" size on level.	100 Cft	41.6			
9	Providing and laying stone for top layer only, on slope.	100 Cft	422.7			
10	Providing and laying stone for top layer only, on Level	100 Cft	126.0			
11	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc or 150 Cft of timber by truck or by any other means owned by the contractor, lead 275 Km.	100 Cft	859.0			
				Total Cost		
viii. Tube Well room						
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m)and lift upto 5' (1.5 m) (b) in ordinary soil.1)By Manual	1000 Cft	544.9			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextaror equivalent@specified suspension concentrate (SC), MixingAbility-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for10-years complete in all respect.as approved by the Engineer Incharge.	1 Sft	508.5			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	105.6			
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	315.0			
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythenesheet 500 gauge 1½" thick (40 mm).	100 Sft	64.5			
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	120.0			
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	150.0			
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	290.9			
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:2:4)	1 Cft	154.2			
10	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	18.4			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
11	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	1035.4			
12	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	32.0			
13	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	40.0			
14	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	49.0			
15	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	95.6			
16	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	99.6			
17	Supplying and filling sand under floor or plugging in wells.	100 Cft	40.9			
18	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	48.9			
19	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	b) Nominal mix ratio 1:2:4	100 Cft	45.9			
20	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	568.3			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
21	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	114.5			
22	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	489.9			
23	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	13.0			
24	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d	1 No	2.0			
25	Making top khurra on roof 2' x 2' x 6".	1 No	1.0			
26	Distempering:- 3 coat	100 Sft	510.3			
27	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	172.6			
28	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	89.0			
29	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, rebitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	335.0			
30	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.					
	a) 20mm (3/4") i/d.	1 Rft	60.0			
	b) 25 mm (1") i/d	1 Rft	30.0			
	c) 50 mm (2") i/d	1 Rft	15.0			
31	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pipe/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only)					
	(a) 250/440 volts, P.V.C. insulated.					
	a) 3/0.74mm (3/0.029").	1 Rft	180.0			
	b) 7/0.74mm (7/0.029").	1 Rft	60.0			
32	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only) (a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).	1 Rft	40.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
33	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.					
	a) 10 x 10 cm (4" x 4").	1 Each	1.0			
	b) 17.5 x 10 cm (7" x 4").	1 Each	1.0			
	c) 22.5 x 10 cm (9" x 4").	1 Each	1.0			
34	Supply and erection of switches 5 amp. Piano Type.	1 Each	20.0			
35	Supply and erection of ceiling rose, bakelite.	1 Each	4.0			
36	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	2.0			
37	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	1.0			
38	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessed/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	1.0			
39	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screwes,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	6.0			
40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaid DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole (ii) 15-100 Amp (10 KA,15KA)	1 No	2.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
41	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker) of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (with fixed Thermal-Magnetic Trip) in pre-laid DB and Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the Engineer in charge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	1.0			
42	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii) single rod (40 watts) with one choke and one starter.	1 No	3.0			
43	Supply and erection of bakelite button holder shade, large size	1 No	3.0			
44	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	101.4			
ii	PCC 1:2:4	100 Cft	40.4			
iii	RCC 1:2:4	100 Cft	151.9			
iv	DPC 1:2:4	100 Cft	7.1			
				Total Cost:		

12. Electrical Work (All New drainage system including Jarewala Drain)

1. Installation of Complete Electricity HT/LT Network Sub Stations for Tubewells and Pump Stations at D1 Main Drain System, Jarewala Drain System and Manthar Drain.

1.1 Cost of 11 KV Line						
1	HT Spun Pole 45'	No	25.0			
2	HT S/STRUCTURE Pole 36'	No	700.0			
3	Earthing	No	700.0			
4	Steel -X-ARMS	No	1000.0			
5	11-KV Disc: Insulator	No	1500.0			
6	Eye Nut/Ahchore Shackle/D.End Clump	No	1200.0			
7	11KV Pin Insulator with Pins	No	250.0			
8	D-Shackle + Spool Insulator	No	1000.0			
9	DA Bolts	No	700.0			
10	Nuts & Bolts 14"	No	500.0			
11	Nuts & Bolts 12"	No	500.0			
12	Nuts & Bolts 02"	No	200.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
13	Stay Rod + stay strips Complete	No	150.0			
14	Stay Wire	m	1200.0			
15	ACSR Rabbit Conductor	No	55000.0			
				Total:		
1.2 Cost of Sub Station						
1	Transformer 400-KVA	No	2.0			
2	Transformer 100-KVA	No	5.0			
3	Transformer 50-KVA	No	5.0			
4	Transformer 25-KVA	No	40.0			
5	Earthing	No	120.0			
6	Steel -X-ARMS	No	700.0			
7	11KV Pin Insulator with Pins	No	2100.0			
8	Plate form D/Edge	No	60.0			
9	ACSR Rabbit Conductor	No	3200.0			
10	Nuts & Bolts	No	500.0			
11	D-Fues Fitting Set	No	150.0			
12	Steel Crass arm for D fuse Mounting	No	50.0			
13	LT Capacitor	No	50.0			
14	LT Spun Pole 31'	No	500.0			
15	street light pole bracket 30 mm (1¼") G.I. pipe 2 metre long, complete with 2 No. pole clamp. (Ch-24) [Pump station + Tubewell Rooms)	No	200.0			
16	Supply and erection of pole mounted street light, holders, shade and glass, etc., for fitting 125/250 watts mercury vapour lamp (excluding cost of lamps): ii) Philips design (Ch 24) [Pump station + Tubewell Rooms)	No	200.0			
17	Supply and fitting of mercury vapour lamp, complete with choke set ii) 250 watt lamp (Ch 24) [Pump station + Tubewell Rooms)	No	200.0			
				Total:		
1.3 Cost of Metering						
1	PVC 4/C Cable 19.083 (70mm Armoured	No	5000.0			
2	AMR METER HT/LT Type (bi-directional)	No	50.0			
3	ATB A-Type 100/5	No	10.0			
4	Earthing	No	20.0			
5	CTs 100/5 Amp	No	80.0			
				Total:		
1.4 Installation Charges 20%						
1	(A) Cost of 11 KV Line material	No	1.0			
2	(B) Cost of Sub Station material	No	1.0			
3	(c.) Cost of service and Metering material	No	1.0			
				Total:		
1.5 Earthing Charges						

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
1	Earthing Pit & Material will be provided by consumer	No	1.0			
				Total:		
1.6 Foundation / Contractor Charges						
1	Contractor Charges/ Foundation Charges 60000 x 700	No	1.0			
				Total:		
1.7 Less Charges of Return to store (Healthy) Material						
1	Feeder Rehabilitation Charges / Security	No	1.0			
				Total:		
				Total:		
2. Installation of Complete Electricity HT/LT Network Sub Stations for Tubewells and Pump Stations at D2 Drain PS-5, D3 Drain PS-6, PS-3 and Manthar Drain						
2.1 NEAR SCARP T/WELL NO.M-29 IN RESPECT OF MEPCO DIVISION						
1	25 KVATRANSFORMER	Ea	1.0			
2	S/STRUCTURE PLATFORM	Ea	1.0			
3	HT PCC POLE	Ea	3.0			
4	Steel -X-ARMS	Ea	9.0			
5	D-Fuse Fitting	Ea	3.0			
6	ACSR RABBIT	M	930.0			
7	AMR METER	Ea	1.0			
8	Pin Insulator with Pins	Ea	9.0			
9	11 KV Disc	Ea	6.0			
10	Stay Rods	Ea	4.0			
11	Stay Wire	kg	110.0			
12	Earth Rods	Ea	7.0			
13	PVC 4/C 19/.052	M	30.0			
14	Nuts & Bolts	L/S	1.0			
		Total:				
		20% Installation Charges				
		Civil Work Charges (Contactor Charges)	Ea	3.0		
		SECURITY				
				Total:		
2.2 NEAR SCARP T/WELL NO.M-26 IN RESPECT OF MEPCO DIVISION						
1	25 KVATRANSFORMER	Ea	1.0			
2	S/STRUCTURE PLATFORM	Ea	1.0			
3	HT PCC POLE	Ea	1.0			
4	Steel -X-ARMS	Ea	3.0			
5	D-Fuse Fitting	Ea	3.0			
6	ACSR RABBIT	M	30.0			
7	AMR METER	Ea	1.0			
8	Pin Insulator with Pins	Ea	6.0			
9	Stay Wire	kg	30.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
10	Earth Rods	Ea	3.0			
11	PVC 4/C 19/.052	M	30.0			
12	Nuts & Bolts	L/S	1.0			
	Total:					
	20% Installation Charges					
	Civil Work Charges (Contactor Charges)	Ea	1.0			
	SECURITY					
	Total:					
2.3 NEAR SCARP T/WELL NO.M-128 IN RESPECT OF MEPCO DIVISION						
1	25 KVATransformer	Ea	1.0			
2	S/STRUCTURE PLATFORM	Ea	1.0			
3	HT PCC POLE	Ea	1.0			
4	Steel -X-ARMS	Ea	6.0			
5	D-Fuse Fitting	Ea	3.0			
6	ACSR RABBIT	M	380.0			
7	AMR METER	Ea	1.0			
8	Pin Insulator with Pins	Ea	6.0			
9	11 KV Disc	Ea	6.0			
10	Stay Rods	Ea	2.0			
11	Stay Wire	kg	60.0			
12	Earth Rods	Ea	4.0			
13	PVC 4/C 19/.052	M	30.0			
14	Nuts & Bolts	L/S	1.0			
	Total:					
	20% Installation Charges					
	Civil Work Charges (Contactor Charges)	Ea	1.0			
	SECURITY					
	Total:					
2.4 NEAR SCARP T/WELL NO.M-32 IN RESPECT OF MEPCO DIVISION						
1	25 KVATransformer	Ea	1.0			
2	S/STRUCTURE PLATFORM	Ea	1.0			
3	HT PCC POLE	Ea	4.0			
4	Steel -X-ARMS	Ea	10.0			
5	D-Fuse Fitting	Ea	3.0			
6	ACSR RABBIT	M	1130.0			
7	AMR METER	Ea	1.0			
8	Pin Insulator with Pins	Ea	12.0			
9	11 KV Disc	Ea	6.0			
10	Stay Rods	Ea	4.0			
11	Stay Wire	kg	120.0			
12	Earth Rods	Ea	8.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
13	PVC 4/C 19/.052	M	30.0			
14	Nuts & Bolts	L/S	1.0			
	Total:					
	20% Installation Charges					
	Civil Work Charges (Contactor Charges)	Ea	4.0			
	SECURITY					
	Total:					
2.5 NEAR SCARP T/WELL NO.M-26 IN RESPECT OF MEPCO DIVISION						
1	200 KVA TRANSFORMER	Ea	1.0			
2	D/STRUCTURE PLATFORM	Ea	1.0			
3	LT PCC POLE	Ea	1.0			
4	Steel -X-ARMS	Ea	4.0			
5	D-Fuse Fitting	Ea	3.0			
6	ACSR RABBIT	M	50.0			
7	AMR METER	Ea	1.0			
8	Pin Insulator with Pins	Ea	6.0			
9	ATB A TYPE	Ea	2.0			
10	CTS 100/5	Ea	8.0			
11	Stay Wire	kg	40.0			
12	Earth Rods	Ea	4.0			
13	PVC 4/C 19/.083	M	100.0			
14	Nuts & Bolts	L/S	1.0			
	Total:					
	20% Installation Charges					
	Civil Work Charges (Contactor Charges)	Ea	1.0			
	SECURITY					
	Total:					
2.6 NEAR SCARP T/WELL NO.M-128 IN RESPECT OF MEPCO DIVISION						
1	25 KVATransformer	Ea	1.0			
2	S/STRUCTURE PLATFORM	Ea	1.0			
3	HT PCC POLE	Ea	1.0			
4	Steel -X-ARMS	Ea	6.0			
5	D-Fuse Fitting	Ea	3.0			
6	ACSR RABBIT	M	380.0			
7	AMR METER	Ea	1.0			
8	Pin Insulator with Pins	Ea	6.0			
9	11 KV Disc	Ea	6.0			
10	Stay Rods	Ea	2.0			
11	Stay Wire	kg	60.0			
12	Earth Rods	Ea	4.0			
13	PVC 4/C 19/.052	M	100.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
14	Nuts & Bolts	L/S	1.0			
	Total:					
	20% Installation Charges					
	Civil Work Charges (Contactor Charges)	Ea	1.0			
	SECURITY					
	Total:					
2.7 NEAR SCARP T/WELL NO.M-19 IN RESPECT OF MEPCO DIVISION						
1	200 KVA TRANSFORMER	Ea	1.0			
2	D/STRUCTURE PLATEFORM	Ea	1.0			
3	HT PCC POLE	Ea	1.0			
4	LT PCC POLE	Ea	1.0			
5	Steel -X-ARMS	Ea	4.0			
6	D-Fuse Fitting	Ea	3.0			
7	ACSR RABBIT	M	50.0			
8	AMR METER	Ea	1.0			
9	Pin Insulator with Pins	Ea	6.0			
10	ATB A TYPE	Ea	2.0			
11	CTS 100/5	Ea	8.0			
12	Stay Wire	kg	40.0			
13	Earth Rods	Ea	4.0			
14	PVC 4/C 19/.083	M	200.0			
	Nuts & Bolts	L/S	1.0			
	Total:					
	20% Installation Charges					
	Civil Work Charges (Contactor Charges)	Ea	2.0			
	SECURITY					
	Total:					
2.8 NEAR SCARP T/WELL NO.M-34 IN RESPECT OF MEPCO DIVISION						
1	25 KVATransformer	Ea	1.0			
2	S/STRUCTURE PLATEFORM	Ea	1.0			
3	HT PCC POLE	Ea	1.0			
4	Steel -X-ARMS	Ea	6.0			
5	D-Fuse Fitting	Ea	3.0			
6	ACSR RABBIT	M	290.0			
7	AMR METER	Ea	1.0			
8	Pin Insulator with Pins	Ea	6.0			
9	11 KV Disc	Ea	6.0			
10	Stay Rods	Ea	2.0			
11	Stay Wire	kg	60.0			
12	Earth Rods	Ea	4.0			
13	PVC 4/C 19/.052	M	200.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
14	Nuts & Bolts	L/S	1.0			
	Total:					
	20% Installation Charges					
	Civil Work Charges (Contactor Charges)	Ea	1.0			
	SECURITY					
	Total:					
2.9 NEAR SCARP PUMPING STATION-3 IN RESPECT OF MEPCO DIVISION						
1	630 KVA TRANSFORMER	Ea	2.0			
2	D/STRUCTURE PLATFORM	Ea	5.0			
3	LT PCC POLE	Ea	25.0			
4	Steel -X-ARMS	Ea	12.0			
5	D-Fuse Fitting	Ea	9.0			
6	ACSR RABBIT	M	150.0			
7	AMR METER	Ea	1.0			
8	Pin Insulator with Pins	Ea	8.0			
9	ATB A TYPE	Ea	3.0			
10	CTS 100/5	Ea	12.0			
11	Stay Wire	kg	150.0			
12	Earth Rods	Ea	20.0			
13	PVC 4/C 19/.083	M	1000.0			
14	Nuts & Bolts	L/S	1.0			
	Total:					
	20% Installation Charges					
	Civil Work Charges (Contactor Charges)	Ea	1.0			
	SECURITY					
	Total:					
3. Security Fencing Barbed Wire at quarters and pumping stations						
1	Providing and fixing barbed wire fencing, with 4 horizontal and two cross wires, with R.C.C. 1:2:4 posts, 5.5'x6"x9" (1.68mx150mmx225 mm) at 8 ft. (2.45 m) center to center, reinforced with 4 No. 3/8" (10 mm) dia vertical bars and 1/8" (3 mm) dia stirrups 12" (300 mm) center to center, complete in all respects.	49390.0	100.0			
2	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m)and lift upto 5' (1.5 m) (b) in ordinary soil.	2063.0	1000.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	515.7	100.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	745.6	100.0			
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with 2 coats of bitumen: 1½" thick (40 mm).	427.5	100.0			
5	Pacca brick work other than building upto 10ft. (3 m) Ratio 1:4	1656.6	100.0			
6	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	6225.5	100.0			
7	Providing and fixing collapsible gate made of 2"x2"x¼" (50x50x6 mm) tee iron at top and bottom, channel iron verticals ¾"x¼"x¼"x1/8" (20x6x6x3 mm) at 3" (75 mm) to 5" (125 mm) centre to centre (approximate) and flat iron crosses 3"x3/16" (75x5 mm), and best quality rollers at bottom of 3" (75 mm) diameter including holdfasts, handles 12" (300 mm) long of ¾"x¼"x¼"x1/8" (20x6x6x3 mm) channel iron, locking arrangement inside and outside, painting 3 coats of black Japan enameled, complete in working order.	6650.0	1.0			
8	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 50mm i/d	14250.0	1.0			
9	Supply and erection of single core PVC insulated copper conductor cables, in prelaid PVC pipe/M.S. conduit/G.I pipe/wooden strip batten/wooden casing an capping/G.I. wire/trenches (rate for cables only):7/0.74 mm (7/0.029")	28500.0	1.0			
				Total:		
13. Installation of Tubewells (Mechanical)						
1	Providing installation, testing, and commissioning of a vertical deep well turbine tubewell pump with discharge 2 cusec against 70 ft head, including bowl assembly, vertical column pipe with shaft, motor, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical connections, cables and accessories from transformer to tubewell including earthing and protection devices, complete suction and delivery piping up to 25 ft outlet basin of approved material (MS/CI) with bends, flanges, valves, gaskets, supports and accessories, carrying out all works for energizing, testing, and full-load commissioning; pump casing in Gray Cast Iron EN-GJL-250, impeller in Stainless Steel grade 1.4408, column pipe coated internally and externally with epoxy paint, materials verified per EN 10204-3.1, minimum 80% efficiency per ISO 9906-1B; motor of reputed manufacturer, vertical solid shaft, IE3 efficiency class, 15 kW (20 HP, 1450 rpm), 4-pole, 3-phase, 50 Hz, 380/400 V, manufacturer to have in-house hydraulic and metallurgical testing facility, complete in all respects suitable for tubewell application. [including transportation and all overhead charges]	No	37.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
2	Direct Rotary / Reverse Rotary drilling of bore for tubewell in all type of soil except shingle gravel and rock. i). 15 " To 18" (500 to 650 mm)	Rft	8140.0			
3	Collection of lithological samples with sieve analysis at every 5 ft. interval or change of lithology whichever is earlier.	No.	1628.0			
4	Furnishing sample of water from bore hole.	Per Set of 2 bottles	37.0			
5	Providing, installations testing and commissioning of 16" dia fiberglass blind pump housing casing with 6mm wall thickness having quick lock mechanical key joints complete in all respect as per specification and approved by the Engineer.	Rft	2590.0			
6	Providing and installation of Fibre Glass reducer 16"x10" with wall thickness 5.5 mm. complete in all respect as per specification and approved by the Engineer.	Nos	74.0			
7	Providing and installing Fiberglass Reinforced Polypropelene (FRP) strainer of specifid wall thickness having slot size of 0.9 mm to 1.10 mm in Tubewell borehole i/c the cost of male/female coupling with Nylone Strip, studs complete in all respect as approved and directed by the Engineer Incharge vi) 10" inch dia (6.35 mm thickness	Rft	4440.0			
8	Proving and installation of fiberglass Blank blind casing pipe dia 10" with 5.5" wall thickness. complete in all respect as per specification and approved by the Engineer.	Rft	740.0			
9	Providing and installing Fiber glass Reinforced Polypropelene (FRP) bail plug of specified wall thickness having slot size of 0.9 mm to 1.10 mm in Tubewell bore hole i/c the cost of male / female coupling with Nylone Strip, studs complete in all respect as approved and directed by the Engineer Incharge.vi) 10"dia (6.35mm thickness)	Rft	370.0			
10	Providing and installation of centralizer complete in all respect as per specification and approved by the Engineer.	No.	148.0			
11	Shrouding with graded pea gravel 3/8" to 1/8" around tubewell casing in the bore hole.	Cft	6520.9			
12	Testing and Development of tubewell of size 6"(150 mm) and above continusly. ii) Above 1.5 cs Discharge	Hours	2664.0			
13	Supply and erection of copper conductor cables for service connection (rate for cable only), PVC insulated, PVC sheathed 4 core , 600/1100 volt non armoured cable. (7/0.064")	Rft	1850.0			
14	Excavation of trenches in all kinds of soil except cutting rock, for watersupply pipelines upto 5 ft. (1.5 m) depth from ground level, including trimming, dressing sides leveling the beds of trenches to correct grade and cutting pits for joints, etc. complete in all respects.	1000 Cft	118400.0			
15	Rehandling of earthwork lead upto a lead of 50 ft.	1000 Cft	118400.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
16	Providing,laying,testing and commissioning µPVC (Unplasticized Poly vinyl Chloride Pressure pipe of nominal diameter, conforming to PS-3051/BS-3505, Dadex/ Popular/ Beta or approved equivalent manufacturer,i/c the cost of solvent and specials complete as approved and directed by the Engineer Incharge. a)Class-D 12 inch	Lft	14800.0			
17	Providing,laying,testing and commissioning µPVC (Unplasticized Poly vinyl Chloride Pressure pipe of nominal diameter, conforming to PS-3051/BS-3505, Dadex/ Popular/ Beta or approved equivalent manufacturer,i/c the cost of solvent and specials complete as approved and directed by the Engineer Incharge. a)Class-D 3 inch	Lft	555.0			
				Total:		
14. Installation of Pumps, Motors and Allied accessories (Mechanical Works for Jarewala Drain) PS-7						
1	Providing installation, testing and commissioning of vertical tubular casing pump with ever cleaning blades having discharge capacity of 40 cusec against 16-25 ft head including pump, motor, bowl assembly, column set, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical cables, accessories and connections from transformer to pump including earthing and protection devices, complete suction piping inside the chamber (SS/MS/CI) and delivery piping up to the outlet basin (40–50 ft) of approved material (Fibre reinforced cement/upvc of suitable internal diameter size as approved by E-in-C) with all bends, flanges, valves, gaskets, supports and accessories, and carrying out all works necessary for energizing, testing and full-load commissioning of the complete pump set in all respects. . Pump shall have min. 84% efficiency which should be verified according to ISO 9906-1B standard. Material of pump casing shall be Gray cast iron JL-1040 having propeller (ever cleaning blades) in Stainless Steel grade 1.4408. Pump and column pipe shall be coated internally and externally with epoxy paint. Material of pump shall be verified according to material test certificate EN 10204-3.1. Motor shall be of reputed manufacturer having min. IE3 efficiency class. Vertical solid shaft. Rating of motor to be 110 KW (150HP, 450 rpm)/8 pole, 3 phase, 50 Hz, 380/400 Volts. . Manufacturer shall have its own testing facility to verify pumps hydraulic performance testing. Manufacturer shall have its own material testing lab to verify metallurgical testing. [including transportation and all overhead charges]	No.	8.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
2	Providing installation, testing and commissioning of horizontal centrifugal pump having discharge capacity of 10 cusec against 30 ft - 35 ft head including pump, motor, bowl assembly, column set, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical cables and connections from transformer to pump including earthing and protection devices, complete suction piping inside the chamber (SS/MS/CI) and delivery piping up to the outlet basin (40–50 ft) of approved material (Fibre reinforced cement/upvc of suitable internal diameter size as approved by E-in-C) with all bends, flanges, gaskets, supports and accessories, and carrying out all works necessary for energizing, testing and full-load commissioning of the complete pump set in all respects.. Pump shall have min. 81% efficiency which should be verified according to ISO 9906-1B standard. Material of pump casing shall be Gray cast iron EN-GJL-250 having impeller in Stainless Steel grade 1.4408. Pump shall be coated internally with epoxy paint. Material of pump shall be verified according to material test certificate EN 10204-3.1. Motor shall be of reputed manufacturer having min. IE3 efficiency class. Rating of motor to be 37 KW (50HP, 950 rpm)/6 pole, 3 phase, 50 Hz, 380/400 Volts. Manufacturer shall have its own testing facility to verify pumps hydraulic performance testing. Manufacturer shall have its own material testing lab to verify metallurgical testing. [including transportation and all overhead charges]	No.	1.0			
3	Providing, installation, testing and comissioning of 10 Ton and more capacity Gantry Craine, with girder bridge type arrangement, fitted with electric motor for its operation and mobility, electric wiring and fixing in position, complete in all respect.	No.	1.0			
				Total:		
15. Installation of Pumps, Motors and Allied accessories (Mechanical Works for D1,D2,D3 Drain) PS-4,5,6						
Installation of PUMPS AT D1 DRAIN (PS-4)						

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
1	Providing installation, testing and commissioning of horizontal centrifugal pump having discharge capacity of 10 cusec against 30 ft - 35 ft head including pump, motor, bowl assembly, column set, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical cables, accessories and connections from transformer to pump including earthing and protection devices, complete suction piping inside the chamber (SS/MS/CI) and delivery piping up to the outlet basin (40–50 ft) of approved material (Fibre-Glass/Fibre cement/upvc as approved by E-in-C) with all bends, flanges, valves, gaskets, supports and accessories, and carrying out all works necessary for energizing, testing and full-load commissioning of the complete pump set in all respects.. Pump shall have min. 81% efficiency which should be verified according to ISO 9906-1B standard. Material of pump casing shall be Gray cast iron EN-GJL-250 having impeller in Stainless Steel grade 1.4408. Pump shall be coated internally with epoxy paint. Material of pump shall be verified according to material test certificate EN 10204-3.1. Motor shall be of reputed manufacturer having min. IE3 efficiency class. Rating of motor to be 37 KW (50HP, 950 rpm) /6 pole, 3 phase, 50 Hz, 380/400 Volts. Manufacturer shall have its own testing facility to verify pumps hydraulic performance testing. Manufacturer shall have its own material testing lab to verify metallurgical testing. [including transportation and all overhead charges]	No.	3.0			
2	Providing installation, testing and commissioning of horizontal centrifugal pump having discharge capacity of 20 cusec against 30 ft - 35 ft head including pump, motor, bowl assembly, column set, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical cables, accessories and connections from transformer to pump including earthing and protection devices, complete suction piping inside the chamber (SS/MS/CI) and delivery piping up to the outlet basin (40 -- 50 ft) of approved material (Fibre reinforced cement/upvc of suitable internal diameter size as approved by E-in-C) with all bends, flanges, valves, gaskets, supports and accessories, and carrying out all works necessary for energizing, testing and full-load commissioning of the complete pump set in all respects.. Pump shall have min. 83% efficiency which should be verified according to ISO 9906-1B standard. Material of pump casing shall be Gray cast iron EN-GJL-250 having impeller in Stainless Steel grade 1.4408. Pump shall be coated internally with epoxy paint. Material of pump shall be verified according to material test certificate EN 10204-3.1. Motor shall be of reputed manufacturer having min. IE3 efficiency class. Rating of motor to be 75 KW (100HP, 950 rpm) /8 pole, 3 phase, 50 Hz, 380/400 Volts. Manufacturer shall have its own testing facility to verify pumps hydraulic performance testing. Manufacturer shall have its own material testing lab to verify metallurgical testing. [including transportation and all overhead charges]	No.	1.0			
3	Providing, installation, testing and comissioning of 5 Ton and more capacity Gantry Craine, with girder bridge type arrangement, fitted with electric motor for its operation and mobility, electric wiring and fixing in position, complete in all rspect.	No.	1.0			
INSTALLATION OF PUMPS AT D-2 DRAIN (PS-5)						

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
1	Providing installation, testing and commissioning of horizontal centrifugal pump having discharge capacity of 10 cusec against 30 ft - 35 ft head including pump, motor, bowl assembly, column set, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical cables, accessories and connections from transformer to pump including earthing and protection devices, complete suction piping inside the chamber (SS/MS/CI) and delivery piping up to the outlet basin (40–50 ft) of approved material (Fibre reinforced cement/upvc of suitable internal diameter size as approved by E-in-C) with all bends, flanges, valves, gaskets, supports and accessories, and carrying out all works necessary for energizing, testing and full-load commissioning of the complete pump set in all respects.. Pump shall have min. 81% efficiency which should be verified according to ISO 9906-1B standard. Material of pump casing shall be Gray cast iron EN-GJL-250 having impeller in Stainless Steel grade 1.4408. Pump shall be coated internally with epoxy paint. Material of pump shall be verified according to material test certificate EN 10204-3.1. Motor shall be of reputed manufacturer having min. IE3 efficiency class. Rating of motor to be 37 KW (50HP, 950 rpm) /6 pole, 3 phase, 50 Hz, 380/400 Volts. Manufacturer shall have its own testing facility to verify pumps hydraulic performance testing. Manufacturer shall have its own material testing lab to verify metallurgical testing. [including transportation and all overhead charges]	No.	2.0			
2	Providing, installation, testing and comissioning of 5 Ton capacity Gantry Craine, with girder bridge type arrangement, fitted with electric motor for its operation and mobility, electric wiring and fixing in position, complete in all rspect.	No.	1.0			
INSTALLATION OF PUMPS AT D-3 DRAIN (PS-6)						
1	Providing installation, testing and commissioning of horizontal centrifugal pump having discharge capacity of 10 cusec against 30 ft - 35 ft head including pump, motor, bowl assembly, column set, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical cables, accessories and connections from transformer to pump including earthing and protection devices, complete suction piping inside the chamber (SS/MS/CI) and delivery piping up to the outlet basin (40–50 ft) of approved material (Fibre reinforced cement/upvc of suitable internal diameter size as approved by E-in-C) with all bends, valves, flanges, gaskets, supports and accessories, and carrying out all works necessary for energizing, testing and full-load commissioning of the complete pump set in all respects.. Pump shall have min. 81% efficiency which should be verified according to ISO 9906-1B standard. Material of pump casing shall be Gray cast iron EN-GJL-250 having impeller in Stainless Steel grade 1.4408. Pump shall be coated internally with epoxy paint. Material of pump shall be verified according to material test certificate EN 10204-3.1. Motor shall be of reputed manufacturer having min. IE3 efficiency class. Rating of motor to be 37 KW (50HP, 950 rpm) /6 pole, 3 phase, 50 Hz, 380/400 Volts. Manufacturer shall have its own testing facility to verify pumps hydraulic performance testing. Manufacturer shall have its own material testing lab to verify metallurgical testing. [including transportation and all overhead charges]	No.	2.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
2	Providing, installation, testing and comissioning of 5 Ton capacity Gantry Craine, with girder bridge type arrangement, fitted with electric motor for its operation and mobility, electric wiring and fixing in position, complete in all rspect.	No.	1.0			
Total:						
16. Solarization of Pumps on proposed Pump Houses						
16.1 PS-4 of D1 main Drain						

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
	Providing installation, testing, and commissioning of a 53.5 kW Solar PV system capable of running a horizontal centrifugal pump with discharge 10 cusec against 30–35 ft head, pump minimum 81% efficiency, including Tier-1 Bloomberg-certified mono / bi-facial N-type solar panels (JINKO / LONGI / JA / Canadian / AKCome / TW / Trina, 700+ W/panel, 23.5% efficiency), solar pump inverter INVT suitably rated for system capacity, mounted on 12 ft high L2/L3/L4 galvanized steel structure (14 gauge) with complete mechanical and civil works, DC and AC cabling with XLPE/PVC insulated tin-coated copper wires (DC 1-core 6 mm, AC 4-core 6 mm, 25 mm PVC/XLPE), combiner boxes, AC & DC breakers, SPDs (A+ grade), all distribution/protection boxes (12"×18"×18" SWG or equivalent), PVC pipes, flexible pipes (1–1.5"), thimbles (O-type, U-type with shrouds), Rawl bolts, nuts and bolts, complete earthing system, lightning arrestor, all civil works, foundations, supports, electrical connections for net metering with meter, transportation of all materials from warehouse to site, testing, commissioning, and manufacturer-provided maintenance/after-sales service for 2 years, complete in all respects as directed by the Engineer-in-Charge.	No	3.0			
16.2 PS-4 of D1 main Drain						
	Providing installation, testing, and commissioning of a 107 kW Solar PV system for a horizontal centrifugal pump with discharge 20 cusec against 30 - 35 ft head , pump minimum 83% efficiency, including Tier-1 Bloomberg-certified mono/ bi-facial N-type solar panels (JINKO / LONGI / JA / Canadian / AKCome / TW / Trina, 700+ W/panel, 23.5% efficiency), solar pump inverter INVT suitably rated for system capacity, mounted on 12 ft high L2/L3/L4 galvanized steel structure (14 gauge) with complete mechanical and civil works, DC and AC cabling with XLPE/PVC insulated tin-coated copper wires (DC 1-core 6 mm, AC 4-core 6 mm, 25 mm PVC/XLPE), combiner boxes, AC & DC breakers, SPDs (A+ grade), all distribution/protection boxes (12"×18"×18" SWG or equivalent), PVC pipes, flexible pipes (1–1.5"), thimbles (O-type, U-type with shrouds), Rawl bolts, nuts and bolts, complete earthing system, lightning arrestor, all civil works, foundations, and supports, all electrical connections for net metering with meter, transportation of all materials from warehouse to site, testing, commissioning, and manufacturer-provided maintenance/after-sales service for up to 2 years, complete in all respects as directed by the Engineer-in-Charge.	No	1.0			
16.3 PS-5 of D2 Drain						

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
	Providing installation, testing, and commissioning of a 53.5 kW Solar PV system capable of running a horizontal centrifugal pump with discharge 10 cusec against 30–35 ft head, pump minimum 81% efficiency, including Tier-1 Bloomberg-certified mono / bi-facial N-type solar panels (JINKO / LONGI / JA / Canadian / AKCome / TW / Trina, 700+ W/panel, 23.5% efficiency), solar pump inverter INVT suitably rated for system capacity, mounted on 12 ft high L2/L3/L4 galvanized steel structure (14 gauge) with complete mechanical and civil works, DC and AC cabling with XLPE/PVC insulated tin-coated copper wires (DC 1-core 6 mm, AC 4-core 6 mm, 25 mm PVC/XLPE), combiner boxes, AC & DC breakers, SPDs (A+ grade), all distribution/protection boxes (12"×18"×18" SWG or equivalent), PVC pipes, flexible pipes (1–1.5"), thimbles (O-type, U-type with shrouds), Rawl bolts, nuts and bolts, complete earthing system, lightning arrestor, all civil works, foundations, supports, electrical connections for net metering with meter, transportation of all materials from warehouse to site, testing, commissioning, and manufacturer-provided maintenance/after-sales service for 2 years, complete in all respects as directed by the Engineer-in-Charge.	No	2.0			
	16.4 PS-6 of D3 Drain					
	Providing installation, testing, and commissioning of a 53.5 kW Solar PV system capable of running a horizontal centrifugal pump with discharge 10 cusec against 30–35 ft head, pump minimum 81% efficiency, including Tier-1 Bloomberg-certified mono / bi-facial N-type solar panels (JINKO / LONGI / JA / Canadian / AKCome / TW / Trina, 700+ W/panel, 23.5% efficiency), solar pump inverter INVT suitably rated for system capacity, mounted on 12 ft high L2/L3/L4 galvanized steel structure (14 gauge) with complete mechanical and civil works, DC and AC cabling with XLPE/PVC insulated tin-coated copper wires (DC 1-core 6 mm, AC 4-core 6 mm, 25 mm PVC/XLPE), combiner boxes, AC & DC breakers, SPDs (A+ grade), all distribution/protection boxes (12"×18"×18" SWG or equivalent), PVC pipes, flexible pipes (1–1.5"), thimbles (O-type, U-type with shrouds), Rawl bolts, nuts and bolts, complete earthing system, lightning arrestor, all civil works, foundations, supports, electrical connections for net metering with meter, transportation of all materials from warehouse to site, testing, commissioning, and manufacturer-provided maintenance/after-sales service for 2 years, complete in all respects as directed by the Engineer-in-Charge.	No	2.0			
				Total:		

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
17. Solarization of Tubewells 2 cusec 70 feet head						
17.1 Solarization of New Tubewells						
	Providing installation, testing, and commissioning of a 22.5 kW Solar PV system capable of running a horizontal centrifugal pump with discharge 2 cusec against 70 ft head, pump minimum 81% efficiency, including Tier-1 Bloomberg-certified mono / bi-facial N-type solar panels (JINKO / LONGI / JA / Canadian / AKCome / TW / Trina, 700+ W/panel, 23.5% efficiency), solar pump inverter INVT suitably rated for system capacity, mounted on 12 ft high L2/L3/L4 galvanized steel structure (14 gauge) with complete mechanical and civil works, DC and AC cabling with XLPE/PVC insulated tin-coated copper wires, combiner boxes, AC & DC breakers, SPDs (A+ grade), all distribution/protection boxes (12"×18"×18" SWG or equivalent), PVC pipes, flexible pipes (1–1.5"), thimbles (O-type, U-type with shrouds), Rawl bolts, nuts and bolts, complete earthing system, lightning arrestor, all civil works, foundations, and supports, all electrical connections for net metering with meter, transportation of all materials from warehouse to site, testing, commissioning, and manufacturer-provided maintenance/after-sales service for up to 2 years, complete in all respects as directed by the Engineer-in-Charge.	No	37.0			
17.2 Solarization of Existing Tubewells						
	Providing installation, testing, and commissioning of a 22.5 kW Solar PV system capable of running a horizontal centrifugal pump with discharge 2 cusec against 70 ft head, pump minimum 81% efficiency, including Tier-1 Bloomberg-certified mono / bi-facial N-type solar panels (JINKO / LONGI / JA / Canadian / AKCome / TW / Trina, 700+ W/panel, 23.5% efficiency), solar pump inverter INVT suitably rated for system capacity, mounted on 12 ft high L2/L3/L4 galvanized steel structure (14 gauge) with complete mechanical and civil works, DC and AC cabling with XLPE/PVC insulated tin-coated copper wires, combiner boxes, AC & DC breakers, SPDs (A+ grade), all distribution/protection boxes (12"×18"×18" SWG or equivalent), PVC pipes, flexible pipes (1–1.5"), thimbles (O-type, U-type with shrouds), Rawl bolts, nuts and bolts, complete earthing system, lightning arrestor, all civil works, foundations, and supports, all electrical connections for net metering with meter, transportation of all materials from warehouse to site, testing, commissioning, and manufacturer-provided maintenance/after-sales service for up to 2 years, complete in all respects as directed by the Engineer-in-Charge.	No	50.0			
Total:						
18. Construction of New Quarter for Tube well Operator						
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m)and lift upto 5' (1.5 m) (b) in ordinary soil. By Manual	1000 Cft	72531.7			
2	Spraying antitermite liquid mixed with water ratio 1:40	1 Sft	88776.2			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	0.0 11548.9			
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	44360.7			
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythene sheet 500 gauge 1½" thick (40 mm).	100 Sft	8834.1			
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	8771.5			
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	31674.4			
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4	100 Cft	47794.1			
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) - a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type C (nominal mix 1:2:4)	1 Cft	21724.4			
10	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	65173.3			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
11	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	3276.0			
12	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	3822.0			
13	Providing and fixing 1½" (40 mm) thick solid flush door shutter sterling or equivalent with commercial ply (5mm thick) on both sides double pressed and deodar wood lapping 1½" x 3/8" (40 mm x 10 mm) around shutter including chromium plated fitting, iron hinges with aluminum kick plate 22 SWG on both sides and finger plate complete in all respect.	1 Sft	3822.0			
14	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	33854.8			
15	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	34218.8			
16	Supplying and filling sand under floor or plugging in wells.	100 Cft	7420.1			
17	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	9109.1			
18	1½"(40 mm) thick mosaic flooring, consisting of ½ " mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1"(25 mm) thick floor of 1:2:4 cement concrete, including rubbing and polishing complete with finishing :-using grey cement	100 Sft	22325.4			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
19	Mosaic dado or skirting with one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1/2"(13 mm) thick cement plaster 1:3, including rubbing and polishing, complete with finishing:(a) using grey cement: i) 1/2"(13 mm) thick	100 Sft	14054.0			
20	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels(a) Size 1 1/2" x 3/8" (40 x 10 mm)	1 Rft	22750.0			
21	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) b) Nominal mix ratio 1:2:4	100 Cft	0.0 1780.2			
22	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	113184.7			
23	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	21116.6			
24	Distempering:- 3 coat	100 Sft	99928.2			
25	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	31339.9			
26	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	65280.2			
27	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	1183.0			
28	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	182.0			
29	Making top khurra on roof 2' x 2' x 6".	1 No	91.0			
30	Providing and fixing sliding; bolt to doors iron sliding bolt, 10" (250 mm) long.	1 No	182.0			
31	Painting new surface (c) preparing surface and painting of doors and windows any type (including edges) priming coat and 2 subsequent coats of paint.	100 Sft	7644.0			
32	Providing and fitting glazed earthen ware water closet, squatter type (Orisa pattern) combined with foot rest white.	1 Each	91.0			
33	Providing and fitting "P" trap 10 cm (4") glazed.	1 Each	273.0			
34	Providing and Fixing chromium plated bib cock (ii)1.5 cm (1/2").	1 Each	364.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
35	Providing & fitting plastic made low down flushing cistern 13.63 litre (3 gallons) capacity, including bracket set, copper connection, etc. complete (i) white.	1 Each	91.0			
36	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	9100.0			
37	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	364.0			
38	Providing and installing P.V.C. tees, of B.S.S.Class 'B' working pressure:-b) 4" i/d (100 mm)	1 No	364.0			
39	Providing,laying,testing and commissioning of POLYPROPYLENE RANDOM COPOLYMER (PPRC water supply pipe (Dadex/ Popular/ Beta or approved equivalent manufacturer, withs pecified pressure rating PN (PRESSURE NOMINAL) and conforming to DIN8077-8078 codei/ccost of solvent,specials,making jharries complete in all respect as approved and directed by Engineer Incharge.(Internal/ExternalDiametersmentioned). a) PN-16 pipe					
i	a) 20mm	1 Rft	9100.0			
ii	b) 25mm	1 Rft	4550.0			
40	Providing and fixing looking glass (mirror) 22" x 16" (55 x 40) cm, and 5 mm thick glass first quality.	1 Each	91.0			
41	Providing and fixing stainless steel sink with drain board, size 120 x 60 cm (48 x 24") including bracket set, waste pipe and waste coupling.	1 Each	91.0			
42	Providing and fitting.	-	0.0			
	a) Plastic soap dish.	1 Each	91.0			
	b) Plastic towel rail.	1 Each	91.0			
	c) plastic shelf 60x13cm (24" x 5") with bracket and railing.	1 Each	91.0			
43	Providing and fixing chromium plated tee stop cock 15 mm (1/2").	1 Each	91.0			
44	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.					
	a) 20mm (3/4") i/d.	1 Rft	9100.0			
	b) 25 mm (1") i/d	1 Rft	4550.0			
45	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and caping/G.I. wire/trenches (rate for cables only)					
	(a) 250/440 volts, P.V.C. insulated.					
	a) 3/0.74mm (3/0.029").	1 Rft	27300.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
	b) 7/0.74mm (7/0.029").	1 Rft	9100.0			
46	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only) (a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).	1 Rft	18200.0			
47	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.					
	a) 10 x 10 cm (4" x 4").	1 Each	182.0			
	b) 17.5 x 10 cm (7" x 4").	1 Each	364.0			
	c) 22.5 x 10 cm (9" x 4").	1 Each	91.0			
48	Supply and erection of switches 5 amp. Piano Type.	1 Each	3185.0			
49	Supply and erection of backlite button holder shade, large size.	1 Each	546.0			
50	Supply and erection of ceiling rose, bakelite.	1 Each	546.0			
51	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	182.0			
52	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	182.0			
53	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessded/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	91.0			
54	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screwes,necessary wire completb) Double Pole(iii) 6-63 Amp (10 KA)	1 No	91.0			
55	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screwes,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	364.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
56	Supply and erection of 3/8" (10mm) dia M.S. bar fan hook, placed at the time of casting of slab.	1 Each	91.0			
57	Providing and fixing Pakistan Energy Label NEECA approved Copper winded Ceiling Fan i/c the cost of necessary cable and hardware for connection as approved and directed by Engineer Incharge. 56" Sweep	1 Each	91.0			
58	Erecting of ceiling fan along with regulator (all sizes) including carriage local railway station/ store to site of work, electric wire/cable for suspension rod and board connection and cutting, threading on the rod where necessary.	1 Each	91.0			
59	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii) single rod (40 watts) with one choke and one starter.	1 No	546.0			
60	Provided and installed 1 HP electric water pump with 70 ft bore, and successfully installed a 200-gallon water tank including all accessories and plumbing connections.	1 Each	91.0			
61	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	11087.0			
ii	PCC 1:2:4	100 Cft	1566.6			
iii	RCC 1:2:4	100 Cft	19117.5			
iv	DPC 1:2:4	100 Cft	971.8			
				Total Cost:		

19. Eastward Extension of Evaporation Ponds

I. Earth Work for Jarewala Drain (from RD 0+000 to 25+446)

1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	4234073.1			
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	1712984.0			
3	Transportation of earth all types when the total distance, including the lead covered in the item of work.					
	a) 500 ft	1000 Cft	70005.0			
	b) 750 ft	1000 Cft	29937.5			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
4	Providing and fixing Enamelled steel plate gauge 4" wide 1/4" thick (including painting and lettering) 10 ft length	1 No	5.0			
5	Jungle clearance and removing within 100 ft. light	1000 Sft	1272300.0			
6	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	260.0			
ii. Data Board:						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	24.5			
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.5			
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.0			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.7			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.7			
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.7			
8	Writing letter or figures per letter per inch height	1 No	500.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.3			
iii. RD Marks:						
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	44.7			
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	102.2			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
3	Carriage of consignment job upto 5 KMs Average	1 No	26.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	26.0			
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	91.0			
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	260.0			
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	39.4			
iv. Road Barier:						
1	Earthwork excavation undressed lead upto a single throw of Kassi, phaorah or shovel: In ordinary soil.	1000 Cft	245.0			
2	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate) Ratio 1: 2: 4	100 Cft	367.5			
3	Providing, laying, cutting, jointing, testing and disinfecting G.I. pipeline in trenches, with socket joints, using G.I. pipes of B.S.S. 1387-1967 complete in all respects, with specials and valves. i) 4" i/d (100 mm) 3.65mm thick	1 Rft	560.0			
4	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 300Km.(From Sakhi Sarwar)	100 Cft	323.4			
				Total Cost:		
v. Earth Work of New 1-L / Jarewala Drain (from RD 0+000 to 16+500)						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	3676695.0			
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	4402362.5			
3	Transportation of earth all types when the total distance, including the lead covered in the item of work.					
	Lead 500 Feet	1000 Cft	137177.5			
	Lead 750 Feet	1000 Cft	898790.0			
	Lead 1750 Feet	1000 Cft	496885.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
4	Borrowpit excavation undressed lead upto 100 ft (30 metre) in a ordinary soil with Lead 500 feet	1000 Cft	1780642.5			
7	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	170.0			
vi. Data Board:						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	24.5			
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.5			
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.0			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.7			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.7			
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.7			
8	Writing letter or figures per letter per inch height	1 No	500.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.3			
vii. RD Marks:						
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	29.2			
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	66.8			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
3	Carriage of consignment job upto 5 KMs Average	1 No	17.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	17.0			
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	59.5			
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	170.0			
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	25.7			
				Total Cost:		
viii. Remodelling of Existing 1-L / Jarewala Drain (Earth Work from RD 0+000 to 3+500)						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preparation of working pad for operation of machinery. (rates includes 100ft lead)	1000 Cft	15402.5			
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	51770.0			
3	Transportation of earth all types when the total distance, including the lead covered in the item of work.					
	Lead 500 Feet	1000 Cft	1360.0			
4	Borrowpit excavation undressed lead upto 100 ft (30 metre) in a) ordinary soil with					
	Lead 500 feet	1000 Cft	45770.0			
5	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	40.0			
ix. Data Board:						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	49.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	12.3			
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	48.8			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	19.5			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortor ratio 1:3	100 Cft	40.9			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	115.3			
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	115.3			
8	Writing letter or figures per letter per inch height	1 No	250.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	2.1			
x. RD Marks:						
1	Precast reinfoced cement concrete type "C" 1:2:4.	1 Cft	6.9			
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	15.7			
3	Carriage of consignment job upto 5 KMs Average	1 No	4.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	4.0			
5	Preparing surface and painting with emulation paint 3 coat.	100 Sft	14.0			
6	Writing letter or firgures per letter per inch height (three figure each side).	1 No	40.0			
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	6.1			
				Total Cost:		
xi. Construction of Link Channels of Jarewala Drain System						
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	4410982.1			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	1949662.1			
3	Rehandling of earthwork lead upto 50ft (35% of excess cutting)	1000 Cft	910707.8			
4	Transportation of earth all types when the total distance, including the lead covered in the item of work.					
	Lead 500 Feet	1000 Cft	147378.6			
	Lead 1000 Feet	1000 Cft	224897.5			
	Lead 1500 Feet	1000 Cft	468525.0			
5	Borrowpit excavation undressed lead upto 100 ft (30 metre) in a) ordinary soil with Lead 250 feet	1000 Cft	140702.3			
xii. Data Board:						
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	294.0			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	73.5			
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	292.5			
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	117.0			
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	245.1			
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	692.0			
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	692.0			
8	Writing letter or figures per letter per inch height	1 No	1500.0			
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	12.9			
xiii. RD Marks:						
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	20.6			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	47.2			
3	Carriage of consignment job upto 5 KMs Average	1 No	12.0			
4	Placing boundary pillars in position, including digging pits.	1 Each	12.0			
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	42.0			
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	120.0			
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
ii	PCC 1:2:4	100 Cft	18.2			
				Total Cost:		
xiv. Pump House No: 7 (1-L / Jarewala Drain at RD 3+750)						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	125135.8			
2	Extra for slush or Daldal including dewatering.	1000 Cft	125135.8			
	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
3	a) Nominal mix ratio 1:4:8	100 Cft	1808.1			
4	b) Nominal mix ratio 1:2:4	100 Cft	577.9			
5	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars).Deformed Bars (Grade 60)	100 Kg	129118.0			
	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
6	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	18946.3			
7	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	9746.6			
8	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	9774.6			
9	Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sand blinded.	100 Sft	1394.3			
10	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	1394.3			
11	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	282.0			
12	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	12.0			
13	Making top khurra on roof 2' x 2' x 6".	1 No	6.0			
14	Providing and fixing windows consisting of M.S. box section frame 2"x1½", (50x40mm) leaves frame 1½"x1" (40x25mm) box section frame for glazing 3/8"x3/8" (10x10mm) using 16 SWG sheet 'U' shaped rubber supported with 1"x1/8" (25x3mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section ½"x1½" (13x13mm) of 16 SWG for fixing 24 SWG wire gauze on outer side by means of ¾"x1/8" (20x3mm) M.S. flat and screws including grill of M.S. flat ½"x1/8" (13x3mm) or ¼"x¼" (6x6mm) square bar with independent frame of ½"x1½" (13x13mm) box section of 16 SWG i/c all C.P. fitting and painting 3 coats complete in all respect.	1 Sft	463.9			
15	Making and fixing steel grated door with 1/16" thick 1.5mm) sheeting, including angle iron frame 2"x2"x3/8" (50x50x10 mm) and ¾" (20 mm) square bars 4" (100 mm)	1 Sft	184.0			
16	Distempering:- 2 coats	100 Sft	4838.9			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
17	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect.	100 Sft	6169.2			
18	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	344.0			
19	Providing and fixing 1¼x1¼"x3/16" (31x31x5 mm) angle" iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	1 No	150.0			
20	Providing/fixing stair railing consisting of M.S. Box section size 1-1/2"x3" of 16 SWG welded with M.S. flat 1"x1/8" continuously and welded over M.S. square bars 5/8"x5/8"punched in M.S. flat 2 ¾" high @ 5½" c/c fixed in steps of stair I/C painting 3 coats complete.	1 Rft	40.0			
21	Providing and fixing trash rack as per drawing	1 Sft	696.0			
22	Providing and layingTuff Pavers, having 7000PSI ,crushing strength of approved manufa cturer, over2"to3" sand cushion i/c grouting withsand in joints i/c finishing to require slope . complete in all respect. (50% Grey / 50% Coloured) 60-mm thick	1 Sft	2220.2			
23	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	585.6			
24	1½"(40 mm) thick mosaic flooring, consisting of ½ " mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1"(25 mm) thick floor of 1:2:4 cement concrete, including rubbing and polishing complete with finishing :-using grey cement	100 Sft	1394.3			
25	Mosaic dado or skirting with one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over ½"(13 mm) thick cement plaster 1:3, including rubbing and polishing, complete with finishing:(a) using grey cement: i) 1/2"(13 mm) thick	100 Sft	93.4			
26	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels(a) Size 1½" x 3/8" (40 x 10 mm)	1 Rft	723.4			
27	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	312.9			
28	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.					
	a) 20mm (3/4") i/d.	1 Rft	350.0			
	b) 25 mm (1") i/d	1 Rft	250.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
29	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated.					
	a) 3/0.74mm (3/0.029").	1 Rft	1000.0			
	b) 7/0.74mm (7/0.029").	1 Rft	500.0			
30	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.					
	b) 17.5 x 10 cm (7" x 4").	1 Each	10.0			
31	Supply and erection of switches 5 amp. Piano Type.	1 Each	50.0			
32	Supply and erection of backlite button holder shade, large size.	1 Each	15.0			
33	Supply and erection of ceiling rose, bakelite.	1 Each	15.0			
34	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screws,necessary wire completb) Double Pole(iii) 6-63 Amp (10 KA)	1 No	1.0			
35	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	10.0			
36	Providing and fixing Pakistan Energy Label NEECA approved Copper winded wall bracket Fan i/c the cost of necessary cable and hardware for connection as approved and directed by Engineer Incharge.ii) 24" Sweep dia	1 Each	10.0			
37	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)singel rod (40 watts) with one choke and one starter.	1 No	15.0			
47	Stone Pitching Work Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	5141.1			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
48	Providing & laying graded bajri ⅛" to ½"gauge on slope (including carriage).	100 Cft	812.4			
49	Providing & laying graded bajri ½" to 2" gauge on slope (including carriage).	100 Cft	812.4			
50	Providing & laying graded bajri ⅛" to ½"gauge on level (including carriage).	100 Cft	147.4			
51	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	147.4			
52	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	2461.9			
53	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	446.7			
54	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 300Km.(From Sakhi Sarwar)	100 Cft	36777.2			
				Total Cost		
xv. Construction of Bridge Cum Outlet at RD 0+000 New 1-L Jarewala						
1	Dismantling brick work in lime or cement mortar	100 Cft	803.3			
2	Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000 Cft	8700.0			
3	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	6543.0			
4	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	435.9			
5	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars).Deformed Bars (Grade 60)	100 Kg	20607.4			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
6	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	4518.0			
b	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	1972.2			
7	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	2183.8			
8	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	6.0			
9	Plain wood work for regulation karries or needles, etc. including sawing, planning, wroughting wood and providing and fixing steel parts of karries i.e. end strip and rods, etc. b) Shisham wood	1 Cft	143.6			
1	Stone Pitching Work Earthwork in excavation of drains in irrigation channels through excavator / draglines in all kind of soil and conditions	1000 Cft	2700.3			
2	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	2700.3			
3	Formation dressing and preparing subgrade, on slope	100 Sft	785.3			
4	Formation dressing and preparing subgrade, in bed.	100 Sft	136.0			
5	Providing & laying graded bajri ⅛" to ½" gauge on slope (including carriage).	100 Cft	259.2			
6	Providing & laying graded bajri ½" to 2" gauge on slope (including carriage).	100 Cft	259.2			
7	Providing & laying graded bajri ⅛" to ½" gauge on level (including carriage).	100 Cft	54.3			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
8	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	54.3			
9	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	785.3			
10	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	164.6			
11	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 300Km.(From Sakhi Sarwar)	100 Cft	10655.6			
12	Credit to old material Brick batts	100 Cft	803.3			
				Total Cost		
xvi. Construction of Canal Cum Canal Aquaduct Cum Bridge at Jarewala Main Drain						
1	Dismantling and removing road pavement, etc.,including screening and stacking of byproducts upto one chain lead (30 metre).	100 Cft	1155.0			
2	Dismantling brick work in lime or cement mortar	100 Cft	507.9			
3	Dismantling cement concrete reinforced, separating reinforcement from concrete, cleaning and straightening the same.	100 Cft	422.5			
4	Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000 Cft	32500.0			
5	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	40500.0			
6	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	40500.0			
7	Providing and laying R.C.C. pipe sewers, moulded with cement concrete 4000 psi conforming to Specification C-76-20, Class II. Wall B, including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade, jointing with rubber ring,cutting pipes where necessary, testing, etc., complete. 24 inch internal dia	1 Rft	112.0			
8	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	2658.1			
9	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	531.6			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
10	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars).Deformed Bars (Grade 60)	100 Kg	27968.8			
11	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	6010.7			
b	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	2797.9			
12	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	51.3			
13	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	2047.1			
14	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	6.0			
15	Providing and laying sub-base course of stone product of approved quality and grade, including placing, mixing, spreading and compaction of sub-base material to required depth, camber, grade to achieve 100% maximum modified AASHO dry density, including carriage of all material to site of work except gravel and aggregate. Crushed stone aggregate.	100 Cft	825.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
16	Providing and laying base course of crushed stone aggregate of approved quality and grade, and supply and spreading of stone screening, including placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHO dry density, including carriage of all materials to site of work except gravel and aggregate.	100 Cft	825.0			
17	Providing and laying road edging of 3" (75 mm) wide and	1 Rft	200.0			
18	Providing surface treatment of roads, including supply of bitumen and bajri/crushed stone aggregate of approved quality, including cleaning of road surface, heating, spraying bitumen, spreading bajri and rolling etc. complete including carriage of all material to site of work except bajri/crushed stone aggregate for which supply within 3 miles (5.0 km) is included in the rate.					
a	1st coat 35 lbs. bitumen, and 4 Cft. bajri of nominal size 1" (25 mm) per 100 sq. feet or 1.72 Kg bitumen and 0.017 cu. metre bajri per square metre..	100 Sft	1650.0			
b	2nd coat 18 lbs. bitumen, and 2 Cft. bajri of nominal size ½" (13 mm) per %sft or 1.23 Kg bitumen and 0.008 cu. metre bajri per sq. metre.	100 Sft	1650.0			
c	3rd coat 14 lbs. bitumen, and 1.5 Cft. bajri of nominal size ¼" (6 mm) per %sft or 0.69 Kg bitumen and 0.005 cubic metre bajri per sq. metre.	100 Sft	1650.0			
19	Stone Pitching Work Earthwork in excavation of drains in irrigation channels through excavator / draglines in all kind of soil and conditions	1000 Cft	967.1			
20	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excluding carriage)	100 Cft	967.1			
21	Formation dressing and preparing subgrade, on slope	100 Sft	614.7			
22	Formation dressing and preparing subgrade, in bed.	100 Sft	96.0			
23	Providing & laying graded bajri ⅛" to ½" gauge on slope (including carriage).	100 Cft	202.9			
24	Providing & laying graded bajri ½" to 2" gauge on slope (including carriage).	100 Cft	202.9			
25	Providing & laying graded bajri ⅛" to ½" gauge on level (including carriage).	100 Cft	31.7			
26	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	31.7			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
27	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	614.7			
28	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	96.0			
29	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 300Km.(From Sakhi Sarwar)	100 Cft	11198.2			
30	Credit to old material					
a	Steel	1 Kg	1267.5			
b	Brick batts	100 Cft	507.9			
				Total Cost		
xvii. Construction of Bridge at New 1-L / Jjarwewala Drain at RD 4+000						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	19789.8			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	358.9			
	b) Nominal mix ratio 1:2:4	100 Cft	100.3			
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars).Deformed Bars (Grade 60)	100 Kg	12287.6			
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	2130.8			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
b	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	1739.1			
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	978.1			
6	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with `B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	6.0			
7	Stone Pitching Work Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000 Cft	967.1			
8	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	967.1			
9	Formation dressing and preparing subgrade, on slope	100 Sft	594.5			
10	Formation dressing and preparing subgrade, in bed.	100 Sft	96.0			
11	Providing & laying graded bajri 1/8" to 1/2"gauge on slope (including carriage).	100 Cft	196.2			
12	Providing & laying graded bajri 1/2" to 2" gauge on slope (including carriage).	100 Cft	196.2			
13	Providing & laying graded bajri 1/8" to 1/2"gauge on level (including carriage).	100 Cft	31.7			
14	Providing & laying graded bajri 1/2" to 2" gauge on level (including carriage).	100 Cft	31.7			
15	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	594.5			
16	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	96.0			
17	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 300Km.(From Sakhi Sarwar)	100 Cft	5817.8			
				Total Cost		
xviii. Construction of Bridge at New 1-L / Jjarwewala Drain at RD 9+500						
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	23091.9			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)					
	a) Nominal mix ratio 1:4:8	100 Cft	358.9			
	b) Nominal mix ratio 1:2:4	100 Cft	100.3			
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars).Deformed Bars (Grade 60)	100 Kg	15546.4			
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	3157.1			
b	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	1739.1			
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	1471.5			
6	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	6.0			
7	Stone Pitching Work Earthwork in excavation of drains in irrigation channels through excavator / draglines in all kind of soil and conditions	1000 Cft	967.1			
8	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	967.1			
9	Formation dressing and preparing subgrade, on slope	100 Sft	594.5			
10	Formation dressing and preparing subgrade, in bed.	100 Sft	96.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
11	Providing & laying graded bajri ⅛" to ½"gauge on slope (including carriage).	100 Cft	196.2			
12	Providing & laying graded bajri ½" to 2" gauge on slope (including carriage).	100 Cft	196.2			
13	Providing & laying graded bajri ⅛" to ½"gauge on level (including carriage).	100 Cft	31.7			
14	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	31.7			
15	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	594.5			
16	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	96.0			
17	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 300Km.(From Sakhi Sarwar)	100 Cft	6679.9			
				Total Cost		
xix. Culverts						
1	Dismantling brick work in lime or cement mortar	100 Cft	803.3			
2	Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000	8700.0			
3	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	6543.0			
4	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Kg	435.9			
5	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars).Deformed Bars (Grade 60)	100 Kg	20607.4			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
6	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)					
a	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Kg	4518.0			
b	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Kg	1972.2			
7	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Kg	2183.8			
8	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Kg	6.0			
9	Plain wood work for regulation karries or needles, etc. including sawing, planning, wroughting wood and providing and fixing steel parts of karries i.e. end strip and rods, etc. b) Shisham wood	1 Kg	143.6			
9	<u>Stone Pitching Work</u> Earthwork in excavation of drains in irrigation channels through excavator / draglines in all kind of soil and conditions	1000 Kg	2700.3			
10	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Kg	2700.3			
11	Formation dressing and preparing subgrade, on slope	100 Kg	785.3			
12	Formation dressing and preparing subgrade, in bed.	100 Kg	136.0			
13	Providing & laying graded bajri ⅛" to ½" gauge on slope (including carriage).	100 Kg	259.2			
14	Providing & laying graded bajri ½" to 2" gauge on slope (including carriage).	100 Kg	259.2			
15	Providing & laying graded bajri ⅛" to ½" gauge on level (including carriage).	100 Kg	54.3			
16	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Kg	54.3			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
17	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Kg	785.3			
18	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Kg	164.6			
19	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 300Km.(From Sakhi Sarwar)	100 Kg	10655.6			
20 a	<u>Credit to old material</u> Brick batts	100 Cft	803.3			
xx. Tubewell Rooms						
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m)and lift upto 5' (1.5 m) (b) in ordinary soil.1)By Manual	1000 Cft	2724.5			
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextaror equivalent@specified suspension concentrate (SC), MixingAbility-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for10-years complete in all respect.as approved by the Engineer Incharge.	1 Sft	2542.5			
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	528.1			
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	1575.2			
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythensheet 500 gauge 1½" thick (40 mm).	100 Sft	322.5			
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	600.0			
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	750.0			
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	1454.5			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)		0.0			
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:2:4)	1 Cft	770.8			
10	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	92.0			
11	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	5177.2			
12	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	160.0			
13	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	200.0			
14	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	245.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
15	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	477.8			
16	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	497.8			
17	Supplying and filling sand under floor or plugging in wells.	100 Cft	204.7			
18	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	244.7			
19	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) b) Nominal mix ratio 1:2:4	100 Cft	0.0 229.3			
20	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	2841.5			
21	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	572.6			
22	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	2449.4			
23	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	65.0			
24	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	10.0			
25	Making top khurra on roof 2' x 2' x 6".	1 No	5.0			
26	Distempering:- 3 coat	100 Sft	2551.4			
27	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect.	100 Sft	862.8			
28	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	445.0			
29	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, revitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	1674.8			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
30	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.					
	a) 20mm (3/4") i/d.	1 Rft	300.0			
	b) 25 mm (1") i/d	1 Rft	150.0			
	c) 50 mm (2") i/d	1 Rft	75.0			
31	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and caping/G.I. wire/trenches (rate for cables only)					
	(a) 250/440 volts, P.V.C. insulated.					
	a) 3/0.74mm (3/0.029").	1 Rft	900.0			
	b) 7/0.74mm (7/0.029").	1 Rft	300.0			
32	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only) (a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).	1 Rft	200.0			
33	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.					
	a) 10 x 10 cm (4" x 4").	1 Each	5.0			
	b) 17.5 x 10 cm (7" x 4").	1 Each	5.0			
	c) 22.5 x 10 cm (9" x 4").	1 Each	5.0			
34	Supply and erection of switches 5 amp. Piano Type.	1 Each	100.0			
35	Supply and erection of ceiling rose, bakelite.	1 Each	20.0			
36	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	10.0			
37	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	5.0			
38	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessded/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	5.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
39	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screwes,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	30.0			
40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaid DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole (ii) 15-100 Amp (10 KA,15KA)	1 No	10.0			
41	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaid DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	5.0			
42	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)singl rod (40 watts) with one choke and one starter.	1 No	15.0			
43	Supply and erection of bakelite button holder shade, large size	1 No	15.0			
44	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.					
i	PCC 1:4:8	100 Cft	506.9			
ii	PCC 1:2:4	100 Cft	201.8			
iii	RCC 1.2.4	100 Cft	759.3			
iv	DPC 1.2.4	100 Cft	35.5			
				Total Cost:		

20. Installation of Pumps, Motors and Allied accessories (Mechanical Works for Jarewala Drain) PS-7

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
1	Providing installation, testing and commissioning of horizontal centrifugal pump having discharge capacity of 10 cusec against 40 ft - 45 ft head including pump, motor, bowl assembly, column set, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical cables, accessories and connections from transformer to pump including earthing and protection devices, complete suction piping inside the chamber (SS/MS/CI) and delivery piping up to the outlet basin (40–50 ft) of approved material (Fibre reinforced cement/upvc of suitable internal diameter size as approved by E-in-C) with all bends, flanges, valves, gaskets, supports and accessories, and carrying out all works necessary for energizing, testing and full-load commissioning of the complete pump set in all respects.. Pump shall have min. 82% efficiency which should be verified according to ISO 9906-1B standard. Material of pump casing shall be Gray cast iron EN-GJL-250 having impeller in Stainless Steel grade 1.4408. Pump shall be coated internally with epoxy paint. Material of pump shall be verified according to material test certificate EN 10204-3.1. Motor shall be of reputed manufacturer having min. IE3 efficiency class. Rating of motor to be 45 KW (60HP, 950 rpm)/6 pole, 3 phase, 50 Hz, 380/400 Volts. Manufacturer shall have its own testing facility to verify pumps hydraulic performance testing. Manufacturer shall have its own material testing lab to verify metallurgical testing. [including transportation and all overhead charges]	Job	6.0			
2	Providing, installation, testing and comissioning of 5 Ton capacity Gantry Craine, with girder bridge type arrangement, fitted with electric motor for its operation and mobility, electric wiring and fixing in position, complete in all rspect.	No.	1.0			
3	GNSS (Topographical) Surveying instrument with Base, Rover, Controller complete in all respect	No	1.0			
4	Providing and supplying a complete aerial topographic survey package consisting of a professional RTK-enabled survey drone, high-resolution photogrammetry camera, licensed processing software, additional 8 batteries with charging hub, Ground Control Point (GCP) sets/markers, High graded RTK base station kit with tripod and pole, and 5 TB rugged NVMe SSD storage, complete in all respects (Equivalent: DJI Matrice 350 RTK Drone, Zenmuse P1c etc)	No	1.0			
5	Providing and supplying a Total Station with angle accuracy $\leq 5''$, EDM reflectorless range ≥ 500 m, prism range ≥ 1500 m, distance accuracy $\pm (2 \text{ mm} + 2 \text{ ppm})$, 30 $\times$ telescope, dual-axis compensator, rechargeable batteries with charger, prism set with pole, tripod, data storage/USB/Bluetooth interface, carrying case, calibration certificate, and all accessories complete.	No	1.0			
6	Providing and supplying an automatic self-leveling Auto-Level with minimum 32 $\times$ magnification, $\pm 2 \text{ mm/km}$ accuracy, dual-axis compensator, tripod, 2.5 m leveling staff, carrying case, calibration certificate, and all accessories complete.	No	4.0			

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
7	Providing and supplying a high-performance workstation laptop with Intel Core i9-14900HX / AMD Ryzen 9 7940HX or higher, 64GB DDR5 RAM, 2TB NVMe Gen-5 M.2 SSD, dedicated NVIDIA RTX 4080 (12GB) or higher GPU, Windows 11 Pro, full-size keyboard with numeric pad, complete with premium laptop bag, wireless headphones (Sennheiser/Beats/Sony/Anker or equivalent), USB 3.2 Gen-2 (10Gbps) flash drive, and Logitech MX Master 3S wireless mouse or equivalent, complete in all respects.	No	2.0			
				Total:		
21. Installation and Solarization of Pumps						
1	Providing installation, testing, and commissioning of a 64 kW Solar PV system capable of operating a horizontal centrifugal pump with discharge 10 cusec against 40 - 45 ft head , pump minimum 82% efficiency verified as per ISO 9906-1B standard, including Tier-1 Bloomberg-certified mono/ bi-facial N-type solar panels (JINKO / LONGI / JA / Canadian / AKCome / TW / Trina, 700+ W/panel, 23.5% efficiency), solar pump inverter INVT suitably rated for system capacity, mounted on 12 ft high L2/L3/L4 galvanized steel structure (14 gauge) with complete mechanical and civil works, DC and AC cabling using XLPE/PVC insulated tin-coated copper wires, combiner boxes, AC & DC breakers, SPDs (A+ grade), all distribution/protection boxes (12"×18"×18" SWG or equivalent), PVC pipes, flexible pipes (1–1.5"), thimbles (O-type, U-type with shrouds), Rawl bolts, nuts and bolts, complete earthing system, lightning arrestor, all civil works, foundations, and supports, electrical connections for net metering with meter, transportation of all materials from warehouse to site, testing, commissioning, and manufacturer-provided maintenance/after-sales service for 2 years, complete in all respects as directed by the Engineer-in-Charge.	No	6.0			
				Total:		
22. Environmental Monitoring Cost						
1	For Construction Phase					
a	Surface water Monitoring	Lump Sump	1.0			
b	Groundwater Monitoring	Lump Sump	1.0			
c	Ambient Air Quality Monitoring	Lump Sump	1.0			
2	For Operational Phase					
a	Surface water Monitoring	Lump Sump	1.0			
b	Groundwater Monitoring	Lump Sump	1.0			
3	Drinking Water & Groundwater Monitoring near disposal Pit					

Sr. No	Description	Unit	Quantity	Rate		Amount Rupees
				Rupees in figure	Rupees in words	
a	Drinking Water Monitoring	Lump Sump	1.0			
b	Groundwater Monitoring	Lump Sump	1.0			
4	Training					
a	Training Session	Lump Sump	5.0			
5	Emergency Plan	Lump Sump	1.0			
6	Environmental Audit Cost	Lump Sump	3.0			
7	Site Visits by Regulatory Authorities	Lump Sump	1.0			
8	Traffic Management Cost					
a	Sign Board	Lump Sump	1.0			
b	Barricading Fence along Access Roads	Lump Sump	1.0			
c	Temporary Speed Breakers	Lump Sump	1.0			
d	Controlling Dust Pollution	Lump Sump	1.0			
e	Relocation of amenities and localized widening of road and barrier	Lump Sump	1.0			
	Total Cost					

MITIGATION OF WATERLOGGING IN DISTRICT RAHIMYAR KH

Sr. No	Item	Unit	Quantity	Rate
1. 2-L Manthar Drain (RD 0+000 to 31+568)				
i. Earthwork				
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	616,487.50	4,640.70
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	174,315.00	940.90
3	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft.			
	a) 500 ft	1000 Cft	20,640.00	1,073.20
	b) 1000 ft	1000 Cft	2,970.00	2,414.70
	c) 1250 ft	1000 Cft	8,792.50	6,677.80
	d) 1500 ft	1000 Cft	1,215.00	6,751.20
	e) 2000 ft	1000 Cft	18,740.00	6,824.60
	f) 4250 ft	1000 Cft	54,772.50	7,338.40
4	Making boundary or service roads, including dag-belling, leveling and dressing:ii) in ploughed land: a) from 10.0 ft. to 20.0 ft. (3 to 6 m) wide	1 -Chain	410.00	1,935.40
5	Jungle clearance and removing within 100 ft. light	1000 Sft	315,680.00	376.20
ii. Data Board				
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	24.50	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.50	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.00	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortor ratio 1:3	100 Cft	81.70	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.65	4,334.75
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.65	7,379.10
8	Writing letter or figures per letter per inch height	1 No	500.00	30.50
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
	DPC	100 Cft	4.29	14,042.60
iii. RD Marks				
1	Precast reinfoced cement concrete type "C" 1:2:4.	1 Cft	55.04	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	125.76	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	32.00	115.40

4	Placing boundary pillars in position, including digging pits.	1 Each	32.00	141.90
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	112.00	4,307.55
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	320.00	30.50
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
ii	PCC 1:2:4	100 Cft	48.44	14,042.60
				Total Cost

iv. Culverts

1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft.	1000 Cft	6,406.12	12,735.60
2	In ordinary soil (above 5 ft depth) Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	361.00	34,694.30
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	12,000.72	30,376.90
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			
a)	Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	2,556.24	817.55
b)	Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	1,444.00	670.50
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	2,739.76	1,645.10
6	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 80mm dia (3 inch)	1 Rft	13.50	303.80
7	Providing and laying sub-base course of stone product of approved quality and grade, including placing, mixing, spreading and compaction of sub-base material to required depth, camber, grade to achieve 100% maximum modified AASHO dry density, including carriage of all material to site of work except gravel and aggregate. Crushed stone aggregate.	100 Cft	480.00	10,003.50
8	Providing and laying base course of crushed stone aggregate of approved quality and grade, and supply and spreading of stone screening, including placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHO dry density, including carriage of all materials to site of work except gravel and aggregate.	100 Cft	480.00	13,527.40
9	Providing and laying road edging of 3" (75 mm) wide and 9" (225 mm) deep brick on end, complete in all respects	1 Rft	120.00	64.20

10	Providing surface treatment of roads,including supply of bitumen and bajri/crushed stone aggregate of approved quality,including cleaning of road surface,heating,spraying bitumen,spreading bajri and rollingetc.complete including carriageof all material stosite of work excep tbajri/crushed stone aggregate for which supply with in miles (5.0km) is included in the rate.			
a	1st coat 35 lbs. bitumen, and 4 Cft. bajri of nominal size 1" (25 mm) per 100 sq. feet or 1.72 Kg bitumen and 0.017 cu.metre bajri per square metre..	100 Sft	960.00	4,549.95
b	2nd coat 18 lbs. bitumen, and 2 Cft. bajri of nominal size ½" (13 mm) per %sft or 1.23 Kg bitumen and 0.008 cu. metre bajri per sq.metre.	100 Sft	960.00	2,639.45
c	3rd coat 14 lbs. bitumen, and 1.5 Cft. bajri of nominal size ¼" (6 mm) per %sft or 0.69 Kg bitumen and 0.005 cubic metre bajri per sq.metre.	100 Sft	960.00	1,960.75
11	Dismantling and removing road pavement, etc.,including screening and stacking of byproducts upto one chain lead (30 metre).	100 Cft	960.00	4,017.80
12	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	6,480.00	10,533.60
14	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	6,480.00	5,266.80
15	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	346.56	14,042.60
ii	RCC 1:1.5:3	100 Cft	3,360.20	14,042.60
iii	Base	100 Cft	585.60	14,042.60
iii	T.S.T	100 Cft	72.00	14,042.60
Total Cost				

v. Water Course

1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	1,867.65	12,735.60
2	Extra for slush or Daldal including dewatering.	1000 Cft	1,867.65	12,038.40
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			
a)	Nominal mix ratio 1:4:8	100 Cft	257.20	34,694.30
b)	Nominal mix ratio 1:2:4	100 Cft	34.00	47,135.90
4	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	6,108.98	30,376.90
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects.	1 Cft	1,266.91	817.55
b)	Type B (nominal mix 1:1.5:3) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	769.42	670.50
6	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	751.28	1,645.10

7	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	80.00	35,727.00
8	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Lft	189.50	809.40
9	Providing and placing poly sulphide joint sealant 1" wide and 1" deep.	1 Lft	70.00	1,381.00
10	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	4,000.00	5,266.80
11	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	246.91	14,042.60
ii	PCC 1:2:4	100 Cft	29.92	14,042.60
iii	RCC 1.1.5.3	100 Cft	1,710.52	14,042.60

Total Cost:

vi. Stone Pitching

1	Earthwork in excavation of drains in irrigation channels through excavator / draglines in all kind of soil and conditions	1000 Cft	476.44	4,640.70
2	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons.	100 Cft	476.44	6,849.00
3	Formation dressing and preparing subgrade, on slope	100 Sft	735.37	2,265.10
4	Formation dressing and preparing subgrade, in bed.	100 Sft	130.50	1,660.50
5	Providing and laying graded bajri 1/8" to 1/2" size on slope.	100 Cft	242.67	18,564.10
6	Providing and laying graded bajri 1/2" to 2" size on slope.	100 Cft	242.67	18,564.10
7	Providing and laying graded bajri 1/8" to 1/2" size on level.	100 Cft	43.07	18,017.60
8	Providing and laying graded bajri 1/2" to 2" size on level.	100 Cft	43.07	18,017.60
9	Providing and laying stone for top layer only, on slope.	100 Cft	735.37	11,511.00
10	Providing and laying stone for top layer only, on Level	100 Cft	130.50	10,570.50
11	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc or 150 Cft of timber by truck or by any other means owned by the contractor, lead 275 Km.	100 Cft	1,682.24	14,042.60

Total Cost

vii. VRB Repair

1	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	100 Cft	157.90	47,135.90
2	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60)	100 Kg	1,999.52	30,376.90
3	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)		-	
a	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	499.88	817.55
4	Providing and fixing 4" dia P.V.C pipe.	1 Rft	12.00	378.75
5	Borrowpit excavation undressed lead upto 100 ft (30 metre). Ordinary soil	1000 Cft	3,710.00	10,533.60
6	Cement plaster 1:3 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	694.50	4,850.40

7	Providing and laying R.C.C. pipe sewers, moulded with cement concrete 4000 psi conforming to ASTM Specification C-76-20, Class II. Wall B, including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade, jointing with rubber ring, cutting pipes where necessary, testing, etc., complete. 610 mm (24") i/d	1 Rft	96.00	2,150.35
8	Dismantling cement concrete reinforced, separating reinforcement from concrete, cleaning and straightening the same.	100 Cft	307.00	27,086.40
9	Credit old material	1 Kg	82.00	(170.00)
Total Cost:				

viii. Tube Well room

1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil. 1) By Manual	1000 Cft	2,179.57	15,824.15
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextaror equivalent @ specified suspension concentrate (SC), Mixing Ability-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for 10-years complete in all respect. as approved by the Engineer Incharge.	1 Sft	2,034.00	12.55
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
a)	Nominal mix ratio 1:4:8	100 Cft	422.45	34,694.30
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	1,260.16	32,675.95
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythene sheet 500 gauge 1½" thick (40 mm).	100 Sft	258.00	11,460.20
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	480.00	7,607.35
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	600.00	7,547.75
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	1,163.60	35,830.60
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			
a)	Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:2:4)	1 Cft	616.66	741.85
b)	Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work (i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	73.63	595.00
11	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	4,141.77	30,376.90

12	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	128.00	2,180.70
13	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	160.00	457.10
14	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	196.00	2,767.00
15	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	382.25	13,179.60
16	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	398.25	11.00
17	Supplying and filling sand under floor or plugging in wells.	100 Cft	163.75	3,987.00
18	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	195.75	12,801.20
19	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) b) Nominal mix ratio 1:2:4	100 Cft	183.44	47,135.90
20	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	2,273.22	4,614.10
21	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	458.08	5,264.65
22	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	1,959.50	5,012.65
23	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	52.00	514.90
24	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	8.00	849.70
25	Making top khurra on roof 2' x 2' x 6".	1 No	4.00	1,159.65
26	Distempering:- 3 coat	100 Sft	2,041.08	1,548.20
27	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	690.22	7,379.10
28	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	356.00	3,052.40
29	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, revitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	1,339.83	37,098.85
30	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.			-
a)	20mm (3/4") i/d.	1 Rft	240.00	112.25
b)	25 mm (1") i/d	1 Rft	120.00	133.60
c)	50 mm (2") i/d	1 Rft	60.00	231.55
31	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated.			-

a)	3/0.74mm (3/0.029").	1 Rft	720.00	35.70
b)	7/0.74mm (7/0.029").	1 Rft	240.00	56.30
32	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only)	1 Rft	160.00	237.65
	(a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).			
33	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.			-
a)	10 x 10 cm (4" x 4").	1 Each	4.00	382.30
b)	17.5 x 10 cm (7" x 4").	1 Each	4.00	522.75
c)	22.5 x 10 cm (9" x 4").	1 Each	4.00	668.80
34	Supply and erection of switches 5 amp. Piano Type.	1 Each	80.00	102.70
35	Supply and erection of ceiling rose, bakelite.	1 Each	16.00	96.30
36	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	8.00	204.70
37	Supply and erection of 3 pin switch and plug combined recessed type	1 Each	4.00	213.10
	(ii) 10/15 amp.			
38	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessed/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep	1 No	4.00	24,422.65
	(i) 20~60A			
39	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	24.00	1,453.75
40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaidd DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole	1 No	8.00	13,796.30
	(ii) 15-100 Amp (10 KA,15KA)			
41	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaidd DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	4.00	19,859.40
42	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	12.00	1,995.30
43	Supply and erection of bakelite button holder shade, large size	1 No	12.00	178.75
44	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	405.55	14,042.60
ii	PCC 1:2:4	100 Cft	161.43	14,042.60
iii	RCC 1.2.4	100 Cft	607.46	14,042.60
iv	DPC 1.2.4	100 Cft	28.38	14,042.60
Total Cost				

Total Cost Section -1 (2L Manthar Drain)

2. 3-L Manthar Drain (RD 0+000 to 18+007)

i. Earthwork

1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, dalad and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	590,424.88	4,640.70
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	112,011.01	940.90
3	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft.			
	a) 500 ft	1000 Cft	4,055.67	1,073.20
	b) 750 ft	1000 Cft	4,805.00	1,743.95
	c) 1250 ft	1000 Cft	20,505.00	6,677.80
	d) 3000 ft	1000 Cft	1,237.50	7,044.80
	e) 4500 ft	1000 Cft	15,772.50	7,411.80
	f) 6750 ft	1000 Cft	4,869.33	7,934.10
4	Making boundary or service roads, including dag-belling, leveling and dressing:ii) in ploughed land: a) from 10.0 ft. to 20.0 ft. (3 to 6 m) wide	1 - Chain	255.00	1,935.40
5	Jungle clearance and removing within 100 ft. light	1000 Sft	180,070.00	376.20

Total Cost:

ii. Data Board

1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	24.50	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.50	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.00	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.70	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.65	4,334.75
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.65	7,379.10
8	Writing letter or figures per letter per inch height	1 No	500.00	30.50
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.29	14,042.60

Total Cost:

iii. RD Marks:

1	Precast reinfoced cement concrete type "C" 1:2:4.	1 Cft	30.96	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	70.74	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	18.00	115.40
4	Placing boundary pillars in position, including digging pits.	1 Each	18.00	141.90
5	Preparing surface and painting with emulation paint 3 coat.	100 Sft	63.00	4,307.55
6	Writing letter or firgures per letter per inch height (three figure each side).	1 No	180.00	30.50

7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
ii	PCC 1:2:4	100 Cft	27.24	14,042.60
Total Cost:				
iv. Stone Pitching				
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, dalad and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	355.50	4,640.70
2	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons.	100 Cft	355.50	6,849.00
3	Formation dressing and preparing subgrade, on slope	100 Sft	681.66	2,265.10
4	Formation dressing and preparing subgrade, in bed.	100 Sft	126.00	1,660.50
5	Providing and laying graded bajri 1/8" to 1/2" size on slope.	100 Cft	224.94	18,564.10
6	Providing and laying graded bajri 1/2" to 2" size on slope.	100 Cft	224.94	18,564.10
7	Providing and laying graded bajri 1/8" to 1/2" size on level.	100 Cft	41.58	18,017.60
8	Providing and laying graded bajri 1/2" to 2" size on level.	100 Cft	41.58	18,017.60
9	Providing and laying stone for top layer only, on slope.	100 Cft	681.66	11,511.00
10	Providing and laying stone for top layer only, on Level	100 Cft	126.00	10,570.50
11	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc or 150 Cft of timber by truck or by any other means owned by the contractor, lead 275 Km.	100 Cft	1,449.12	14,042.60
Total Cost:				
v. VRB Repair				
1	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	100 Cft	136.81	47,135.90
2	Cement plaster 1:3 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Cft	848.00	4,850.40
Total Cost:				
vi. Tube Well room				
1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil.1)By Manual	1000 Cft	1,089.78	15,824.15
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextar or equivalent @ specified suspension concentrate (SC), Mixing Ability-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for 10-years complete in all respect as approved by the Engineer Incharge.	1 Sft	1,017.00	12.55
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	211.22	34,694.30
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	630.08	32,675.95
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythene sheet 500 gauge 1½" thick (40 mm).	100 Sft	129.00	11,460.20
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	240.00	7,607.35
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	300.00	7,547.75
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	581.80	35,830.60

9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:2:4)	1 Cft	308.33	741.85
10	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	36.82	595.00
11	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	2,070.88	30,376.90
12	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	64.00	2,180.70
13	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	80.00	457.10
14	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	98.00	2,767.00
15	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	191.13	13,179.60
16	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	199.13	11.00
17	Supplying and filling sand under floor or plugging in wells.	100 Cft	81.88	3,987.00
18	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	97.88	12,801.20
19	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	b) Nominal mix ratio 1:2:4	100 Cft	91.72	47,135.90
20	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	1,136.61	4,614.10
21	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	229.04	5,264.65
22	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	979.75	5,012.65
23	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	26.00	514.90
24	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	4.00	849.70
25	Making top khurra on roof 2' x 2' x 6".	1 No	2.00	1,159.65

26	Distempering:- 3 coat	100 Sft	1,020.54	1,548.20
27	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	345.11	7,379.10
28	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	178.00	3,052.40
29	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, revitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	669.92	37,098.85
30	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.			-
	a) 20mm (3/4") i/d.	1 Rft	120.00	112.25
	b) 25 mm (1") i/d	1 Rft	60.00	133.60
	c) 50 mm (2") i/d	1 Rft	30.00	231.55
31	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and caping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated.			-
	a) 3/0.74mm (3/0.029").	1 Rft	360.00	35.70
	b) 7/0.74mm (7/0.029").	1 Rft	120.00	56.30
32	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only) (a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).	1 Rft	80.00	237.65
33	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.			-
	a) 10 x 10 cm (4" x 4").	1 Each	2.00	382.30
	b) 17.5 x 10 cm (7" x 4").	1 Each	2.00	522.75
	c) 22.5 x 10 cm (9" x 4").	1 Each	2.00	668.80
34	Supply and erection of switches 5 amp. Piano Type.	1 Each	40.00	102.70
35	Supply and erection of ceiling rose, bakelite.	1 Each	8.00	96.30
36	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	4.00	204.70
37	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	2.00	213.10
38	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessded/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	2.00	24,422.65
39	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	12.00	1,453.75
40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaid DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole (ii) 15-100 Amp (10 KA,15KA)	1 No	4.00	13,796.30

41	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker) of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (with fixed Thermal-Magnetic Trip) in pre-laid DB and Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the Engineer in charge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	2.00	19,859.40
42	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii) single rod (40 watts) with one choke and one starter.	1 No	6.00	1,995.30
43	Supply and erection of bakelite button holder shade, large size	1 No	6.00	178.75
44	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	202.78	14,042.60
ii	PCC 1:2:4	100 Cft	80.71	14,042.60
iii	RCC 1:2:4	100 Cft	303.73	14,042.60
iv	DPC 1:2:4	100 Cft	14.19	14,042.60

Total Cost:

Total Cost Section -2 (3L Manthar Drain)

3. 4-L Manthar Drain (RD 0+000 to 17+700)

i. Earthwork

1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preparation of working pad for operation of machinery. (rates includes 100ft lead)	1000 Cft	203,524.50	4,640.70
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	262,075.50	940.90
	Transportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft.			
3	a) 500 ft	1000 Cft	3,727.50	1,073.20
	b) 750 ft	1000 Cft	5,270.00	1,743.95
	c) 4500 ft	1000 Cft	109,947.50	7,411.80
	d) 5500 ft	1000 Cft	70,367.50	7,558.60
4	Borrowpit excavation undressed lead upto 100 ft (30 metre) in a) ordinary soil with			
	a) 500 ft	1000 Cft	60,633.00	11,606.80
5	Making boundary or service roads, including dag-belling, leveling and dressing: ii) in ploughed land:	1 - Chain	215.00	1,935.40
	a) from 10.0 ft. to 20.0 ft. (3 to 6 m) wide			
6	Jungle clearance and removing within 100 ft. light	1000 Sft	177,000.00	376.20

ii. Data Board:

1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	24.50	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.50	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.00	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.70	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.65	4,334.75

7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.65	7,379.10
8	Writing letter or figures per letter per inch height	1 No	500.00	30.50
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
	DPC	100 Cft	4.29	14,042.60

iii. RD Marks:

1	Precast reinfoced cement concrete type "C" 1:2:4.	1 Cft	30.96	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	70.74	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	18.00	115.40
4	Placing boundary pillars in position, including digging pits.	1 Each	18.00	141.90
5	Preparing surface and painting with emulation paint 3 coat.	100 Sft	63.00	4,307.55
6	Writing letter or firgures per letter per inch height (three figure each side).	1 No	180.00	30.50
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
ii	PCC 1:2:4	100 Cft	27.24	14,042.60

Total Cost:

iv. Stone Pitching

1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	312.56	4,640.70
2	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons.	100 Cft	312.56	6,849.00
3	Formation dressing and preparing subgrade, on slope	100 Sft	525.12	2,265.10
4	Formation dressing and preparing subgrade, in bed.	100 Sft	129.50	1,660.50
5	Providing and laying graded bajri 1/8" to 1/2" size on slope.	100 Cft	173.29	18,564.10
6	Providing and laying graded bajri 1/2" to 2" size on slope.	100 Cft	173.29	18,564.10
7	Providing and laying graded bajri 1/8" to 1/2" size on level.	100 Cft	42.74	18,017.60
8	Providing and laying graded bajri 1/2" to 2" size on level.	100 Cft	42.74	18,017.60
9	Providing and laying stone for top layer only, on slope.	100 Cft	525.12	11,511.00
10	Providing and laying stone for top layer only, on Level	100 Cft	129.50	10,570.50
11	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc or 150 Cft of timber by truck or by any other means owned by the contractor, lead 275 Km.	100 Cft	1,207.50	14,042.60

Total Cost

Total Cost for Section -3 (4L Manthar Drain)

4. Pattan Minara Drain (RD 0+000 to 23+000)

i. Earthwork

1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	2,110,200.00	4,640.70
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	680,530.00	940.90
3	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft.			
	a) Lead 500 feet	1000 Cft	8,217.50	1,073.20
	b) Lead 1750 ft	1000 Cft	58,687.50	6,751.20

	c) Lead 2750 ft	1000 Cft	75,040.00	6,971.40
4	Making boundary or service roads, including dag-belling, leveling and dressing:ii) in ploughed land: a) from 10.0 ft. to 20.0 ft. (3 to 6 m) wide	1 - Chain	95.00	1,935.40
6	Jungle clearance and removing within 100 ft. light	1000 Sft	460,000.00	376.20
ii. Data Board				
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	24.50	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.50	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.00	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.70	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.65	4,334.75
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.65	7,379.10
8	Writing letter or figures per letter per inch height	1 No	500.00	30.50
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
	DPC	100 Cft	4.29	14,042.60
iii. RD Marks				
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	39.56	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	90.39	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	23.00	115.40
4	Placing boundary pillars in position, including digging pits.	1 Each	23.00	141.90
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	80.50	4,307.55
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	230.00	30.50
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
ii	PCC 1:2:4	100 Cft	34.81	14,042.60
Total Cost				
iv. Stone Pitching				
1	Dismantling stone or spawl pitching and apron in silted condition.	100 Cft	93,240.00	3,762.00
2	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinery. (rates includes 100ft lead)	1000 Cft	129,745.50	4,640.70
3	Supply and dumping at site, without boat, including handling of materials within three chains (90 m)	100 Cft	126,000.00	4,743.75
4	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons.	100 Cft	3,745.50	6,849.00
3	Formation dressing and preparing subgrade, on slope	100 Sft	72,754.37	2,265.10
4	Formation dressing and preparing subgrade, in bed.	100 Sft	12,167.00	1,660.50

4	Providing and laying graded bajri 1/8" to 1/2" size on slope.	100 Cft	24,008.94	18,564.10
5	Providing and laying graded bajri 1/2" to 2" size on slope.	100 Cft	24,008.94	18,564.10
6	Providing and laying graded bajri 1/8" to 1/2" size on level.	100 Cft	4,015.11	18,017.60
7	Providing and laying graded bajri 1/2" to 2" size on level.	100 Cft	4,015.11	18,017.60
8	Providing and laying stone for top layer only, on slope.	100 Cft	72,754.37	11,511.00
9	Providing and laying stone for top layer only, on Level	100 Cft	12,167.00	10,570.50
10	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc or 150 Cft of timber by truck or by any other means owned by the contractor, lead 275 Km.	100 Cft	152,322.07	14,042.60

Total Cost

v. Water Course

1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	1,417.95	12,735.60
2	Extra for slush or Daldal including dewatering.	1000 Cft	1,417.95	12,038.40
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8 b) Nominal mix ratio 1:2:4	100 Cft 100 Cft	140.10 17.00	34,694.30 47,135.90
4	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	4,515.81	30,376.90
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3) b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	1,063.04	817.55
6	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	551.01	1,645.10
7	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	40.00	35,727.00
8	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	180.20	809.40
9	Providing and placing poly sulphide joint sealent 1" wide and 1" deep.	1 Rft	50.00	1,381.00
10	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	2,000.00	5,266.80
11	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	134.50	14,042.60
ii	PCC 1:2:4	100 Cft	14.96	14,042.60
iii	RCC 1.1.5.3	100 Cft	1,264.43	14,042.60

Total Cost:

vi. VRB Repair

1	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	100 Cft	966.72	47,135.90
2	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars): Deformed bars (Grade-60)	100 Kg	2,080.00	30,376.90
3	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			
a	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	520.00	817.55
4	Providing and fixing 4" dia P.V.C pipe.	1 Rft	6.00	378.75
5	Borrowpit excavation undressed lead upto 100 ft (30 metre). Ordinary soil	1000 Cft	8,490.00	10,533.60
6	Cement plaster 1:3 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Cft	3,936.00	4,850.40
7	Providing and laying R.C.C. pipe sewers, moulded with cement concrete 4000 psi conforming to ASTM Specification C-76-20, Class II. Wall B, including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade, jointing with rubber ring, cutting pipes where necessary, testing, etc., complete. 610 mm (24") i/d	1 Rft	48.00	2,150.35
8	Dismantling cement concrete reinforced, separating reinforcement from concrete, cleaning and straightening the same.	100 Cft	384.00	27,086.40
9	Credit old material	1 Kg	768.00	(170.00)
Total Cost:				

vii. Tube Well room

1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil. 1) By Manual	1000 Cft	3,814.24	15,824.15
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextar or equivalent @ specified suspension concentrate (SC), Mixing Ability-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for 10-years complete in all respect as approved by the Engineer Incharge.	1 Sft	3,559.50	12.55
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	739.29	34,694.30
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	2,205.28	32,675.95
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythene sheet 500 gauge 1½" thick (40 mm).	100 Sft	451.50	11,460.20
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	840.00	7,607.35
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	1,050.00	7,547.75
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	2,036.30	35,830.60

9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:2:4)	1 Cft	1,079.16	741.85
10	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	128.85	595.00
11	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	7,248.09	30,376.90
12	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	224.00	2,180.70
13	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	280.00	457.10
14	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	343.00	2,767.00
15	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	668.94	13,179.60
16	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	696.94	11.00
17	Supplying and filling sand under floor or plugging in wells.	100 Cft	286.56	3,987.00
18	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	342.56	12,801.20
19	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
20	b) Nominal mix ratio 1:2:4	100 Cft	321.02	47,135.90
21	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	3,978.14	4,614.10
22	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3). Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	801.64	5,264.65
23	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	91.00	514.90
24	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	14.00	849.70
25	Making top khurra on roof 2' x 2' x 6".	1 No	7.00	1,159.65

26	Distempering:- 3 coat	100 Sft	3,571.89	1,548.20
27	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	1,207.89	7,379.10
28	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	623.00	3,052.40
29	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, revitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	2,344.71	37,098.85
30	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.			-
	a) 20mm (3/4") i/d.	1 Rft	420.00	112.25
	b) 25 mm (1") i/d	1 Rft	210.00	133.60
	c) 50 mm (2") i/d	1 Rft	105.00	231.55
31	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pipe/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and caping/G.I. wire/trenches (rate for cables only)			-
	(a) 250/440 volts, P.V.C. insulated.			
	a) 3/0.74mm (3/0.029").	1 Rft	1,260.00	35.70
	b) 7/0.74mm (7/0.029").	1 Rft	420.00	56.30
32	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only)	1 Rft	280.00	237.65
	(a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).			
33	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.			-
	a) 10 x 10 cm (4" x 4").	1 Each	7.00	382.30
	b) 17.5 x 10 cm (7" x 4").	1 Each	7.00	522.75
	c) 22.5 x 10 cm (9" x 4").	1 Each	7.00	668.80
34	Supply and erection of switches 5 amp. Piano Type.	1 Each	140.00	102.70
35	Supply and erection of ceiling rose, bakelite.	1 Each	28.00	96.30
36	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	14.00	204.70
37	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	7.00	213.10
38	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessed/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	7.00	24,422.65
39	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	42.00	1,453.75
40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaidd DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole (ii) 15-100 Amp (10 KA,15KA)	1 No	14.00	13,796.30

41	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker) of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (with fixed Thermal-Magnetic Trip) in pre-laid DB and Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the Engineer in charge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1	7.00	19,859.40
42	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii) single rod (40 watts) with one choke and one starter.	1	21.00	1,995.30
43	Supply and erection of bakelite button holder shade, large size	1	21.00	178.75
44	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	709.72	14,042.60
ii	PCC 1:2:4	100 Cft	282.50	14,042.60
iii	RCC 1:2:4	100 Cft	1,063.05	14,042.60
iv	DPC 1:2:4	100 Cft	49.67	14,042.60

Total Cost:

Total Cost for Section -4 (Pattan Minara Drain)

5. Manthar Drain (RD 0+000 to 140+000)

i. Earthwork

1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preparation of working pad for operation of machinery. (rates includes 100ft lead)	1000 Cft	15,023,937.50	4,640.70
2	Transportation of earth all types when the total distance, including the lead covered in the item of work.			
	Lead 500 ft	1000 Cft	12,747.50	1,073.20
	Lead 1000 ft	1000 Cft	5,975.00	2,414.70
3	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	2,113,837.50	940.90
4	Making boundary or service roads, including dag-belling, leveling and dressing: ii) in ploughed land:	1 - Chain	720.00	1,935.40
	a) from 10.0 ft. to 20.0 ft. (3 to 6 m) wide			
6	Jungle clearance and removing within 100 ft. light	1000 Sft	2,800,000.00	376.20

ii. Data Board

1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	24.50	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.50	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.00	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.70	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.65	4,334.75
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.65	7,379.10
8	Writing letter or figures per letter per inch height	1 No	500.00	30.50

9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.29	14,042.60
iii. RD Marks				
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	242.52	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	554.13	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	141.00	115.40
4	Placing boundary pillars in position, including digging pits.	1 Each	141.00	141.90
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	493.50	4,307.55
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	1,410.00	30.50
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
ii	PCC 1:2:4	100 Cft	213.42	14,042.60
				Total Cost
iv. Culverts				
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	1,489.60	12,735.60
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	132.00	34,694.30
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	4,803.00	30,376.90
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	1,073.00	817.55
	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	528.00	670.50
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	944.00	1,645.10
6	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 80mm dia (3 inch)	1 Rft	6.00	303.80
7	Providing and laying R.C.C. pipe sewers, moulded with cement concrete 4000 psi conforming to Specification C-76-20, Class II. Wall B, including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade, jointing with rubber ring, cutting pipes where necessary, testing, etc., complete. 24 inch internal dia	1 Rft	48.00	2,150.35
8	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	5,400.00	10,533.60

9	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	5,400.00	5,266.80
10	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	126.72	14,042.60
ii	RCC 1:1.5:3	100 Cft	1,344.84	14,042.60
				Total Cost

v. VRB Repair

1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain (30 m) and lift upto 5 ft. (1.5 m). in ordinary soil Wing walls.	1000 Cft	1,776.00	12,735.60
2	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1: 4: 8.	100 Cft	73.50	34,694.30
3	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	100 Cft	2,414.07	47,135.90
4	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60)	100 Kg	61,090.96	30,376.90
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			
a)	Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects.Type B (nominal mix 1:1.5:3)	1 Cft	13,743.27	817.55
b)	Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	192.00	670.50
6	Providing and fixing 4" dia P.V.C pipe.	1 Rft	30.00	378.75
7	Providing and fixing Neoprene bearing pad with laminated steel plate top and bottom. Size (14" x 9" x 1.75")	Cu. Inch	304.64	72.00
8	Borrowpit excavation undressed lead upto 100 ft (30 metre). Ordinary soil	1000 Cft	30,345.00	10,533.60
9	Cement plaster 1:3 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Cft	5,976.00	4,850.40
10	Providing and laying R.C.C. pipe sewers, moulded with cement concrete 4000 psi conforming to ASTM Specification C-76-20, Class II. Wall B, including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade, jointing with rubber ring, cutting pipes where necessary, testing, etc., complete. 610 mm (24") i/d	1 Rft	320.00	2,150.35
11	Providing and laying sub base course.	100 Cft	2,100.00	10,003.50
12	Providing and laying base course.	100 Cft	2,100.00	13,527.40
13	Providing surface treatment to roads, including supply of bitumen and bujri /crushed stone aggregate of approved quality, including cleaning of road surface, heating and spraying bitumen, spreading bajri and rolling with road roller (including its operation cost, fuel and hire charges, etc.) etc. complete including carriage of all materials to site of work except bajri/crushed stone aggregate.	100 Sft	2,800.00	4,549.95
14	Dismantling cement concrete reinforced, separating reinforcement from concrete, cleaning and straightening the same.	100 Cft	11,823.77	27,086.40

15	Credit old material	1 Kg	(23,647.54)	170.00
Total cost:				
vi. Pump House No: 3 (Manthar Drain at 0+000 RD)				
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	60,639.35	12,735.60
2	Extra for slush or Daldal including dewatering. Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)	1000 Cft	60,639.35	12,038.40
3	a) Nominal mix ratio 1:4:8	100 Cft	2,087.74	34,694.30
4	b) Nominal mix ratio 1:2:4	100 Cft	1,164.38	47,135.90
5	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	117,054.47	30,376.90
6	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	16,160.05	817.55
7	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	9,852.05	670.50
8	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	6,041.91	1,645.10
9	Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sand blinded.	100 Sft	1,758.15	13,179.60
10	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	1,758.15	11.00
11	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	144.00	514.90
12	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	12.00	849.70
13	Making top khurra on roof 2' x 2' x 6".	1 No	6.00	1,159.65
14	Providing and fixing windows consisting of M.S. box section frame 2"x1½", (50x40mm) leaves frame 1½"x1" (40x25mm) box section frame for glazing 3/8"x3/8" (10x10mm) using 16 SWG sheet 'U' shaped rubber supported with 1"x1/8" (25x3mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section ½"x½" (13x13mm) of 16 SWG for fixing 24 SWG wire gauze on outer side by means of ¾"x1/8" (20x3mm) M.S. flat and screws including grill of M.S. flat ½"x1/8" (13x3mm) or ¼"x¼" (6x6mm) square bar with independent frame of ½"x½" (13x13mm) box section of 16 SWG i/c all C.P. fitting and painting 3 coats complete in all respect.	1	607.92	2,180.70
15	Making and fixing steel grated door with 1/16" thick 1.5mm) sheeting, including angle iron frame 2"x2"x3/8" (50x50x10 mm) and ¾" (20 mm) square bars 4" (100 mm)	1 Sft	196.00	2,767.00
16	Distempering:- 2 coats	100 Sft	5,921.95	1,212.35
17	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	5,355.00	7,379.10

18	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	356.00	3,052.40
19	Providing and fixing 1¼x1¼"x3/16" (31x31x5 mm) angle" iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	1 No	99.00	680.75
21	Providing and fixing trash rack as per drawing	1 Sft	1,368.00	603.00
22	Providing and laying Tuff Pavers, having 7000PSI ,crushing strength of approved manufa cturer, over 2"to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope . complete in all respect. (50% Grey / 50% Coloured) 60-mm thick	1 Sft	2,738.75	205.40
23	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	738.42	18,017.60
24	1½"(40 mm) thick mosaic flooring, consisting of ½ " mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1"(25 mm) thick floor of 1:2:4 cement concrete, including rubbing and polishing complete with finishing :-using grey cement	100 Sft	1,758.15	29,658.50
25	Mosaic dado or skirting with one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over ½"(13 mm) thick cement plaster 1:3, including rubbing and polishing, complete with finishing:(a) using grey cement: i) 1/2"(13 mm) thick	100 Sft	112.84	19,146.85
26	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels(a) Size 1½" x 3/8" (40 x 10 mm)	1 Rft	900.26	39.60
27	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	473.50	809.40
28	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.			
	a) 20mm (3/4") i/d.	1 Rft	500.00	112.25
	b) 25 mm (1") i/d	1 Rft	300.00	133.60
29	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only)			
	(a) 250/440 volts, P.V.C. insulated.			
	a) 3/0.74mm (3/0.029").	1 Rft	1,000.00	35.70
	b) 7/0.74mm (7/0.029").	1 Rft	500.00	56.30
30	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.			
	b) 17.5 x 10 cm (7" x 4").	1 Each	10.00	522.75
31	Supply and erection of switches 5 amp. Piano Type.	1 Each	50.00	102.70
32	Supply and erection of backlite button holder shade, large size.	1 Each	15.00	178.75
33	Supply and erection of ceiling rose, bakelite.	1 Each	15.00	96.30
34	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire completb) Double Pole(iii) 6-63 Amp (10 KA)	1 No	1.00	5,616.25
35	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	10.00	1,453.75
36	Providing and fixing Pakistan Energy Label NEECA approved Copper winded wall bracket Fan i/c the cost of necessary cable and hardware for connection as approved and directed by Engineer Incharge.ii) 24" Sweep dia	1 Each	10.00	11,398.45
37	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	15.00	1,995.30
Stone Pitching Work				

38	Earthwork in excavation of drains in irrigation channels through excavator / draglines in all kind of soil and conditions	1000 Cft	275,894.18	4,640.70
39	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	10,945.44	6,849.00
40	Formation dressing and preparing subgrade, on slope	100 Sft	6,058.72	2,265.10
41	Formation dressing and preparing subgrade, in bed.	100 Sft	594.66	1,660.50
42	Providing & laying graded bajri ⅛" to ½" gauge on slope (including carriage).	100 Cft	2,001.64	18,564.10
43	Providing & laying graded bajri ½" to 2" gauge on slope (including carriage).	100 Cft	2,001.64	18,564.10
44	Providing & laying graded bajri ⅛" to ½" gauge on level (including carriage).	100 Cft	196.42	18,017.60
45	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	196.42	18,017.60
46	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	6,058.72	11,511.00
47	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	594.66	10,570.50
48	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 275Km.(From Sakhi Sarwar)	100 Cft	47,639.45	14,042.60
Total Cost				

vii. Tube Well room

1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil. 1) By Manual	1000 Cft	2,724.46	15,824.15
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextar or equivalent @ specified suspension concentrate (SC), Mixing Ability-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for 10-years complete in all respect as approved by the Engineer Incharge.	1 Sft	2,542.50	12.55
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	528.06	34,694.30
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	1,575.20	32,675.95
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythene sheet 500 gauge 1½" thick (40 mm).	100 Sft	322.50	11,460.20
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	600.00	7,607.35
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	750.00	7,547.75
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	1,454.50	35,830.60
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:2:4)	1 Cft	770.83	741.85
10	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work (i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	92.04	595.00

11	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	5,177.21	30,376.90
12	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	160.00	2,180.70
13	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	200.00	457.10
14	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	245.00	2,767.00
15	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	477.81	13,179.60
16	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	497.81	11.00
17	Supplying and filling sand under floor or plugging in wells.	100 Cft	204.69	3,987.00
18	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	244.69	12,801.20
19	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) b) Nominal mix ratio 1:2:4	100 Cft	229.30	47,135.90
20	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	2,841.53	4,614.10
21	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	572.60	5,264.65
22	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	2,449.38	5,012.65
23	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	65.00	514.90
24	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	10.00	849.70
25	Making top khurra on roof 2' x 2' x 6".	1 No	5.00	1,159.65
26	Distempering:- 3 coat	100 Sft	2,551.35	1,548.20
27	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	862.78	7,379.10
28	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	445.00	3,052.40
29	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, revitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	1,674.79	37,098.85
30	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.		-	-
	a) 20mm (3/4") i/d.	1 Rft	300.00	112.25
	b) 25 mm (1") i/d	1 Rft	150.00	133.60
	c) 50 mm (2") i/d	1 Rft	75.00	231.55

31	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pipe/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated. a) 3/0.74mm (3/0.029"). b) 7/0.74mm (7/0.029").	1 Rft 1 Rft	900.00 300.00	35.70 56.30
32	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only) (a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).	1 Rft	200.00	237.65
33	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc. a) 10 x 10 cm (4" x 4"). b) 17.5 x 10 cm (7" x 4"). c) 22.5 x 10 cm (9" x 4").	- 1 Each 1 Each 1 Each	- 5.00 5.00 5.00	- 382.30 522.75 668.80
34	Supply and erection of switches 5 amp. Piano Type.	1 Each	100.00	102.70
35	Supply and erection of ceiling rose, bakelite.	1 Each	20.00	96.30
36	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	10.00	204.70
37	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	5.00	213.10
38	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessed/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Neutral & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	5.00	24,422.65
39	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	30.00	1,453.75
40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaidd DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole (ii) 15-100 Amp (10 KA,15KA)	1 No	10.00	13,796.30
41	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaidd DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	5.00	19,859.40
42	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)singlerod (40 watts) with one choke and one starter.	1 No	15.00	1,995.30
43	Supply and erection of bakelite button holder shade, large size	1 No	15.00	178.75
44	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	506.94	14,042.60
ii	PCC 1:2:4	100 Cft	201.78	14,042.60
iii	RCC 1.2.4	100 Cft	759.32	14,042.60
iv	DPC 1.2.4	100 Cft	35.48	14,042.60

				Total Cost:
Total Cost for Section-5 (Manthar Drain)				
6. Khanpur Drain (RD 0+000 to 84+000)				
i. Earthwork				
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	10,154,747.50	4,640.70
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	4,167,935.00	940.90
	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft.			
3	a) 500 ft	1000 Cft	100,405.00	1,073.20
	b) 750 ft	1000 Cft	9,912.50	1,743.95
	c) 1000 ft	1000 Cft	24,562.50	2,414.70
	d) 1250 ft	1000 Cft	33,180.00	6,677.80
	e) 1500 ft	1000 Cft	79,555.00	6,751.20
	f) 2500 ft	1000 Cft	53,390.00	6,971.40
	g) 3750 ft	1000 Cft	187,560.00	7,191.60
4	Making boundary or service roads, including dag-belling, leveling and dressing:ii) in ploughed land: a) from 10.0 ft. to 20.0 ft. (3 to 6 m) wide	1 - Chain	45.00	1,935.40
5	Jungle clearance and removing within 100 ft. light	1000 Sft	1,680,000.00	376.20
ii. Data Board:				
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	24.50	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.50	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.00	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortor ratio 1:3	100 Cft	81.70	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.65	4,334.75
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.65	7,379.10
8	Writing letter or figures per letter per inch height	1 No	500.00	30.50
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
	DPC	100 Cft	4.29	14,042.60
iii. RD Marks:				
1	Precast reinfoced cement concrete type "C" 1:2:4.	1 Cft	146.20	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	334.05	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	85.00	115.40
4	Placing boundary pillars in position, including digging pits.	1 Each	85.00	141.90
5	Preparing surface and painting with emulation paint 3 coat.	100 Sft	297.50	4,307.55
6	Writing letter or firgures per letter per inch height (three figure each side).	1 No	850.00	30.50
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			

ii	PCC 1:2:4	100 Cft	128.66	14,042.60
Total Cost :				
iv. VRB Repair				
1	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	100 Cft	976.25	47,135.90
2	Cement plaster 1:3 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Cft	4,140.00	4,850.40
Total Cost :				
Total Cost of Section -6 (Khanpur Drain)				
7. D-1 Drain (RD 0+000 to 38+250)				
i. Earthwork				
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinery. (rates includes 100ft lead)	1000 Cft	19,380,715.75	4,640.70
2	Transportation of earth all types when the total distance, including the lead covered in the item of work. b) Lead 500 feet	1000 Cft	10,945.75	1,073.20
3	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	5,396,103.75	940.90
4	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	390.00	1,326.20
ii. Data Board				
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	24.50	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.50	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.00	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.70	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.65	4,334.75
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.65	7,379.10
8	Writing letter or figures per letter per inch height	1 No	500.00	30.50
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.29	14,042.60
iii. RD Marks:				
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	67.08	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	153.27	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	39.00	115.40
4	Placing boundary pillars in position, including digging pits.	1 Each	39.00	141.90
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	136.50	4,307.55
6	Writing letter or figures per letter per inch height (three figure each side). Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.	1 No	390.00	30.50
7				

ii	PCC 1:2:4	100 Cft	59.03	14,042.60
Total Cost :				
iv. Water Course				
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	17,227.97	12,735.60
2	Extra for slush or Daldal including dewatering.	1000 Cft	17,227.97	12,038.40
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8 b) Nominal mix ratio 1:2:4	100 Cft 100 Cft	1,464.43 187.00	34,694.30 47,135.90
4	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	44,509.40	30,376.90
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3) b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	10,355.41	817.55
6	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	6,197.88	1,645.10
7	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	440.00	35,727.00
8	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	1,425.38	809.40
9	Providing and placing poly sulphide joint sealent 1" wide and 1" deep.	1 Rft	450.00	1,381.00
10	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	22,000.00	5,266.80
11	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	1,405.85	14,042.60
ii	PCC 1:2:4	100 Cft	164.56	14,042.60
iii	RCC 1.1.5.3	100 Cft	12,462.63	14,042.60
Total Cost:				
v. Culverts				
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	91,276.02	12,735.60
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	1,441.50	34,694.30

3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	71,071.98	30,376.90
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	17,924.66	817.55
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	5,766.00	670.50
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	16,855.64	1,645.10
6	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 80mm dia (3 inch)	1 Rft	60.00	303.80
7	Providing and laying sub-base course of stone productof approved quality and grade, including placing, mixing, spreading and compaction of sub-base material torequired depth, camber, grade to achieve 100% maximum modified AASHO dry density, including carriage of all material to site of work except gravel and aggregate. Crushed stone aggregate.	100 Cft	480.00	10,003.50
8	Providing and laying base course of crushed stone aggregate of approved quality and grade, and supply and spreading of stone screening, including placing, mixing,spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHO dry density, including carriage of all materials to site of work except gravel and aggregate.	100 Cft	480.00	13,527.40
9	Providing and laying road edging of 3" (75 mm) wide and	1 Rft	160.00	64.20
10	Providing surface treatment of roads,including supply of bitumen and bajri/crushed stone aggregate of approved quality,including cleaning of road surface,heating,spraying bitumen,spreading bajri and rollingetc.complete including carriageof all material stosite of work excep tbajri/crushed stone aggregate for which supplywithin 3miles(5.0km)isincluded in the rate.			
a	1st coat 35 lbs. bitumen, and 4 Cft. bajri of nominal size 1" (25 mm) per 100 sq. feet or 1.72 Kg bitumen and 0.017 cu.metre bajri per square metre..	100 Sft	960.00	4,549.95
b	2nd coat 18 lbs. bitumen, and 2 Cft. bajri of nominal size ½" (13 mm) per %sft or 1.23 Kg bitumen and 0.008 cu. metre bajri per sq.metre.	100 Sft	960.00	2,639.45
c	3rd coat 14 lbs. bitumen, and 1.5 Cft. bajri of nominal size ¼" (6 mm) per %sft or 0.69 Kg bitumen and 0.005 cubic metre bajjri per sq.metre.	100 Sft	960.00	1,960.75
11	Dismantling and removing road pavement, etc.,including screening and stacking of byproducts upto one chain lead (30 metre).	100 Cft	960.00	4,017.80
12	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	9,600.00	10,533.60
13	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	54,240.00	5,266.80
14	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			

i	PCC 1:4:8	100 Cft	1,383.84	14,042.60
ii	RCC 1:1.5:3	100 Cft	19,900.15	14,042.60
iii	Base	100 Cft	585.60	14,042.60
iii	T.S.T	100 Cft	72.00	14,042.60
				Total Cost
vii. Pump House No: 4 (D-1 Drain at RD 0+100)				
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	44,596.77	12,735.60
2	Extra for slush or Daldal including dewatering. Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)	1000 Cft	44,596.77	12,038.40
3	a) Nominal mix ratio 1:4:8	100 Cft	971.79	34,694.30
4	b) Nominal mix ratio 1:2:4	100 Cft	501.68	47,135.90
5	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars).Deformed Bars (Grade 60)	100 Kg	63,787.43	30,376.90
6	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	9,101.68	817.55
7	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect Type B (Nominal Mix 1:1.5:3)	1 Cft	5,073.31	670.50
8	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	5,294.22	1,645.10
9	Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sand blinded.	100 Sft	997.54	13,179.60
10	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	997.54	11.00
11	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	111.00	514.90
12	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	6.00	849.70
13	Making top khurra on roof 2' x 2' x 6".	1 No	6.00	1,159.65
14	Providing and fixing windows consisting of M.S. box section frame 2"x1½", (50x40mm) leaves frame 1½"x1" (40x25mm) box section frame for glazing 3/8"x3/8" (10x10mm) using 16 SWG sheet 'U' shaped rubber supported with 1"x1/8" (25x3mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section ½"x½" (13x13mm) of 16 SWG for fixing 24 SWG wire gauze on outer side by means of ¾"x1/8" (20x3mm) M.S. flat and screws including grill of M.S. flat ½"x1/8" (13x3mm) or ¼"x¼" (6x6mm) square bar with independent frame of ½"x½" (13x13mm) box section of 16 SWG i/c all C.P. fitting and painting 3 coats complete in all respect.	1 Sft	367.92	2,180.70
15	Making and fixing steel grated door with 1/16" thick 1.5mm) sheeting, including angle iron frame 2"x2"x3/8" (50x50x10 mm) and ¾" (20 mm) square bars 4" (100 mm)	1 Sft	176.00	2,767.00

16	Distempering:- 2 coats	100 Sft	3,581.60	1,212.35
17	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	3,896.51	7,379.10
18	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	336.00	3,052.40
19	Providing and fixing 1½"x1¼"x3/16" (31x31x5 mm) angle" iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	1 No	64.00	680.75
20	Providing/fixing stair railing consisting of M.S. Box section size 1-1/2"x3" of 16 SWG welded with M.S. flat 1"x1/8" continuously and welded over M.S. square bars 5/8"x5/8"punched in M.S. flat 2 ¾' high @ 5½" c/c fixed in steps of stair I/C painting 3 coats complete.	1 Rft	71.86	1,125.20
21	Providing and fixing trash rack as per drawing	1 Sft	368.00	603.00
22	Providing and laying Tuff Pavers, having 7000PSI ,crushing strength of approved manufa cturer, over 2"to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope . complete in all respect. (50% Grey / 50% Coloured) 60-mm thick	1 Sft	1,682.75	205.40
23	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	418.97	18,017.60
24	1½"(40 mm) thick mosaic flooring, consisting of ½ " mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1"(25 mm) thick floor of 1:2:4 cement concrete, including rubbing and polishing complete with finishing :-using grey cement	100 Sft	997.54	29,658.50
25	Mosaic dado or skirting with one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over ½"(13 mm) thick cement plaster 1:3, including rubbing and polishing, complete with finishing:(a) using grey cement:	100 Sft	72.10	19,146.85
26	i) 1/2"(13 mm) thick Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels(a) Size 1½" x 3/8" (40 x 10 mm)	1 Rft	519.15	39.60
27	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	236.66	809.40
28	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.			
	a) 20mm (3/4") i/d.	1 Rft	150.00	112.25
	b) 25 mm (1") i/d	1 Rft	150.00	133.60
29	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and caping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated. a) 3/0.74mm (3/0.029"). b) 7/0.74mm (7/0.029").	1 Rft 1 Rft	500.00 300.00	35.70 56.30
30	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc. b) 17.5 x 10 cm (7" x 4").	1 Each	5.00	522.75
31	Supply and erection of switches 5 amp. Piano Type.	1 Each	35.00	102.70
32	Supply and erection of backlite button holder shade, large size.	1 Each	10.00	178.75
33	Supply and erection of ceiling rose, bakelite.	1 Each	10.00	96.30
34	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire completb) Double Pole(iii) 6-63 Amp (10 KA)	1 No	1.00	5,616.25
35	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	5.00	1,453.75

36	Providing and fixing Pakistan Energy Label NEECA approved Copper winded wall bracket Fan i/c the cost of necessary cable and hardware for connection as approved and directed by Engineer Incharge.ii) 24" Sweep dia	1 Each	6.00	11,398.45
37	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	10.00	1,995.30
<u>Lining Portion</u>				
38	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	34,138.38	10,533.60
39	Compaction of earth work with power Road Roller, i.c ploughing mixing, moistening earth to optimum moisture content in layer etc; complete 90 % maximum modified AASHO dry denisty	1000 Cft	34,138.38	1,437.50
40	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed off undressed within 50 ft. (15 m) lead:- ordinary Soil	1000 Cft	5,910.30	5,033.70
41	Cement plaster 1.5" (40 mm) thick ratio 1:6:- a) In bed	100 Sft	1,100.00	6,512.05
42	b) On slope	100 Sft	1,540.00	7,363.45
43	Cement concrete lining, using washed screened and graded stone aggregate:- a) In bed, ratio 1:2:4	100 Cft	376.75	49,016.90
44	b) On slope, ratio 1:2:4	100 Cft	527.45	51,301.80
45	Providing and placing cement, sand and bituminous joint sealant in ratio 1:2:3, 1/2" wide, 1" deep.	1 Rft	264.00	17.30
46	Bitumen coating to plastered or cement concrete surface:- 10 lbs. per 100 Sft.	100 Sft	132.00	1,539.80
<u>Stone Pitching Work</u>				
47	Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000 Cft	10,137.19	4,640.70
48	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	10,137.19	6,849.00
49	Formation dressing and preparing subgrade, on slope	100 Sft	3,737.05	2,265.10
50	Formation dressing and preparing subgrade, in bed.	100 Sft	631.16	1,660.50
51	Providing & laying graded bajri 1/8" to 1/2" gauge on slope (including carriage).	100 Cft	1,233.60	18,564.10
52	Providing & laying graded bajri 1/2" to 2" gauge on slope (including carriage).	100 Cft	1,233.60	18,564.10
53	Providing & laying graded bajri 1/8" to 1/2" gauge on level (including carriage).	100 Cft	208.28	18,017.60
54	Providing & laying graded bajri 1/2" to 2" gauge on level (including carriage).	100 Cft	208.28	18,017.60
55	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	3,738.19	11,511.00
56	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	631.16	10,570.50
57	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 275Km.(From Sakhi Sarwar)	100 Cft	33,005.50	14,042.60
				Total Cost

viii. Inlets

1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m)and lift upto 5' (1.5 m) (b) in ordinary soil. By Manual	1000 Cft	14,140.76	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8 b) Nominal mix ratio 1:2:4	100 Cft 100 Cft	1,744.52 180.37	34,694.30 47,135.90
3	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	2,798.89	35,727.00

4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3) b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	2,377.13	817.55
5	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	9,601.88	30,376.90
6	Providing and laying dry, hand packed stone apron as per drawing	100 Cft	4,464.84	6,849.00
7	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	4,880.00	5,266.80
8	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	1,674.74	14,042.60
i	PCC 1:2:4	100 Cft	158.72	14,042.60
ii	RCC 1:1.5:3	100 Cft	2,688.53	14,042.60
iii	Dry Hand Pack Stone	100 Cft	6,027.53	14,042.60
Total Cost:				

ix. Tube Well room

1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m)and lift upto 5' (1.5 m) (b) in ordinary soil.1)By Manual	1000 Cft	6,538.70	15,824.15
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextaror equivalent@specified suspension concentrate (SC), MixingAbility-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for10-years complete in all respect.as approved by the Engineer Incharge.	1 Sft	6,102.00	12.55
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	1,267.35	34,694.30
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	3,780.48	32,675.95
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythenesheet 500 gauge 1½" thick (40 mm).	100 Sft	774.00	11,460.20
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	1,440.00	7,607.35
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	1,800.00	7,547.75
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	3,490.80	35,830.60

9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)		-	
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:2:4)	1 Cft	1,849.99	741.85
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	220.89	595.00
10	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	12,425.30	30,376.90
11	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	384.00	2,180.70
12	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	480.00	457.10
13	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	588.00	2,767.00
14	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	1,146.75	13,179.60
15	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	1,194.75	11.00
16	Supplying and filling sand under floor or plugging in wells.	100 Cft	491.25	3,987.00
17	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	587.25	12,801.20
18	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) b) Nominal mix ratio 1:2:4	100 Cft	-	-
19	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	6,819.66	4,614.10
20	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	1,374.24	5,264.65
21	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	5,878.50	5,012.65
22	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	156.00	514.90
23	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	24.00	849.70

24	Making top khurra on roof 2' x 2' x 6".	1 No	12.00	1,159.65
25	Distempering:- 3 coat	100 Sft	6,123.24	1,548.20
26	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	2,070.66	7,379.10
27	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	1,068.00	3,052.40
28	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, rebitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	4,019.50	37,098.85
29	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.		-	-
	a) 20mm (3/4") i/d.	1 Rft	720.00	112.25
	b) 25 mm (1") i/d	1 Rft	360.00	133.60
	c) 50 mm (2") i/d	1 Rft	180.00	231.55
30	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pipe/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only)		-	-
	(a) 250/440 volts, P.V.C. insulated.			
	a) 3/0.74mm (3/0.029").	1 Rft	2,160.00	35.70
	b) 7/0.74mm (7/0.029").	1 Rft	720.00	56.30
31	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only)	1 Rft	480.00	237.65
	(a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).			
32	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.		-	-
	a) 10 x 10 cm (4" x 4").	1 Each	12.00	382.30
	b) 17.5 x 10 cm (7" x 4").	1 Each	12.00	522.75
	c) 22.5 x 10 cm (9" x 4").	1 Each	12.00	668.80
33	Supply and erection of switches 5 amp. Piano Type.	1 Each	240.00	102.70
34	Supply and erection of ceiling rose, bakelite.	1 Each	48.00	96.30
35	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	24.00	204.70
36	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	12.00	213.10
37	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessed/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Neutral & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	12.00	24,422.65
38	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	72.00	1,453.75
39	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaidd DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole (ii) 15-100 Amp (10 KA,15KA)	1 No	24.00	13,796.30

40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker) of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (with fixed Thermal-Magnetic Trip) in pre-laid DB and Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the Engineer in charge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	12.00	19,859.40
41	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii) single rod (40 watts) with one choke and one starter.	1 No	36.00	1,995.30
42	Supply and erection of bakelite button holder shade, large size	1 No	36.00	178.75
43	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.	-	-	-
i	PCC 1:4:8	100 Cft	1,216.66	14,042.60
ii	PCC 1:2:4	100 Cft	484.28	14,042.60
iii	RCC 1:2:4	100 Cft	1,822.38	14,042.60
iv	DPC 1:2:4	100 Cft	85.14	14,042.60

Total Cost :

Total Cost of Section-7 (D-1 Drain)

8. D-1 Sub Drain (RD 0+000 to 13+250)

i. Earthwork

1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preparation of working pad for operation of machinery. (rates includes 100ft lead)	1000 Cft	4,710,315.00	4,640.70
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	2,201,861.25	940.90
3	Transportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft.			
	a) Lead 500 feet	1000 Cft	17,267.50	1,073.20
4	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	130.00	1,326.20

ii. Data Board:

1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	24.50	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.50	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.00	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.70	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.65	4,334.75
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.65	7,379.10
8	Writing letter or figures per letter per inch height	1 No	500.00	30.50
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			

	DPC	100 Cft	4.29	14,042.60
iii. RD Marks:				
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	22.36	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	51.09	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	13.00	115.40
4	Placing boundary pillars in position, including digging pits.	1 Each	13.00	141.90
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	45.50	4,307.55
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	130.00	30.50
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
ii	PCC 1:2:4	100 Cft	19.68	14,042.60
				Total Cost
iv. Water Course				
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	6,436.05	12,735.60
2	Extra for slush or Daldal including dewatering.	1000 Cft	6,436.05	12,038.40
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			
	a) Nominal mix ratio 1:4:8	100 Cft	529.73	34,694.30
	b) Nominal mix ratio 1:2:4	100 Cft	68.00	47,135.90
4	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	16,212.10	30,376.90
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	3,788.50	817.55
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	1,615.53	670.50
6	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	2,288.87	1,645.10
7	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	160.00	35,727.00
8	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	518.00	809.40
9	Providing and placing poly sulphide joint sealant 1" wide and 1" deep.	1 Rft	160.00	1,381.00
10	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	8,000.00	5,266.80
11	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			

i	PCC 1:4:8	100 Cft	508.54	14,042.60
ii	PCC 1:2:4	100 Cft	59.84	14,042.60
iii	RCC 1.1.5.3	100 Cft	4,539.39	14,042.60
				Total Cost:
v. Culverts				
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	36,435.20	12,735.60
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	510.00	34,694.30
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	26,990.40	30,376.90
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast	1 Cft	6,956.80	817.55
a)	laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)			
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	2,040.00	670.50
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	7,707.60	1,645.10
6	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 80mm dia (3 inch)	1 Rft	22.50	303.80
7	Providing and laying sub-base course of stone productof approved quality and grade, including placing, mixing, spreading and compaction of sub-base material torequired depth, camber, grade to achieve 100% maximum modified AASHO dry density, including carriage of all material to site of work except gravel and aggregate. Crushed stone aggregate.	100 Cft	180.00	10,003.50
8	Providing and laying base course of crushed stone aggregate of approved quality and grade, and supply and spreading of stone screening, including placing, mixing,spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHO dry density, including carriage of all materials to site of work except gravel and aggregate.	100 Cft	180.00	13,527.40
9	Providing and laying road edging of 3" (75 mm) wide and	1 Rft	60.00	64.20
10	Providing surface treatment of roads,including supply of bitumen and bajri/crushed stone aggregate of approved quality,including cleaning of road surface,heating,spraying bitumen,spreading bajri and rollingetc.complete including carriageof all material stosite of work excep tbajri/crushed stone aggregate for which supplywithin 3miles(5.0km)isincluded in the rate.			
a)	1st coat 35 lbs. bitumen, and 4 Cft. bajri of nominal size 1" (25 mm) per 100 sq. feet or 1.72 Kg bitumen and 0.017 cu.metre bajri per square metre..	100 Sft	360.00	4,549.95
b)	2nd coat 18 lbs. bitumen, and 2 Cft. bajri of nominal size ½" (13 mm) per %sft or 1.23 Kg bitumen and 0.008 cu. metre bajri per sq.metre.	100 Sft	360.00	2,639.45

c)	3rd coat 14 lbs. bitumen, and 1.5 Cft. bajri of nominal size ¼" (6 mm) per %sft or 0.69 Kg bitumen and 0.005 cubic metre bajri per sq.metre.	100 Sft	360.00	1,960.75
11	Dismantling and removing road pavement, etc.,including screening and stacking of byproducts upto one chain lead (30 metre).	100 Cft	360.00	4,017.80
12	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	3,200.00	10,533.60
13	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	20,960.00	5,266.80
14	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	489.60	14,042.60
ii	RCC 1:1.5:3	100 Cft	7,557.31	14,042.60
iii	Base	100 Cft	219.60	14,042.60
iii	T.S.T	100 Cft	27.00	14,042.60
Total Cost				

vi. Stone Pitching

1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	269.25	4,640.70
2	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons.	100 Cft	269.25	6,849.00
3	Formation dressing and preparing subgrade, on slope	100 Sft	480.69	2,265.10
4	Formation dressing and preparing subgrade, in bed.	100 Sft	126.00	1,660.50
5	Providing and laying graded bajri 1/8" to 1/2" size on slope.	100 Cft	158.63	18,564.10
6	Providing and laying graded bajri 1/2" to 2" size on slope.	100 Cft	158.63	18,564.10
7	Providing and laying graded bajri 1/8" to 1/2" size on level.	100 Cft	41.58	18,017.60
8	Providing and laying graded bajri 1/2" to 2" size on level.	100 Cft	41.58	18,017.60
9	Providing and laying stone for top layer only, on slope.	100 Cft	480.69	11,511.00
10	Providing and laying stone for top layer only, on Level	100 Cft	126.00	10,570.50
11	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc or 150 Cft of timber by truck or by any other means owned by the contractor, lead 275 Km.	100 Cft	1,091.52	14,042.60
Total Cost				

vii. Inlets

1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m)and lift upto 5' (1.5 m) (b) in ordinary soil. By Manual	1000 Cft	3,514.66	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	463.39	34,694.30
	b) Nominal mix ratio 1:2:4	100 Cft	48.10	47,135.90
3	Pacca brick work other than buildings upto 10 feet height.	100 Cft	746.37	35,727.00
4	Cement sand mortar ratio 1:4 Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	625.50	817.55

	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	216.00	670.50
5	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	2,524.50	30,376.90
6	Providing and laying dry, hand packed stone apron as per drawing	100 Cft	949.99	6,849.00
14	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	1,280.00	5,266.80
15	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	444.85	14,042.60
i	PCC 1:2:4	100 Cft	42.33	14,042.60
ii	RCC 1:1.5:3	100 Cft	706.86	14,042.60
iii	Dry Hand Pack Stone	100 Cft	1,282.48	14,042.60
Total Cost				

viii. Tube Well room

1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m)and lift upto 5' (1.5 m) (b) in ordinary soil.1)By Manual	1000 Cft	544.89	15,824.15
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextaror equivalent@specified suspension concentrate (SC), MixingAbility-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for10-years complete in all respect.as approved by the Engineer Incharge.	1 Sft	508.50	12.55
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	105.61	34,694.30
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	315.04	32,675.95
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythenesheet 500 gauge 1½" thick (40 mm).	100 Sft	64.50	11,460.20
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	120.00	7,607.35
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	150.00	7,547.75
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	290.90	35,830.60
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:2:4)	1 Cft	154.17	741.85
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	18.41	595.00

11	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	1,035.44	30,376.90
12	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	32.00	2,180.70
13	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	40.00	457.10
14	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	49.00	2,767.00
15	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	95.56	13,179.60
16	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	99.56	11.00
17	Supplying and filling sand under floor or plugging in wells.	100 Cft	40.94	3,987.00
18	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	48.94	12,801.20
19	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) b) Nominal mix ratio 1:2:4	100 Cft	45.86	47,135.90
20	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	568.31	4,614.10
21	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	114.52	5,264.65
22	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	489.88	5,012.65
23	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	13.00	514.90
24	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	2.00	849.70
25	Making top khurra on roof 2' x 2' x 6".	1 No	1.00	1,159.65
26	Distempering:- 3 coat	100 Sft	510.27	1,548.20
27	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	172.56	7,379.10
28	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	89.00	3,052.40
29	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, revitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	334.96	37,098.85
30	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.			-
	a) 20mm (3/4") i/d.	1 Rft	60.00	112.25
	b) 25 mm (1") i/d	1 Rft	30.00	133.60
	c) 50 mm (2") i/d	1 Rft	15.00	231.55

31	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pipe/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated. a) 3/0.74mm (3/0.029"). b) 7/0.74mm (7/0.029").	1 Rft 1 Rft	180.00 60.00	35.70 56.30
32	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only) (a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).	1 Rft	40.00	237.65
33	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc. a) 10 x 10 cm (4" x 4"). b) 17.5 x 10 cm (7" x 4"). c) 22.5 x 10 cm (9" x 4").	1 Each 1 Each 1 Each	1.00 1.00 1.00	382.30 522.75 668.80
34	Supply and erection of switches 5 amp. Piano Type.	1 Each	20.00	102.70
35	Supply and erection of ceiling rose, bakelite.	1 Each	4.00	96.30
36	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	2.00	204.70
37	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	1.00	213.10
38	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessed/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	1.00	24,422.65
39	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	6.00	1,453.75
40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaidd DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole (ii) 15-100 Amp (10 KA,15KA)	1 No	2.00	13,796.30
41	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaidd DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	1.00	19,859.40
42	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	3.00	1,995.30
43	Supply and erection of bakelite button holder shade, large size	1 No	3.00	178.75
44	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	101.39	14,042.60
ii	PCC 1:2:4	100 Cft	40.36	14,042.60

iii	RCC 1.2.4	100 Cft	151.86	14,042.60
iv	DPC 1.2.4	100 Cft	7.10	14,042.60
Total Cost :				
Total Cost for Section-8 (D-1 Sub Drain)				
9. D-2 Drain (RD 0+000 to 12+615)				
i. Earthwork				
1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	2,187,776.70	4,640.70
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	1,607,647.35	940.90
3	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft.			
	a) 500 ft	1000 Cft	1,752.50	1,073.20
	b) 750 ft	1000 Cft	16,955.00	1,743.95
	c) 3000 ft	1000 Cft	97,028.25	7,051.47
7	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	104.00	3,045.61
ii. Data Board:				
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	24.50	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.50	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.00	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.70	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.65	4,334.75
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.65	7,379.10
8	Writing letter or figures per letter per inch height	1 No	500.00	30.50
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
	DPC	100 Cft	4.29	14,042.60
iii. RD Marks:				
1	Precast reinfoced cement concrete type "C" 1:2:4.	1 Cft	22.36	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	51.09	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	13.00	115.40
4	Placing boundary pillars in position, including digging pits.	1 Each	13.00	141.90
5	Preparing surface and painting with emulation paint 3 coat.	100 Sft	45.50	4,307.55
6	Writing letter or firgures per letter per inch height (three figure each side).	1 No	130.00	30.50
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
ii	PCC 1:2:4	100 Cft	19.68	14,042.60
Total Cost				

iv. Water Course				
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	12,395.41	12,735.60
2	Extra for slush or Daldal including dewatering.	1000 Cft	12,395.41	12,038.40
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	1,410.74	34,694.30
	b) Nominal mix ratio 1:2:4	100 Cft	187.00	47,135.90
4	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	35,906.24	30,376.90
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	7,756.14	817.55
	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	4,212.61	670.50
6	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	4,687.73	1,645.10
7	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	440.00	35,727.00
8	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	1,098.74	809.40
9	Providing and placing poly sulphide joint sealent 1" wide and 1" deep.	1 Rft	380.00	1,381.00
10	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	22,000.00	5,266.80
11	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	1,354.31	14,042.60
ii	PCC 1:2:4	100 Cft	164.56	14,042.60
iii	RCC 1.1.5.3	100 Cft	10,053.75	14,042.60
				Total Cost

v. Culverts				
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	29,517.98	12,735.60
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	768.00	34,694.30
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	29,348.94	30,376.90

4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3) b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	6,710.98	817.55
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	6,537.28	1,645.10
6	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 80mm dia (3 inch)	1 Rft	31.50	303.80
7	Providing and laying sub-base course of stone product of approved quality and grade, including placing, mixing, spreading and compaction of sub-base material to required depth, camber, grade to achieve 100% maximum modified AASHO dry density, including carriage of all material to site of work except gravel and aggregate. Crushed stone aggregate.	100 Cft	300.00	10,003.50
8	Providing and laying base course of crushed stone aggregate of approved quality and grade, and supply and spreading of stone screening, including placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHO dry density, including carriage of all materials to site of work except gravel and aggregate.	100 Cft	300.00	13,527.40
9	Providing and laying road edging of 3" (75 mm) wide and	1 Rft	60.00	64.20
10	Providing surface treatment of roads, including supply of bitumen and bajri/crushed stone aggregate of approved quality, including cleaning of road surface, heating, spraying bitumen, spreading bajri and rolling etc. complete including carriage of all material to site of work except bajri/crushed stone aggregate for which supply within 3 miles (5.0 km) is included in the rate.			
a	1st coat 35 lbs. bitumen, and 4 Cft. bajri of nominal size 1" (25 mm) per 100 sq. feet or 1.72 Kg bitumen and 0.017 cu. metre bajri per square metre..	100 Sft	600.00	4,549.95
b	2nd coat 18 lbs. bitumen, and 2 Cft. bajri of nominal size ½" (13 mm) per %sft or 1.23 Kg bitumen and 0.008 cu. metre bajri per sq. metre.	100 Sft	600.00	2,639.45
c	3rd coat 14 lbs. bitumen, and 1.5 Cft. bajri of nominal size ¼" (6 mm) per %sft or 0.69 Kg bitumen and 0.005 cubic metre bajri per sq. metre.	100 Sft	600.00	1,960.75
11	Dismantling and removing road pavement, etc., including screening and stacking of byproducts upto one chain lead (30 metre).	100 Cft	600.00	4,017.80
12	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	4,000.00	10,533.60
13	Rehandling of earthwork: Upto a lead of 50 ft. (15 m).	1000 Cft	30,880.00	5,266.80
14	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	737.28	14,042.60
ii	RCC 1:1.5:3	100 Cft	8,217.70	14,042.60
iii	Base	100 Cft	366.00	14,042.60
iii	T.S.T	100 Cft	45.00	14,042.60
				Total Cost
vii. Pump House No: 5 (D-2 Drain at RD 0+100)				

1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	25,000.75	12,735.60
2	Extra for slush or Daldal including dewatering. Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)	1000 Cft	25,000.75	12,038.40
3	a) Nominal mix ratio 1:4:8	100 Cft	733.67	34,694.30
4	b) Nominal mix ratio 1:2:4	100 Cft	432.54	47,135.90
5	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	40,723.13	30,376.90
6	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3) b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	5,753.34	817.55
7	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	1 Cft	3,296.24	670.50
8	Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sand blinded.	100 Sft	3,466.04	1,645.10
9	Providing and laying polythene sheet under floor or roof complete 500 gauge.	100 Sft	648.78	13,179.60
10	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Sft	46.00	11.00
11	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 Rft	4.00	514.90
12	Making top khurra on roof 2' x 2' x 6".	1 No	4.00	849.70
13	Providing and fixing windows consisting of M.S. box section frame 2"x1½", (50x40mm) leaves frame 1½"x1" (40x25mm) box section frame for glazing 3/8"x3/8" (10x10mm) using 16 SWG sheet 'U' shaped rubber supported with 1"x1/8" (25x3mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section ½"x½" (13x13mm) of 16 SWG for fixing 24 SWG wire gauze on outer side by means of ¾"x1/8" (20x3mm) M.S. flat and screws including grill of M.S. flat ½"x1/8" (13x3mm) or ¼"x¼" (6x6mm) square bar with independent frame of ½"x½" (13x13mm) box section of 16 SWG i/c all C.P. fitting and painting 3 coats complete in all respect.	1 No	4.00	1,159.65
14	Providing and fixing windows consisting of M.S. box section frame 2"x1½", (50x40mm) leaves frame 1½"x1" (40x25mm) box section frame for glazing 3/8"x3/8" (10x10mm) using 16 SWG sheet 'U' shaped rubber supported with 1"x1/8" (25x3mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section ½"x½" (13x13mm) of 16 SWG for fixing 24 SWG wire gauze on outer side by means of ¾"x1/8" (20x3mm) M.S. flat and screws including grill of M.S. flat ½"x1/8" (13x3mm) or ¼"x¼" (6x6mm) square bar with independent frame of ½"x½" (13x13mm) box section of 16 SWG i/c all C.P. fitting and painting 3 coats complete in all respect.	1 Sft	271.92	2,180.70
15	Making and fixing steel grated door with 1/16" thick 1.5mm) sheeting, including angle iron frame 2"x2"x3/8" (50x50x10 mm) and ¾" (20 mm) square bars 4" (100 mm)	1 Sft	176.00	2,767.00
16	Distempering:- 2 coats	100 Sft	2,528.60	1,212.35
17	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	2,362.25	7,379.10
18	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	168.00	3,052.40

19	Providing and fixing 1½x1¼"x3/16" (31x31x5 mm) angle" iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	1 No	28.00	680.75
21	Providing and fixing trash rack as per drawing	1 Sft	184.00	603.00
22	Providing and laying Tuff Pavers, having 7000PSI ,crushing strength of approved manufa cturer, over 2"to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope . complete in all respect. (50% Grey / 50% Coloured) 60-mm thick	1 Sft	1,417.67	205.40
23	Providing & laying graded bajri ½" to 2" gauge on level (including carriage). 1½"(40 mm) thick mosaic flooring, consisting of ½ " mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1"(25 mm) thick floor of 1:2:4 cement concrete, including rubbing and polishing complete with finishing :-using grey cement	100 Cft	272.49	18,017.60
24	Mosaic dado or skirting with one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over ½"(13 mm) thick cement plaster 1:3, including rubbing and polishing, complete with finishing:(a) using grey cement: i) 1/2"(13 mm) thick	100 Sft	648.78	29,658.50
25	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels(a) Size 1½" x 3/8" (40 x 10 mm)	100 Sft	53.42	19,146.85
26	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	389.75	39.60
27	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.	1 Rft	173.29	809.40
28	a) 20mm (¾") i/d. b) 25 mm (1") i/d	1 Rft 1 Rft	100.00 100.00	112.25 133.60
29	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated. a) 3/0.74mm (3/0.029"). b) 7/0.74mm (7/0.029").	1 Rft 1 Rft	250.00 200.00	35.70 56.30
30	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc. b) 17.5 x 10 cm (7" x 4").	1 Each	3.00	522.75
31	Supply and erection of switches 5 amp. Piano Type.	1 Each	20.00	102.70
32	Supply and erection of backlite button holder shade, large size.	1 Each	5.00	178.75
33	Supply and erection of ceiling rose, bakelite.	1 Each	5.00	96.30
34	Suppling, Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire completb) Double Pole(iii) 6-63 Amp (10 KA)	1 No	1.00	5,616.25
35	Suppling, Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	2.00	1,453.75
36	Providing and fixing Pakistan Energy Label NEECA approved Copper winded wall bracket Fan i/c the cost of necessary cable and hardware for connection as approved and directed by Engineer Incharge.ii) 24" Sweep dia	1 Each	4.00	11,398.45
37	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	5.00	1,995.30
<u>Lining Portion</u>				
38	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	10,698.49	10,533.60

39	Compaction of earth work with power Road Roller, i.e ploughing mixing, moistening earth to optimum moisture content in layer etc; complete 90 % maximum modified AASHO dry density	1000 Cft	10,698.49	1,437.50
40	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed off undressed within 50 ft. (15 m) lead:- ordinary Soil	1000 Cft	4,319.86	5,033.70
41	Cement plaster 1.5" (40 mm) thick ratio 1:6:- a) In bed	100 Sft	700.00	6,512.05
42	b) On slope	100 Sft	1,168.00	7,363.45
43	Cement concrete lining, using washed screened and graded stone aggregate:- a) In bed, ratio 1:2:4	100 Cft	239.75	49,016.90
44	b) On slope, ratio 1:2:4	100 Cft	400.04	51,301.80
45	Providing and placing cement, sand and bituminous joint sealant in ratio 1:2:3, 1/2" wide, 1" deep.	1 Rft	186.80	17.30
46	Bitumen coating to plastered or cement concrete surface:- 10 lbs. per 100 Sft.	100 Sft	93.40	1,539.80
Stone Pitching Work				
47	Earthwork in excavation of drains in irrigation channels through excavator / draglines in all kind of soil and conditions	1000 Cft	6,208.72	4,640.70
48	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excluding carriage)	100 Cft	6,208.72	6,849.00
49	Formation dressing and preparing subgrade, on slope	100 Sft	2,589.88	2,265.10
50	Formation dressing and preparing subgrade, in bed.	100 Sft	524.66	1,660.50
51	Providing & laying graded bajri 1/8" to 1/2" gauge on slope (including carriage).	100 Cft	854.71	18,564.10
52	Providing & laying graded bajri 1/2" to 2" gauge on slope (including carriage).	100 Cft	854.71	18,564.10
53	Providing & laying graded bajri 1/8" to 1/2" gauge on level (including carriage).	100 Cft	173.14	18,017.60
54	Providing & laying graded bajri 1/2" to 2" gauge on level (including carriage).	100 Cft	173.14	18,017.60
55	Providing and laying stone pitching for top layer only on slope (excluding carriage)	100 Cft	2,590.02	11,511.00
56	Providing and laying stone pitching for top layer only on level (excluding carriage)	100 Cft	173.14	10,570.50
57	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 275Km.(From Sakhi Sarwar)	100 Cft	20,947.18	14,042.60

Total Cost

viii. Inlets

1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil. By Manual	1000 Cft	12,209.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8 b) Nominal mix ratio 1:2:4	100 Cft 100 Cft	1,730.87 180.37	34,694.30 47,135.90
3	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	2,798.89	35,727.00
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	2,314.13	817.55

	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	796.50	670.50
5	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	9,331.88	30,376.90
6	Providing and laying dry, hand packed stone apron as per drawing	100 Cft	2,649.90	6,849.00
14	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	4,720.00	5,266.80
15	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	1,661.64	14,042.60
i	PCC 1:2:4	100 Cft	158.72	14,042.60
ii	RCC 1:1.5:3	100 Cft	2,612.93	14,042.60
iii	Dry Hand Pack Stone	100 Cft	3,577.37	14,042.60

Total Cost

Total Cost for Section 9 (D-2 Drain)

10. D-3 Drain (RD 0+000 to 12+524)

i. Earthwork

1	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed off and dressed within 50 ft. (15 m) lead:- (In Banks)	1000 Cft	1,671,902.14	4,640.70
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	1,638,852.06	940.90
3	Transportation of earth all types when the total distance, including the lead covered in the item of work , is more than 1000 ft.			
	a) 500 ft	1000 Cft	10,467.50	1,073.20
	b) 750 ft	1000 Cft	23,965.00	1,743.95
	c) 1000 ft	1000 Cft	5,747.50	2,414.70
4	Borrowpit excavation undressed lead upto 100 ft (30 metre) in a) ordinary soil with	1000 Cft		
	a) 1 mile	1000 Cft	159,193.80	18,092.20
7	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	130.00	1,326.20

ii. Data Board:

1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	24.50	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.50	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.00	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.70	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.65	4,334.75
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.65	7,379.10
8	Writing letter or figures per letter per inch height	1 No	500.00	30.50

9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.29	14,042.60
iii. RD Marks:				
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	22.36	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	51.09	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	13.00	115.40
4	Placing boundary pillars in position, including digging pits.	1 Each	13.00	141.90
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	45.50	4,307.55
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	130.00	30.50
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
ii	PCC 1:2:4	100 Cft	19.68	14,042.60
				Total Cost
iv. Water Course				
1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	15,395.30	12,735.60
2	Extra for slush or Daldal including dewatering.	1000 Cft	15,395.30	12,038.40
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8 b) Nominal mix ratio 1:2:4	100 Cft 100 Cft	1,785.03 238.00	34,694.30 47,135.90
4	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	45,010.33	30,376.90
5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3) b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work (i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	9,694.24	817.55
6	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	5,822.75	1,645.10
7	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	560.00	35,727.00
8	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	1,373.78	809.40
9	Providing and placing poly sulphide joint sealant 1" wide and 1" deep.	1 Rft	470.00	1,381.00
10	Rehandling of earthwork: Upto a lead of 50 ft. (15 m).	1000 Cft	28,000.00	5,266.80

11	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	1,713.62	14,042.60
ii	PCC 1:2:4	100 Cft	209.44	14,042.60
iii	RCC 1:1.5:3	100 Cft	12,602.89	14,042.60
Total Cost:				

v. Culverts

1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	21,204.33	12,735.60
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	564.50	34,694.30
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	22,179.12	30,376.90
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	5,135.04	817.55
	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	2,258.00	670.50
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	4,909.28	1,645.10
6	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 80mm dia (3 inch)	1 Rft	22.50	303.80
7	Providing and laying sub-base course of stone product of approved quality and grade, including placing, mixing, spreading and compaction of sub-base material to required depth, camber, grade to achieve 100% maximum modified AASHO dry density, including carriage of all material to site of work except gravel and aggregate. Crushed stone aggregate. Providing and laying base course of crushed stone aggregate of approved quality and grade, and supply and spreading of stone screening, including placing, mixing, spreading and compaction of base course material to	100 Cft	350.00	10,003.50
8	required depth, camber and grade to achieve 100% maximum modified AASHO dry density, including carriage of all materials to site of work except gravel and aggregate.	100 Cft	350.00	13,527.40
9	Providing and laying road edging of 3" (75 mm) wide and	1 Rft	100.00	64.20
10	Providing surface treatment of roads, including supply of bitumen and bajri/crushed stone aggregate of approved quality, including cleaning of road surface, heating, spraying bitumen, spreading bajri and rolling etc. complete including carriage of all material to site of work except bajri/crushed stone aggregate for which supply within 3 miles (5.0 km) is included in the rate.			

a	1st coat 35 lbs. bitumen, and 4 Cft. bajri of nominal size 1" (25 mm) per 100 sq. feet or 1.72 Kg bitumen and 0.017 cu.metre bajri per square metre..	100 Sft	700.00	4,549.95
b	2nd coat 18 lbs. bitumen, and 2 Cft. bajri of nominal size ½" (13 mm) per %sft or 1.23 Kg bitumen and 0.008 cu. metre bajri per sq.metre.	100 Sft	700.00	2,639.45
c	3rd coat 14 lbs. bitumen, and 1.5 Cft. bajri of nominal size ¼" (6 mm) per %sft or 0.69 Kg bitumen and 0.005 cubic metre bajri per sq.metre.	100 Sft	700.00	1,960.75
11	Dismantling and removing road pavement, etc.,including screening and stacking of byproducts upto one chain lead (30 metre).	100 Cft	600.00	4,017.80
12	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	6,400.00	10,533.60
13	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	24,812.80	5,266.80
14	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	541.92	14,042.60
ii	RCC 1:1.5:3	100 Cft	6,210.15	14,042.60
iii	Base	100 Cft	427.00	14,042.60
iii	T.S.T	100 Cft	52.50	14,042.60

Total Cost

vi. Pump House No: 6 (D-3 Drain at RD 0+100)

1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	21,403.79	12,735.60
2	Extra for slush or Daldal including dewatering.	1000 Cft	21,403.79	12,038.40
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			
4	a) Nominal mix ratio 1:4:8	100 Cft	736.13	34,694.30
4	b) Nominal mix ratio 1:2:4	100 Cft	432.54	47,135.90
5	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars).Deformed Bars (Grade 60)	100 Kg	40,760.53	30,376.90
6	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			-
6	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects.	1 Cft	5,794.46	817.55
7	Type B (nominal mix 1:1.5:3) b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect:	1 Cft	3,263.43	670.50
8	Type B (Nominal Mix 1:1.5:3) Bitumen coating to plastered or cement concrete surface.	100 Sft	3,489.50	1,645.10
9	14 lbs per 100 Sft (6.35 Kg. per Sq.m) Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sand blinded.	100 Sft	648.78	13,179.60
10	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	648.78	11.00

11	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Sft	46.00	514.90
12	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d	1 No	4.00	849.70
13	Making top khurra on roof 2' x 2' x 6".	1 No	4.00	1,159.65
14	Providing and fixing windows consisting of M.S. box section frame 2"x1½", (50x40mm) leaves frame 1½"x1" (40x25mm) box section frame for glazing 3/8"x3/8" (10x10mm) using 16 SWG sheet 'U' shaped rubber supported with 1"x1/8" (25x3mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section ½"x½" (13x13mm) of 16 SWG for fixing 24 SWG wire gauze on outer side by means of ¾"x1/8" (20x3mm) M.S. flat and screws including grill of M.S. flat ½"x1/8" (13x3mm) or ¼"x¼" (6x6mm) square bar with independent frame of ½"x½" (13x13mm) box section of 16 SWG i/c all C.P. fitting and painting 3 coats complete in all respect.	1 Sft	271.92	2,180.70
15	Making and fixing steel grated door with 1/16" thick 1.5mm) sheeting, including angle iron frame 2"x2"x3/8" (50x50x10 mm) and ¾" (20 mm) square bars 4" (100 mm)	1 Sft	176.00	2,767.00
16	Distempering:- 2 coats	100 Sft	2,528.60	1,212.35
17	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	2,362.25	7,379.10
18	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	168.00	3,052.40
19	Providing and fixing 1¼x1¼"x3/16" (31x31x5 mm) angle" iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	1 No	28.00	680.75
21	Providing and fixing trash rack as per drawing	1	184.00	603.00
22	Providing and laying Tuff Pavers, having 7000PSI ,crushing strength of approved manufa cturer, over 2"to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope . complete in all respect. (50% Grey / 50% Coloured) 60-mm thick	1 Sft	1,417.67	205.40
23	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	272.49	18,017.60
24	1½"(40 mm) thick mosaic flooring, consisting of ½ " mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1"(25 mm) thick floor of 1:2:4 cement concrete, including rubbing and polishing complete with finishing :-using grey cement	100 Sft	648.78	29,658.50
25	Mosaic dado or skirting with one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over ½"(13 mm) thick cement plaster 1:3, including rubbing and polishing, complete with finishing:(a) using grey cement:	100 Sft	53.42	19,146.85
26	i) 1/2"(13 mm) thick Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels(a) Size 1½" x 3/8" (40 x 10 mm)	1 Rft	389.75	39.60
27	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	176.57	809.40
28	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.			
	a) 20mm (3/4") i/d.	1 Rft	100.00	112.25
	b) 25 mm (1") i/d	1 Rft	100.00	133.60
29	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and caping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated. a) 3/0.74mm (3/0.029"). b) 7/0.74mm (7/0.029").	1 Rft 1 Rft	250.00 200.00	35.70 56.30
30	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.			
	b) 17.5 x 10 cm (7" x 4").	1 Each	3.00	522.75
31	Supply and erection of switches 5 amp. Piano Type.	1 Each	20.00	102.70

32	Supply and erection of backlite button holder shade, large size.	1 Each	5.00	178.75
33	Supply and erection of ceiling rose, bakelite.	1 Each	5.00	96.30
34	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire completb) Double Pole(iii) 6-63 Amp (10 KA)	1 No	1.00	5,616.25
35	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	2.00	1,453.75
36	Providing and fixing Pakistan Energy Label NEECA approved Copper winded wall bracket Fan i/c the cost of necessary cable and hardware for connection as approved and directed by Engineer Incharge.ii) 24" Sweep dia	1 Each	4.00	11,398.45
37	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	5.00	1,995.30
	<u>Lining Portion</u>			
38	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	14,034.93	10,533.60
39	Compaction of earth work with power Road Roller, i.c ploughing mixing, moistening earth to optimum moisture content in layer etc; complete 90 % maximum modified AASHO dry denisty	1000 Cft	14,034.93	1,437.50
40	Earthwork excavation in irrigation channels, drains, etc. to designed section, grades and profiles, excavated material disposed off undressed within 50 ft. (15 m) lead:- ordinary Soil	1000 Cft	4,319.86	5,033.70
41	Cement plaster 1.5" (40 mm) thick ratio 1:6:- a) In bed	100 Cft	700.00	6,512.05
42	b) On slope	100 Cft	1,168.00	7,363.45
	Cement concrete lining, using washed screened and graded stone aggregate:-			
43	a) In bed, ratio 1:2:4	100 Cft	239.75	49,016.90
44	b) On slope, ratio 1:2:4	100 Cft	400.04	51,301.80
45	Providing and placing cement, sand and bituminous joint sealant in ratio 1:2:3, 1/2" wide, 1" deep.	1 Rft	186.80	17.30
46	Bitumen coating to plastered or cement concrete surface:- 10 lbs. per 100 Sft.	100 Sft	93.40	1,539.80
	<u>Stone Pitching Work</u>			
47	Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000 Cft	6,208.72	4,640.70
48	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	6,208.72	6,849.00
49	Formation dressing and preparing subgrade, on slope	100 Sft	3,457.11	2,265.10
50	Formation dressing and preparing subgrade, in bed.	100 Sft	524.66	1,660.50
51	Providing & laying graded bajri 1/8" to 1/2" gauge on slope (including carriage).	100 Cft	1,140.89	18,564.10
52	Providing & laying graded bajri 1/2" to 2" gauge on slope (including carriage).	100 Cft	1,140.89	18,564.10
53	Providing & laying graded bajri 1/8" to 1/2" gauge on level (including carriage).	100 Cft	173.14	18,017.60
54	Providing & laying graded bajri 1/2" to 2" gauge on level (including carriage).	100 Cft	173.14	18,017.60
55	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	3,457.25	11,511.00
56	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	173.14	10,570.50
57	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 275Km.(From Sakhi Sarwar)	100 Cft	21,997.20	14,042.60
				Total Cost

vii. Inlets

1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil. By Manual	1000 Cft	11,890.33	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	1,730.87	34,694.30
	b) Nominal mix ratio 1:2:4	100 Cft	180.37	47,135.90
3	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	2,798.89	35,727.00
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	2,314.13	817.55
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work (i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	796.50	670.50
5	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	9,331.88	30,376.90
6	Providing and laying dry, hand packed stone apron as per drawing	100 Cft	2,331.23	6,849.00
14	Rehandling of earthwork: Upto a lead of 50 ft. (15 m).	1000 Cft	4,720.00	5,266.80
15	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	1,661.64	14,042.60
i	PCC 1:2:4	100 Cft	158.72	14,042.60
ii	RCC 1:1.5:3	100 Cft	2,612.93	14,042.60
iii	Dry Hand Pack Stone	100 Cft	3,147.16	14,042.60

Total Cost

Total Cost for Section 10 (D-3 Drain)

11. 1-L of D-1 Drain (RD 0+000 to 2+697)

i. Earthwork

1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, dalad and under water) including its disposal and preperation of working pad for operation of machinery. (rates includes 100ft lead)	1000 Cft	307,260.39	4,640.70
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	392,780.15	940.90
3	Transportation of earth all types when the total distance, including the lead covered in the item of work, is more than 1000 ft.			
	c) 1000 ft	1000 Cft	11,732.79	2,414.70
3	Borrowpit excavation undressed lead upto 100 ft (30 metre) in a) ordinary soil with	1000 Cft		
	a) 1000 ft	1000 Cft	97,969.47	12,948.30
4	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	30.00	1,326.20

ii. Data Board:

1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	24.50	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.50	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.00	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.70	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.65	4,334.75
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.65	7,379.10
8	Writing letter or figures per letter per inch height	1 No	500.00	30.50
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
	DPC	100 Cft	4.29	14,042.60

iii. RD Marks:

1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	5.16	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	11.79	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	3.00	115.40
4	Placing boundary pillars in position, including digging pits.	1 Each	3.00	141.90
5	Preparing surface and painting with emulation paint 3 coat.	100 Sft	10.50	4,307.55
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	30.00	30.50
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
ii	PCC 1:2:4	100 Cft	4.54	14,042.60

Total Cost

iv. Water Course

1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	1,949.33	12,735.60
2	Extra for slush or Daldal including dewatering.	1000 Cft	1,949.33	12,038.40
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			
	a) Nominal mix ratio 1:4:8	100 Cft	458.78	34,694.30
	b) Nominal mix ratio 1:2:4	100 Cft	68.00	47,135.90
4	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	9,117.49	30,376.90

5	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	1,761.11	817.55
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	1,278.05	670.50
6	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	986.24	1,645.10
7	Pacca brick work other than buildings upto 10 feet height. Cement sand mortar ratio 1:4	100 Cft	160.00	35,727.00
8	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	213.58	809.40
9	Providing and placing poly sulphide joint sealent 1" wide and 1" deep.	1 Rft	90.00	1,381.00
10	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	8,000.00	5,266.80
11	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	440.43	14,042.60
ii	PCC 1:2:4	100 Cft	59.84	14,042.60
iii	RCC 1.1.5.3	100 Cft	2,552.90	14,042.60
Total Cost:				

v. Culverts

1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft.	1000 Cft	11,161.16	12,735.60
2	In ordinary soil (above 5 ft depth) Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	252.00	34,694.30
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement(also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	10,673.28	30,376.90
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	2,549.76	817.55
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	1,008.00	670.50
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	2,884.80	1,645.10

6	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 80mm dia (3 inch)	1 Rft	13.50	303.80
7	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	11,520.00	5,266.80
18	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	241.92	14,042.60
ii	RCC 1:1.5:3	100 Cft	2,988.52	14,042.60
				Total Cost

vi. Inlets

1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m)and lift upto 5' (1.5 m) (b) in ordinary soil. By Manual	1000 Cft	4,728.65	15,824.15
	Cement concrete plain including, placing, compacting, finishing and curing complete			-
2	(including screening and washing of stones aggregate)			
	a) Nominal mix ratio 1:4:8	100 Cft	695.08	34,694.30
	b) Nominal mix ratio 1:2:4	100 Cft	72.15	47,135.90
3	Pacca brick work other than buildings upto 10 feet height.	100 Cft	1,119.56	35,727.00
	Cement sand mortar ratio 1:4			
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			
a)	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects.	1 Cft	938.25	817.55
	Type B (nominal mix 1:1.5:3)			
b)	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect:	1 Cft	324.00	670.50
	Type B (Nominal Mix 1:1.5:3)			
5	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	3,786.75	30,376.90
6	Providing and laying dry, hand packed stone apron as per drawing	100 Cft	881.65	6,849.00
7	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	1,920.00	5,266.80
8	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	667.28	14,042.60
i	PCC 1:2:4	100 Cft	63.49	14,042.60
ii	RCC 1:1.5:3	100 Cft	1,060.29	14,042.60
iii	Dry Hand Pack Stone	100 Cft	1,190.22	14,042.60
				Total Cost

vii. Stone Pitching

1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	148.50	4,640.70
2	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons.	100 Cft	148.50	6,849.00
3	Formation dressing and preparing subgrade, on slope	100 Sft	422.73	2,265.10

4	Formation dressing and preparing subgrade, in bed.	100 Sft	126.00	1,660.50
5	Providing and laying graded bajri 1/8" to 1/2" size on slope.	100 Cft	139.50	18,564.10
6	Providing and laying graded bajri 1/2" to 2" size on slope.	100 Cft	139.50	18,564.10
7	Providing and laying graded bajri 1/8" to 1/2" size on level.	100 Cft	41.58	18,017.60
8	Providing and laying graded bajri 1/2" to 2" size on level.	100 Cft	41.58	18,017.60
9	Providing and laying stone for top layer only, on slope.	100 Cft	422.73	11,511.00
10	Providing and laying stone for top layer only, on Level	100 Cft	126.00	10,570.50
11	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc or 150 Cft of timber by truck or by any other means owned by the contractor, lead 275 Km.	100 Cft	858.95	14,042.60
				Total Cost

viii. Tube Well room

1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil. 1) By Manual	1000 Cft	544.89	15,824.15
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextar or equivalent @ specified suspension concentrate (SC), Mixing Ability-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for 10-years complete in all respect as approved by the Engineer Incharge.	1 Sft	508.50	12.55
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	105.61	34,694.30
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	315.04	32,675.95
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythene sheet 500 gauge 1½" thick (40 mm).	100 Sft	64.50	11,460.20
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	120.00	7,607.35
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	150.00	7,547.75
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	290.90	35,830.60
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:2:4)	1 Cft	154.17	741.85
10	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work (i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:2:4)	1 Cft	18.41	595.00
11	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	1,035.44	30,376.90

12	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	32.00	2,180.70
13	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	40.00	457.10
14	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	49.00	2,767.00
15	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	95.56	13,179.60
16	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	99.56	11.00
17	Supplying and filling sand under floor or plugging in wells.	100 Cft	40.94	3,987.00
18	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	48.94	12,801.20
19	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) b) Nominal mix ratio 1:2:4	100 Cft	45.86	47,135.90
20	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	568.31	4,614.10
21	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	114.52	5,264.65
22	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	489.88	5,012.65
23	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	13.00	514.90
24	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d	1 No	2.00	849.70
25	Making top khurra on roof 2' x 2' x 6".	1 No	1.00	1,159.65
26	Distempering:- 3 coat	100 Sft	510.27	1,548.20
27	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	172.56	7,379.10
28	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	89.00	3,052.40
29	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, revitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	334.96	37,098.85
30	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials. a) 20mm (3/4") i/d. b) 25 mm (1") i/d c) 50 mm (2") i/d	1 Rft 1 Rft 1 Rft	60.00 30.00 15.00	112.25 133.60 231.55
31	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only) (a) 250/440 volts, P.V.C. insulated. a) 3/0.74mm (3/0.029"). b) 7/0.74mm (7/0.029").	1 Rft 1 Rft	180.00 60.00	35.70 56.30

32	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only) (a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).	1 Rft	40.00	237.65
33	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc. a) 10 x 10 cm (4" x 4"). b) 17.5 x 10 cm (7" x 4"). c) 22.5 x 10 cm (9" x 4").	1 Each 1 Each 1 Each	1.00 1.00 1.00	- 382.30 522.75 668.80
34	Supply and erection of switches 5 amp. Piano Type.	1 Each	20.00	102.70
35	Supply and erection of ceiling rose, bakelite.	1 Each	4.00	96.30
36	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	2.00	204.70
37	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	1.00	213.10
38	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessed/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	1.00	24,422.65
39	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	6.00	1,453.75
40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBSWITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaidd DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole (ii) 15-100 Amp (10 KA,15KA)	1 No	2.00	13,796.30
41	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker)of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (withfixedThermal-MagneticTrip)in prelaidd DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the EngineerIncharge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	1.00	19,859.40
42	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)singl rod (40 watts) with one choke and one starter.	1 No	3.00	1,995.30
43	Supply and erection of bakelite button holder shade, large size	1 No	3.00	178.75
44	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	101.39	14,042.60
ii	PCC 1:2:4	100 Cft	40.36	14,042.60
iii	RCC 1.2.4	100 Cft	151.86	14,042.60
iv	DPC 1.2.4	100 Cft	7.10	14,042.60

Total Cost:

Total Cost for Section -11 1L of D1 Drain)

12. Electrical Work (All New drainage system incuding Jarewala Drain)

1. Installation of Complete Electricity HT/LT Network Sub Stations for Tubewells and Pump Stations at D1 Main Drain System, Jarewala Drain.

1.1 Cost of 11 KV Line				
1	HT Spun Pole 45'	No	25	71344
2	HT S/STRUCTURE Pole 36'	No	700	71680
3	Earthing	No	700	5488
4	Steel -X-ARMS	No	1000	8333
5	11-KV Disc: Insulator	No	1500	4250
6	Eye Nut/Ahchore Shakle/D.End Clump	No	1200	609
7	11KV Pin Insulator with Pins	No	250	1797
8	D-Shakel + Spool Insulator	No	1000	599
9	DA Bolts	No	700	358
10	Nuts & Bolts 14"	No	500	208
11	Nuts & Bolts 12"	No	500	184
12	Nuts & Bolts 02"	No	200	49
13	Stay Rod + stay strips Complete	No	150	3935
14	Stay Wire	m	1200	399
15	ACSR Rabbit Conductor	No	55000	246
				Total:

1.2 Cost of Sub Station				
1	Transformer 400-KVA	No	2	2189000
2	Transformer 100-KVA	No	5	506760
3	Transformer 50-KVA	No	5	400567
4	Transformer 25-KVA	No	40	286340
5	Earthing	No	120	5488
6	Steel -X-ARMS	No	700	8333
7	11KV Pin Insulator with Pins	No	2100	1797
8	Plate form D/Edge	No	60	24290
9	ACSR Rabbit Conductor	No	3200	246
10	Nuts & Bolts	No	500	198
11	D-Fues Fitting Set	No	150	18250
12	Steel Crass arm for D fuse Mounting	No	50	4770
13	LT Capacitor	No	50	10900
14	LT Spun Pole 31'	No	500	23650
15	street light pole bracket 30 mm (1¼") G.I. pipe 2 metre long, complete with 2 No. pole clamp. (Ch-24) [Pump station + Tubewell Rooms)	No	200	3378.5
16	Supply and erection of pole mounted street light, holders, shade and glass, etc., for fitting 125/250 watts mercury vapour lamp (excluding cost of lamps): ii) Philips design (Ch 24) [Pump station + Tubewell Rooms)	No	200	6949.8
17	Supply and fitting of mercury vapour lamp, complete with choke set ii) 250 watt lamp (Ch 24) [Pump station + Tubewell Rooms)	No	200	4113.3
				Total:

1.3 Cost of Metering				
1	PVC 4/C Cable 19.083 (70mm Armoured	No	5000	976
2	AMR METER HT/LT Type (bi-directional)	No	50	48900
3	ATB A-Type 100/5	No	10	31300
4	Earthing	No	20	5488
5	CTs 100/5 Amp	No	80	10530
				Total:

1.4 Installation Charges 20%				
1	(A) Cost of 11 KV Line material	No		16263340
2	(B) Cost of Sub Station material	No		5598490
3	(c.) Cost of service and Metering material	No		1034832
				Total:

1.5 Earthing Charges				
1	Earthing Pit & Material will be provided by consumer	No		
				Total:

1.6 Foundation / Contractor Charges				
1	Contractor Charges/ Foundation Charges 60000 x 700	No		
				Total:

1.7 Less Charges of Return to store (Healthy) Material				
1	Feeder Rehabilitation Charges / Security	No		
				Total:
				Total:

2. Installation of Complete Electricity HT/LT Network Sub Stations for Tubewells and Pump Stations at D2 Drain PS-5, D3 Drain PS-6, PS-3 and

2.1 NEAR SCARP T/WELL NO.M-29 IN RESPECT OF MEPCO DIVISION				
1	25 KVATransformer	Ea	1	286340
2	S/STRUCTURE PLATFORM	Ea	1	15786
3	HT PCC POLE	Ea	3	33000
4	Steel -X-ARMS	Ea	9	8333

5	D-Fuse Fitting	Ea	3	18250
6	ACSR RABBIT	M	930	245.67
7	AMR METER	Ea	1	35200
8	Pin Insulator with Pins	Ea	9	1797
9	11 KV Disc	Ea	6	4250
10	Stay Rods	Ea	4	3591
11	Stay Wire	kg	110	399
12	Earth Rods	Ea	7	1498
13	PVC 4/C 19/.052	M	30	435
14	Nuts & Bolts	L/S	1	20000
	Total:			
	20% Installation Charges Civil Work Charges (Contractor Charges) SECURITY	Ea	3	15000
	Total:			
2.2 NEAR SCARP T/WELL NO.M-26 IN RESPECT OF MEPCO DIVISION				
1	25 KVATRANSFORMER	Ea	1	286340
2	S/STRUCTURE PLATFORM	Ea	1	15786
3	HT PCC POLE	Ea	1	33000
4	Steel -X-ARMS	Ea	3	8333
5	D-Fuse Fitting	Ea	3	18250
6	ACSR RABBIT	M	30	245
7	AMR METER	Ea	1	35200
8	Pin Insulator with Pins	Ea	6	1797
9	Stay Wire	kg	30	399
10	Earth Rods	Ea	3	1498
11	PVC 4/C 19/.052	M	30	435
12	Nuts & Bolts	L/S	1	10000
	Total:			
	20% Installation Charges Civil Work Charges (Contractor Charges) SECURITY	Ea	1	15000
	Total:			
2.3 NEAR SCARP T/WELL NO.M-128 IN RESPECT OF MEPCO DIVISION				
1	25 KVATRANSFORMER	Ea	1	286340
2	S/STRUCTURE PLATFORM	Ea	1	15786
3	HT PCC POLE	Ea	1	33000
4	Steel -X-ARMS	Ea	6	8333
5	D-Fuse Fitting	Ea	3	18250
6	ACSR RABBIT	M	380	245
7	AMR METER	Ea	1	35200
8	Pin Insulator with Pins	Ea	6	1797
9	11 KV Disc	Ea	6	4250
10	Stay Rods	Ea	2	3591
11	Stay Wire	kg	60	399
12	Earth Rods	Ea	4	1498
13	PVC 4/C 19/.052	M	30	435
14	Nuts & Bolts	L/S	1	20000
	Total:			
	20% Installation Charges Civil Work Charges (Contractor Charges) SECURITY	Ea	1	15000
	Total:			
2.4 NEAR SCARP T/WELL NO.M-32 IN RESPECT OF MEPCO DIVISION				
1	25 KVATRANSFORMER	Ea	1	286340
2	S/STRUCTURE PLATFORM	Ea	1	15786
3	HT PCC POLE	Ea	4	33000
4	Steel -X-ARMS	Ea	10	8333
5	D-Fuse Fitting	Ea	3	18250
6	ACSR RABBIT	M	1130	245
7	AMR METER	Ea	1	35200
8	Pin Insulator with Pins	Ea	12	1797
9	11 KV Disc	Ea	6	4250
10	Stay Rods	Ea	4	3591
11	Stay Wire	kg	120	399
12	Earth Rods	Ea	8	1498
13	PVC 4/C 19/.052	M	30	435
14	Nuts & Bolts	L/S	1	20000
	Total:			
	20% Installation Charges Civil Work Charges (Contractor Charges)	Ea	4	15000

	SECURITY			
Total:				
2.5 NEAR SCARP T/WELL NO.M-26 IN RESPECT OF MEPCO DIVISION				
1	200 KVA TRANSFORMER	Ea	1	904422
2	D/STRUCTURE PLATFORM	Ea	1	24290
3	LT PCC POLE	Ea	1	23650
4	Steel -X-ARMS	Ea	4	8333
5	D-Fuse Fitting	Ea	3	18250
6	ACSR RABBIT	M	50	245
7	AMR METER	Ea	1	35200
8	Pin Insulator with Pins	Ea	6	1797
9	ATB A TYPE	Ea	2	31300
10	CTS 100/5	Ea	8	10530
11	Stay Wire	kg	40	399
12	Earth Rods	Ea	4	1498
13	PVC 4/C 19/.083	M	100	975
14	Nuts & Bolts	L/S	1	10000
Total:				
	20% Installation Charges Civil Work Charges (Contactor Charges) SECURITY	Ea	1	15000
Total:				
2.6 NEAR SCARP T/WELL NO.M-128 IN RESPECT OF MEPCO DIVISION				
1	25 KVATransformer	Ea	1	286340
2	S/STRUCTURE PLATFORM	Ea	1	15786
3	HT PCC POLE	Ea	1	33000
4	Steel -X-ARMS	Ea	6	8333
5	D-Fuse Fitting	Ea	3	18250
6	ACSR RABBIT	M	380	245
7	AMR METER	Ea	1	35200
8	Pin Insulator with Pins	Ea	6	1797
9	11 KV Disc	Ea	6	4250
10	Stay Rods	Ea	2	3591
11	Stay Wire	kg	60	399
12	Earth Rods	Ea	4	1498
13	PVC 4/C 19/.052	M	100	435
14	Nuts & Bolts	L/S	1	20000
Total:				
	20% Installation Charges Civil Work Charges (Contactor Charges) SECURITY	Ea	1	15000
Total:				
2.7 NEAR SCARP T/WELL NO.M-19 IN RESPECT OF MEPCO DIVISION				
1	200 KVA TRANSFORMER	Ea	1	904422
2	D/STRUCTURE PLATFORM	Ea	1	24290
3	HT PCC POLE	Ea	1	33000
4	LT PCC POLE	Ea	1	23650
5	Steel -X-ARMS	Ea	4	8333
6	D-Fuse Fitting	Ea	3	18250
7	ACSR RABBIT	M	50	245
8	AMR METER	Ea	1	35200
9	Pin Insulator with Pins	Ea	6	1797
10	ATB A TYPE	Ea	2	31300
11	CTS 100/5	Ea	8	10530
12	Stay Wire	kg	40	399
13	Earth Rods	Ea	4	1498
14	PVC 4/C 19/.083	M	200	975
	Nuts & Bolts	L/S	1	10000
Total:				
	20% Installation Charges Civil Work Charges (Contactor Charges) SECURITY	Ea	2	15000
Total:				
2.8 NEAR SCARP T/WELL NO.M-34 IN RESPECT OF MEPCO DIVISION				
1	25 KVATransformer	Ea	1	286340
2	S/STRUCTURE PLATFORM	Ea	1	15786
3	HT PCC POLE	Ea	1	33000
4	Steel -X-ARMS	Ea	6	8333
5	D-Fuse Fitting	Ea	3	18250
6	ACSR RABBIT	M	290	245
7	AMR METER	Ea	1	35200

8	Pin Insulator with Pins	Ea	6	1797
9	11 KV Disc	Ea	6	4250
10	Stay Rods	Ea	2	3591
11	Stay Wire	kg	60	399
12	Earth Rods	Ea	4	1498
13	PVC 4/C 19/.052	M	200	435
14	Nuts & Bolts	L/S	1	10000
Total:				
	20% Installation Charges Civil Work Charges (Contactor Charges) SECURITY	Ea	1	15000
		Total:		

2.9 NEAR SCARP PUMPING STATION-3 IN RESPECT OF MEPCO DIVISION

1	630 KVA TRANSFORMER	Ea	2	2375000
2	D/STRUCTURE PLATFORM	Ea	5	24290
3	LT PCC POLE	Ea	25	23650
4	Steel -X-ARMS	Ea	12	8333
5	D-Fuse Fitting	Ea	9	18250
6	ACSR RABBIT	M	150	245
7	AMR METER	Ea	1	35200
8	Pin Insulator with Pins	Ea	8	1797
9	ATB A TYPE	Ea	3	31300
10	CTS 100/5	Ea	12	10530
11	Stay Wire	kg	150	399
12	Earth Rods	Ea	20	1498
13	PVC 4/C 19/.083	M	1000	975
14	Nuts & Bolts	L/S	1	35000
Total:				
	20% Installation Charges Civil Work Charges (Contactor Charges) SECURITY	Ea	1	15000
		Total:		
		Total:		

3. Security Fencing Barbed Wire at quarters and pumping stations

1	Providing and fixing barbed wire fencing, with 4 horizontal and two cross wires, with R.C.C. 1:2:4 posts, 5.5'x6"x9" (1.68mx150mmx225 mm) at 8 ft. (2.45 m) center to center, reinforced with 4 No. 3/8" (10 mm) dia vertical bars and 1/8" (3 mm) dia stirrups 12" (300 mm) center to center, complete in all respects.	49390.0	100 Rft	69347.90
2	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil.	2063.0	1000 Cft	15824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	515.7	100 Cft	34694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	745.6	100 Cft	32675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with 2 coats of bitumen: 1½" thick (40 mm).	427.5	100 Sft	11851.70
5	Pacca brick work other than building upto 10ft. (3 m) Ratio 1:4	1656.6	100 Cft	35727.00
6	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	6225.5	100 Sft	4614.10
7	Providing and fixing collapsible gate made of 2"x2"x¼" (50x50x6 mm) tee iron at top and bottom, channel iron verticals ¾"x¼"x¼"x1/8" (20x6x6x3 mm) at 3" (75 mm) to 5" (125 mm) centre to centre (approximate) and flat iron crosses 3"x3/16" (75x5 mm), and best quality rollers at bottom of 3" (75 mm) diameter including holdfasts, handles 12" (300 mm) long of ¾"x¼"x¼"x1/8" (20x6x6x3 mm) channel iron, locking arrangement inside and outside, painting 3 coats of black Japan enameled. complete in working order.	6650.0	1 Sft	1985.95
8	Supply and erection PVC pipe for recessed wiring (main and sub-main) purpose, including bends, specials, etc. in floor, wall or trenches:- 50mm i/d	14250.0	1 Rft	234.95
9	Supply and erection of single core PVC insulated copper conductor cables, in prelaidd PVC pipe/M.S. conduit/G.I pipe/wooden strip batten/wooden casing an capping/G.I. wire/trenches (rate for cables only):7/0.74 mm (7/0.029")	28500.0	1 Rft	56.30

				Total:
				Total:
13. Installation of Tubewells (Mechanical)				
1	Providing installation, testing, and commissioning of a vertical deep well turbine tubewell pump with discharge 2 cusec against 70 ft head, including bowl assembly, vertical column pipe with shaft, motor, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical connections, cables and accessories from transformer to tubewell including earthing and protection devices, complete suction and delivery piping up to 25 ft outlet basin of approved material (MS/CI) with bends, flanges, valves, gaskets, supports and accessories, carrying out all works for energizing, testing, and full-load commissioning; pump casing in Gray Cast Iron EN-GJL-250, impeller in Stainless Steel grade 1.4408, column pipe coated internally and externally with epoxy paint, materials verified per EN 10204-3.1, minimum 80% efficiency per ISO 9906-1B; motor of reputed manufacturer, vertical solid shaft, IE3 efficiency class, 15 kW (20 HP, 1450 rpm), 4-pole, 3-phase, 50 Hz, 380/400 V, manufacturer to have in-house hydraulic and metallurgical testing facility, complete in all respects suitable for tubewell application. [including transportation and all overhead charges]	No	37	4,350,150
2	Direct Rotary / Reverse Rotary drilling of bore for tubewell in all type of soil except shingle gravel and rock. i). 15 " To 18" (500 to 650 mm)	Rft	8140	864.05
3	Collection of lithological samples with sieve analysis at every 5 ft. interval or change of lithology whichever is earlier.	No.	1628	80
4	Furnishing sample of water from bore hole.	Per Set of 2 bottles	37	232.8
5	Providing, installations testing and commissioning of 16" dia fiberglass blind pump housing casing with 6mm wall thickness having quick lock mechanical key joints complete in all respect as per specification and approved by the Engineer.	Rft	2590	5371
6	Providing and installation of Fibre Glass reducer 16"x10" with wall thickness 5.5 mm. complete in all respect as per specification and approved by the Engineer.	Nos	74	35582
7	Providing and installing Fiberglass Reinforced Polypropelene (FRP) strainer of specifid wall thickness having slot size of 0.9 mm to 1.10 mm in Tubewell borehole i/c the cost of male/female coupling with Nylone Strip, studs complete in all respect as approved and directed by the Engineer Incharge vi) 10" inch dia (6.35 mm thickness	Rft	4440	3866.45
8	Proving and installation of fiberglass Blank blind casing pipe dia 10" with 5.5" wall thickness. complete in all respect as per specification and approved by the Engineer.	Rft	740	3583
9	Providing and installing Fiber glass Reinforced Polypropelene (FRP) bail plug of specified wall thickness having slot size of 0.9 mm to 1.10 mm in Tubewell bore hole i/c the cost of male / female coupling with Nylone Strip, studs complete in all respect as approved and directed by the Engineer Incharge.vi) 10"dia (6.35mm thickness)	Rft	370	3735.5
10	Providing and installation of centralizer complete in all respect as per specification and approved by the Engineer.	No.	148	1148
11	Shrouding with graded pea gravel 3/8" to 1/8" arround tubewell casing in the bore hole.	Cft	6520.88	186.65
12	Testing and Development of tubewell of size 6"(150 mm) and above continusly. ii) Above 1.5 cs Discharge	Hours	2664	3253.1
13	Supply and erection of copper conductor cables for service connection (rate for cable only), PVC insulated, PVC sheathed 4 core , 600/1100 volt non armoured cable. (7/0.064")	Rft	1850	924.05
14	Excavation of trenches in all kinds of soil except cutting rock, for watersupply pipelines upto 5 ft. (1.5 m) depth from ground level, including trimming, dressing sides leveling the beds of trenches to correct grade and cutting pits for joints, etc. complete in all respects.	1000 Cft	118400	11293.9
15	Rehandling of earthwork lead upto a lead of 50 ft.	1000 Cft	118400	5266.8
16	Providing,laying,testing and commissioning µPVC (Unplasticized Poly vinyl Chloride Pressure pipe of nominal diameter, conforming to PS-3051/BS-3505, Dadex/ Popular/ Beta or approved equivalent manufacturer,i/c the cost of solvent and specials complete as approved and directed by the Engineer Incharge. a)Class-D 12 inch	Lft	14800	3565
17	Providing,laying,testing and commissioning µPVC (Unplasticized Poly vinyl Chloride Pressure pipe of nominal diameter, conforming to PS-3051/BS-3505, Dadex/ Popular/ Beta or approved equivalent manufacturer,i/c the cost of solvent and specials complete as approved and directed by the Engineer Incharge. a)Class-D 3 inch	Lft	555	500.3
				Total:

14. Installation of Pumps, Motors and Allied accessories (Mechanical Works for Jarewala Drain) PS-7

1	Providing installation, testing and commissioning of vertical tubular casing pump with ever cleaning blades having discharge capacity of 40 cusec against 16-25 ft head including pump, motor, bowl assembly, column set, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical cables, accessories and connections from transformer to pump including earthing and protection devices, complete suction piping inside the chamber (SS/MS/CI) and delivery piping up to the outlet basin (40–50 ft) of approved material (Fibre reinforced cement/upvc of suitable internal diameter size as approved by E-in-C) with all bends, flanges, valves, gaskets, supports and accessories, and carrying out all works necessary for energizing, testing and full-load commissioning of the complete pump set in all respects. . Pump shall have min. 84% efficiency which should be verified according to ISO 9906-1B standard. Material of pump casing shall be Gray cast iron JL-1040 having propeller (ever cleaning blades) in Stainless Steel grade 1.4408. Pump and column pipe shall be coated internally and externally with epoxy paint. Material of pump shall be verified according to material test certificate EN 10204-3.1. Motor shall be of reputed manufacturer having min. IE3 efficiency class. Vertical solid shaft. Rating of motor to be 110 KW (150HP, 450 rpm)/8 pole, 3 phase, 50 Hz, 380/400 Volts. . Manufacturer shall have its own testing facility to verify pumps hydraulic performance testing. Manufacturer shall have its own material testing lab to verify metallurgical testing. [including transportation and all overhead charges]	No.	8.00	13,004,544.0
2	Providing installation, testing and commissioning of horizontal centrifugal pump having discharge capacity of 10 cusec against 30 ft - 35 ft head including pump, motor, bowl assembly, column set, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical cables and connections from transformer to pump including earthing and protection devices, complete suction piping inside the chamber (SS/MS/CI) and delivery piping up to the outlet basin (40–50 ft) of approved material (Fibre reinforced cement/upvc of suitable internal diameter size as approved by E-in-C) with all bends, flanges, gaskets, supports and accessories, and carrying out all works necessary for energizing, testing and full-load commissioning of the complete pump set in all respects.. Pump shall have min. 81% efficiency which should be verified according to ISO 9906-1B standard. Material of pump casing shall be Gray cast iron EN-GJL-250 having impeller in Stainless Steel grade 1.4408. Pump shall be coated internally with epoxy paint. Material of pump shall be verified according to material test certificate EN 10204-3.1. Motor shall be of reputed manufacturer having min. IE3 efficiency class. Rating of motor to be 37 KW (50HP, 950 rpm)/6 pole, 3 phase, 50 Hz, 380/400 Volts. Manufacturer shall have its own testing facility to verify pumps hydraulic performance testing. Manufacturer shall have its own material testing lab to verify metallurgical testing. [including transportation and all overhead charges]	No.	1	3886124
3	Providing, installation, testing and comissioning of 10 Ton and more capacity Gantry Craine, with girder bridge type arrangement, fitted with electric motor for its operation and mobility, electric wiring and fixing in position, complete in all respect.	No.	1	1472223

Total:

15. Installation of Pumps, Motors and Allied accessories (Mechanical Works for D1,D2,D3 Drain) PS-4,5,6

Installation of PUMPS AT D1 DRAIN (PS-4)

1	Providing installation, testing and commissioning of horizontal centrifugal pump having discharge capacity of 10 cusec against 30 ft - 35 ft head including pump, motor, bowl assembly, column set, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical cables, accessories and connections from transformer to pump including earthing and protection devices, complete suction piping inside the chamber (SS/MS/CI) and delivery piping up to the outlet basin (40–50 ft) of approved material (Fibre-Glass/Fibre cement/upvc as approved by E-in-C) with all bends, flanges, valves, gaskets, supports and accessories, and carrying out all works necessary for energizing, testing and full-load commissioning of the complete pump set in all respects.. Pump shall have min. 81% efficiency which should be verified according to ISO 9906-1B standard. Material of pump casing shall be Gray cast iron EN-GJL-250 having impeller in Stainless Steel grade 1.4408. Pump shall be coated internally with epoxy paint. Material of pump shall be verified according to material test certificate EN 10204-3.1. Motor shall be of reputed manufacturer having min. IE3 efficiency class. Rating of motor to be 37 KW (50HP, 950 rpm) /6 pole, 3 phase, 50 Hz, 380/400 Volts. Manufacturer shall have its own testing facility to verify pumps hydraulic performance testing. Manufacturer shall have its own material testing lab to verify metallurgical testing. [including transportation and all overhead charges]	No.	3.00	3,886,124.00
---	---	-----	------	--------------

2	Providing installation, testing and commissioning of horizontal centrifugal pump having discharge capacity of 20 cusec against 30 ft - 35 ft head including pump, motor, bowl assembly, column set, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical cables, accessories and connections from transformer to pump including earthing and protection devices, complete suction piping inside the chamber (SS/MS/CI) and delivery piping up to the outlet basin (40 -- 50 ft) of approved material (Fibre reinforced cement/upvc of suitable internal diameter size as approved by E-in-C) with all bends, flanges, valves, gaskets, supports and accessories, and carrying out all works necessary for energizing, testing and full-load commissioning of the complete pump set in all respects.. Pump shall have min. 83% efficiency which should be verified according to ISO 9906-1B standard. Material of pump casing shall be Gray cast iron EN-GJL-250 having impeller in Stainless Steel grade 1.4408. Pump shall be coated internally with epoxy paint. Material of pump shall be verified according to material test certificate EN 10204-3.1. Motor shall be of reputed manufacturer having min. IE3 efficiency class. Rating of motor to be 75 KW (100HP, 950 rpm) /8 pole, 3 phase, 50 Hz, 380/400 Volts. Manufacturer shall have its own testing facility to verify pumps hydraulic performance testing. Manufacturer shall have its own material testing lab to verify metallurgical testing. [including transportation and all overhead charges]	No.	1.00	8,178,639.0
3	Providing, installation, testing and comissioning of 5 Ton and more capacity Gantry Craine, with girder bridge type arrangement, fitted with electric motor for its operation and mobility, electric wiring and fixing in position, complete in all respect.	No.	1.0	1,472,223.0

INSTALLATION OF PUMPS AT D-2 DRAIN (PS-5)

1	Providing installation, testing and commissioning of horizontal centrifugal pump having discharge capacity of 10 cusec against 30 ft - 35 ft head including pump, motor, bowl assembly, column set, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical cables, accessories and connections from transformer to pump including earthing and protection devices, complete suction piping inside the chamber (SS/MS/CI) and delivery piping up to the outlet basin (40–50 ft) of approved material (Fibre reinforced cement/upvc of suitable internal diameter size as approved by E-in-C) with all bends, flanges, valves, gaskets, supports and accessories, and carrying out all works necessary for energizing, testing and full-load commissioning of the complete pump set in all respects.. Pump shall have min. 81% efficiency which should be verified according to ISO 9906-1B standard. Material of pump casing shall be Gray cast iron EN-GJL-250 having impeller in Stainless Steel grade 1.4408. Pump shall be coated internally with epoxy paint. Material of pump shall be verified according to material test certificate EN 10204-3.1. Motor shall be of reputed manufacturer having min. IE3 efficiency class. Rating of motor to be 37 KW (50HP, 950 rpm) /6 pole, 3 phase, 50 Hz, 380/400 Volts. Manufacturer shall have its own testing facility to verify pumps hydraulic performance testing. Manufacturer shall have its own material testing lab to verify metallurgical testing. [including transportation and all overhead charges]	No.	2.00	3,886,124.00
2	Providing, installation, testing and comissioning of 5 Ton capacity Gantry Craine, with girder bridge type arrangement, fitted with electric motor for its operation and mobility, electric wiring and fixing in position, complete in all respect.	No.	1.00	1,472,223.00

INSTALLATION OF PUMPS AT D-3 DRAIN (PS-6)

1	Providing installation, testing and commissioning of horizontal centrifugal pump having discharge capacity of 10 cusec against 30 ft - 35 ft head including pump, motor, bowl assembly, column set, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical cables, accessories and connections from transformer to pump including earthing and protection devices, complete suction piping inside the chamber (SS/MS/CI) and delivery piping up to the outlet basin (40–50 ft) of approved material (Fibre reinforced cement/upvc of suitable internal diameter size as approved by E-in-C) with all bends, valves, flanges, gaskets, supports and accessories, and carrying out all works necessary for energizing, testing and full-load commissioning of the complete pump set in all respects.. Pump shall have min. 81% efficiency which should be verified according to ISO 9906-1B standard. Material of pump casing shall be Gray cast iron EN-GJL-250 having impeller in Stainless Steel grade 1.4408. Pump shall be coated internally with epoxy paint. Material of pump shall be verified according to material test certificate EN 10204-3.1. Motor shall be of reputed manufacturer having min. IE3 efficiency class. Rating of motor to be 37 KW (50HP, 950 rpm) /6 pole, 3 phase, 50 Hz, 380/400 Volts. Manufacturer shall have its own testing facility to verify pumps hydraulic performance testing. Manufacturer shall have its own material testing lab to verify metallurgical testing. [including transportation and all overhead charges]	No.	2	3,886,124.00
2	Providing, installation, testing and comissioning of 5 Ton capacity Gantry Craine, with girder bridge type arrangement, fitted with electric motor for its operation and mobility, electric wiring and fixing in position, complete in all respect.	No.	1	1,472,223.00

Total:

16. Solarization of Pumps on proposed Pump Houses**16.1 PS-4 of D1 main Drain**

	Providing installation, testing, and commissioning of a 53.5 kW Solar PV system capable of running a horizontal centrifugal pump with discharge 10 cusec against 30–35 ft head, pump minimum 81% efficiency, including Tier-1 Bloomberg-certified mono / bi-facial N-type solar panels (JINKO / LONGI / JA / Canadian / AKCome / TW / Trina, 700+ W/panel, 23.5% efficiency), solar pump inverter INVT suitably rated for system capacity, mounted on 12 ft high L2/L3/L4 galvanized steel structure (14 gauge) with complete mechanical and civil works, DC and AC cabling with XLPE/PVC insulated tin-coated copper wires (DC 1-core 6 mm, AC 4-core 6 mm, 25 mm PVC/XLPE), combiner boxes, AC & DC breakers, SPDs (A+ grade), all distribution/protection boxes (12"×18"×18" SWG or equivalent), PVC pipes, flexible pipes (1–1.5"), thimbles (O-type, U-type with shrouds), Rawl bolts, nuts and bolts, complete earthing system, lightning arrestor, all civil works, foundations, supports, electrical connections for net metering with meter, transportation of all materials from warehouse to site, testing, commissioning, and manufacturer-provided maintenance/after-sales service for 2 years, complete in all respects as directed by the Engineer-in-Charge.	No	3	4,116,450
--	---	----	---	-----------

16.2 PS-4 of D1 main Drain

	Providing installation, testing, and commissioning of a 107 kW Solar PV system for a horizontal centrifugal pump with discharge 20 cusec against 30 - 35 ft head , pump minimum 83% efficiency, including Tier-1 Bloomberg-certified mono / bi-facial N-type solar panels (JINKO / LONGI / JA / Canadian / AKCome / TW / Trina, 700+ W/panel, 23.5% efficiency), solar pump inverter INVT suitably rated for system capacity, mounted on 12 ft high L2/L3/L4 galvanized steel structure (14 gauge) with complete mechanical and civil works, DC and AC cabling with XLPE/PVC insulated tin-coated copper wires (DC 1-core 6 mm, AC 4-core 6 mm, 25 mm PVC/XLPE), combiner boxes, AC & DC breakers, SPDs (A+ grade), all distribution/protection boxes (12"×18"×18" SWG or equivalent), PVC pipes, flexible pipes (1–1.5"), thimbles (O-type, U-type with shrouds), Rawl bolts, nuts and bolts, complete earthing system, lightning arrestor, all civil works, foundations, and supports, all electrical connections for net metering with meter, transportation of all materials from warehouse to site, testing, commissioning, and manufacturer-provided maintenance/after-sales service for up to 2 years, complete in all respects as directed by the Engineer-in-Charge.	No	1	8,787,425
--	--	----	---	-----------

16.3 PS-5 of D2 Drain

	Providing installation, testing, and commissioning of a 53.5 kW Solar PV system capable of running a horizontal centrifugal pump with discharge 10 cusec against 30–35 ft head, pump minimum 81% efficiency, including Tier-1 Bloomberg-certified mono / bi-facial N-type solar panels (JINKO / LONGI / JA / Canadian / AKCome / TW / Trina, 700+ W/panel, 23.5% efficiency), solar pump inverter INVT suitably rated for system capacity, mounted on 12 ft high L2/L3/L4 galvanized steel structure (14 gauge) with complete mechanical and civil works, DC and AC cabling with XLPE/PVC insulated tin-coated copper wires (DC 1-core 6 mm, AC 4-core 6 mm, 25 mm PVC/XLPE), combiner boxes, AC & DC breakers, SPDs (A+ grade), all distribution/protection boxes (12"×18"×18" SWG or equivalent), PVC pipes, flexible pipes (1–1.5"), thimbles (O-type, U-type with shrouds), Rawl bolts, nuts and bolts, complete earthing system, lightning arrestor, all civil works, foundations, supports, electrical connections for net metering with meter, transportation of all materials from warehouse to site, testing, commissioning, and manufacturer-provided maintenance/after-sales service for 2 years, complete in all respects as directed by the Engineer-in-Charge.	No	2	4,116,450
	16.4 PS-6 of D3 Drain Providing installation, testing, and commissioning of a 53.5 kW Solar PV system capable of running a horizontal centrifugal pump with discharge 10 cusec against 30–35 ft head, pump minimum 81% efficiency, including Tier-1 Bloomberg-certified mono / bi-facial N-type solar panels (JINKO / LONGI / JA / Canadian / AKCome / TW / Trina, 700+ W/panel, 23.5% efficiency), solar pump inverter INVT suitably rated for system capacity, mounted on 12 ft high L2/L3/L4 galvanized steel structure (14 gauge) with complete mechanical and civil works, DC and AC cabling with XLPE/PVC insulated tin-coated copper wires (DC 1-core 6 mm, AC 4-core 6 mm, 25 mm PVC/XLPE), combiner boxes, AC & DC breakers, SPDs (A+ grade), all distribution/protection boxes (12"×18"×18" SWG or equivalent), PVC pipes, flexible pipes (1–1.5"), thimbles (O-type, U-type with shrouds), Rawl bolts, nuts and bolts, complete earthing system, lightning arrestor, all civil works, foundations, supports, electrical connections for net metering with meter, transportation of all materials from warehouse to site, testing, commissioning, and manufacturer-provided maintenance/after-sales service for 2 years, complete in all respects as directed by the Engineer-in-Charge.	No	2	4,116,450

Total:**17. Solarization of Tubewells 2 cusec 70 feet head****17.1 Solarization of New Tubewells**

	Providing installation, testing, and commissioning of a 22.5 kW Solar PV system capable of running a horizontal centrifugal pump with discharge 2 cusec against 70 ft head, pump minimum 81% efficiency, including Tier-1 Bloomberg-certified mono / bi-facial N-type solar panels (JINKO / LONGI / JA / Canadian / AKCome / TW / Trina, 700+ W/panel, 23.5% efficiency), solar pump inverter INVT suitably rated for system capacity, mounted on 12 ft high L2/L3/L4 galvanized steel structure (14 gauge) with complete mechanical and civil works, DC and AC cabling with XLPE/PVC insulated tin-coated copper wires, combiner boxes, AC & DC breakers, SPDs (A+ grade), all distribution/protection boxes (12"x18"x18" SWG or equivalent), PVC pipes, flexible pipes (1-1.5"), thimbles (O-type, U-type with shrouds), Rawl bolts, nuts and bolts, complete earthing system, lightning arrestor, all civil works, foundations, and supports, all electrical connections for net metering with meter, transportation of all materials from warehouse to site, testing, commissioning, and manufacturer-provided maintenance/after-sales service for up to 2 years, complete in all respects as directed by the Engineer-in-Charge.	No	37	1950150
--	---	----	----	---------

17.2 Solarization of Existing Tubewells

	Providing installation, testing, and commissioning of a 22.5 kW Solar PV system capable of running a horizontal centrifugal pump with discharge 2 cusec against 70 ft head, pump minimum 81% efficiency, including Tier-1 Bloomberg-certified mono / bi-facial N-type solar panels (JINKO / LONGI / JA / Canadian / AKCome / TW / Trina, 700+ W/panel, 23.5% efficiency), solar pump inverter INVT suitably rated for system capacity, mounted on 12 ft high L2/L3/L4 galvanized steel structure (14 gauge) with complete mechanical and civil works, DC and AC cabling with XLPE/PVC insulated tin-coated copper wires, combiner boxes, AC & DC breakers, SPDs (A+ grade), all distribution/protection boxes (12"x18"x18" SWG or equivalent), PVC pipes, flexible pipes (1-1.5"), thimbles (O-type, U-type with shrouds), Rawl bolts, nuts and bolts, complete earthing system, lightning arrestor, all civil works, foundations, and supports, all electrical connections for net metering with meter, transportation of all materials from warehouse to site, testing, commissioning, and manufacturer-provided maintenance/after-sales service for up to 2 years, complete in all respects as directed by the Engineer-in-Charge.	No	50	1,950,150
--	---	----	----	-----------

Total:

18. Construction of New Quarter for Tube well Operator

1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m) and lift upto 5' (1.5 m) (b) in ordinary soil. By Manual	1000 Cft	72,531.66	15,824.15
2	Spraying antitermite liquid mixed with water ratio 1:40	1 Sft	88,776.19	12.55
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	-	-
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	11,548.92	34,694.30
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythene sheet 500 gauge 1½" thick (40 mm).	100 Sft	44,360.68	32,675.95
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	8,834.11	11,460.20
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	100 Sft	8,771.49	7,607.35
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4	1000 Cft	31,674.37	7,547.75
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) - a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type C (nominal mix 1:2:4)	100 Cft	47,794.11	35,830.60
		1 Cft	21,724.43	741.85

10	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	65,173.29	30,376.90
11	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	3,276.00	2,180.70
12	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	3,822.00	457.10
13	Providing and fixing 1½" (40 mm) thick solid flush door shutter sterling or equivalent with commercial ply (5mm thick) on both sides double pressed and deodar wood lapping 1½" x 3/8" (40 mm x 10 mm) around shutter including chromium plated fitting, iron hinges with aluminum kick plate 22 SWG on both sides and finger plate complete in all respect.	1 Sft	3,822.00	638.85
14	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	33,854.84	13,179.60
15	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	34,218.84	11.00
16	Supplying and filling sand under floor or plugging in wells.	100 Cft	7,420.14	3,987.00
17	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	9,109.10	12,801.20
18	1½"(40 mm) thick mosaic flooring, consisting of ½ " mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1"(25 mm) thick floor of 1:2:4 cement concrete, including rubbing and polishing complete with finishing :-using grey cement	100 Sft	22,325.37	29,658.50
19	Mosaic dado or skirting with one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over ½"(13 mm) thick cement plaster 1:3, including rubbing and polishing, complete with finishing:(a) using grey cement: i) 1/2"(13 mm) thick	100 Sft	14,054.04	19,146.85
20	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels(a) Size 1½" x 3/8" (40 x 10 mm)	1 Rft	22,750.00	39.60
21	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) b) Nominal mix ratio 1:2:4	100 Cft	-	-
22	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	113,184.66	4,614.10
23	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	21,116.55	5,264.65
24	Distempering:- 3 coat	100 Sft	99,928.24	1,548.20
25	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	31,339.95	7,379.10
26	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	65,280.22	5,012.65
27	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	1,183.00	514.90

28	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	182.00	849.70
29	Making top khurra on roof 2' x 2' x 6".	1 No	91.00	1,159.65
30	Providing and fixing sliding; bolt to doors iron sliding bolt, 10" (250 mm) long.	1 No	182.00	656.85
31	Painting new surface (c) preparing surface and painting of doors and windows any type (including edges) priming coat and 2 subsequent coats of paint.	100 Sft	7,644.00	3,052.40
32	Providing and fitting glazed earthen ware water closet, squatter type (Orisa pattern) combined with foot rest white.	1 Each	91.00	4,105.05
33	Providing and fitting "P" trap 10 cm (4") glazed.	1 Each	273.00	463.15
34	Providing and Fixing chromium plated bib cock (ii) 1.5 cm (1/2").	1 Each	364.00	1,639.20
35	Providing & fitting plastic made low down flushing cistern 13.63 litre (3 gallons) capacity, including bracket set, copper connection, etc. complete (i) white.	1 Each	91.00	8,069.20
36	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	9,100.00	514.90
37	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	364.00	849.70
38	Providing and installing P.V.C. tees, of B.S.S.Class 'B' working pressure:-b) 4" i/d (100 mm)	1 No	364.00	2,374.25
39	Providing, laying, testing and commissioning of POLYPROPYLENE RANDOM COPOLYMER (PPRC water supply pipe (Dadex/Popular/ Beta or approved equivalent manufacturer, with specified pressure rating PN (PRESSURE NOMINAL) and conforming to DIN8077-8078 code/cost of solvent, specials, making jharries complete in all respect as approved and directed by Engineer Incharge. (Internal/External Diameters mentioned). a) PN-16 pipe	-	-	-
i	a) 20mm	1 Rft	9,100.00	62.95
ii	b) 25mm	1 Rft	4,550.00	87.10
40	Providing and fixing looking glass (mirror) 22" x 16" (55 x 40) cm, and 5 mm thick glass first quality.	1 Each	91.00	1,457.70
41	Providing and fixing stainless steel sink with drain board, size 120 x 60 cm (48 x 24") including bracket set, waste pipe and waste coupling.	1 Each	91.00	15,209.10
42	Providing and fitting.	-	-	-
	a) Plastic soap dish.	1 Each	91.00	1,380.00
	b) Plastic towel rail.	1 Each	91.00	1,610.00
	c) plastic shelf 60x13cm (24" x 5") with bracket and railing.	1 Each	91.00	1,035.00
43	Providing and fixing chromium plated tee stop cock 15 mm (1/2").	1 Each	91.00	1,999.20
44	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.	-	-	-
	a) 20mm (3/4") i/d.	1 Rft	9,100.00	112.25
	b) 25 mm (1") i/d	1 Rft	4,550.00	133.60
45	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pipe/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only)	-	-	-
	(a) 250/440 volts, P.V.C. insulated.			
	a) 3/0.74mm (3/0.029").	1 Rft	27,300.00	35.70
	b) 7/0.74mm (7/0.029").	1 Rft	9,100.00	56.30
46	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only)	1 Rft	18,200.00	237.65
	(a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).			
47	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.	-	-	-
	a) 10 x 10 cm (4" x 4").	1 Each	182.00	382.30
	b) 17.5 x 10 cm (7" x 4").	1 Each	364.00	522.75
	c) 22.5 x 10 cm (9" x 4").	1 Each	91.00	668.80
48	Supply and erection of switches 5 amp. Piano Type.	1 Each	3,185.00	102.70

49	Supply and erection of backlite button holder shade, large size.	1 Each	546.00	178.75
50	Supply and erection of ceiling rose, bakelite.	1 Each	546.00	96.30
51	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	182.00	204.70
52	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	182.00	213.10
53	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessed/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	91.00	24,422.65
54	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire completb) Double Pole(iii) 6-63 Amp (10 KA)	1 No	91.00	5,616.25
55	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	364.00	1,453.75
56	Supply and erection of 3/8" (10mm) dia M.S. bar fan hook, placed at the time of casting of slab.	1 Each	91.00	83.75
57	Providing and fixing Pakistan Energy Label NEECA approved Copper winded Ceiling Fan i/c the cost of necessary cable and hardware for connection as approved and directed by Engineer Incharge. 56" Sweep	1 Each	91.00	10,815.40
58	Erecting of ceiling fan along with regulator (all sizes) including carriage local railway station/ store to site of work, electric wire/cable for suspension rod and board connection and cutting, threading on the rod where necessary.	1 Each	91.00	663.65
59	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	546.00	1,995.30
60	Provided and installed 1 HP electric water pump with 70 ft bore, and successfully installed a 200-gallon water tank including all accessories and plumbing connections.	1 Each	91.00	99,800.00
61	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.		-	
i	PCC 1:4:8	100 Cft	11,086.97	14,042.60
ii	PCC 1:2:4	100 Cft	1,566.57	14,042.60
iii	RCC 1.2.4	100 Cft	19,117.50	14,042.60
iv	DPC 1.2.4	100 Cft	971.75	14,042.60
Total Cost for Section -12 (New Quarter for Tube well Operator)				

19. Eastward Extension of Evaporation Ponds

i. Earth Work for Jarewala Drain (from RD 0+000 to 25+446)

1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinary. (rates includes 100ft lead)	1000 Cft	4,234,073.10	4,640.70
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	1,712,983.98	940.90
3	Transportation of earth all types when the total distance, including the lead covered in the item of work.			
	a) 500 ft	1000 Cft	70,005.00	1,073.20
	b) 750 ft	1000 Cft	29,937.50	1,743.95
4	Providing and fixing Enamelled steel plate gauge 4" wide 1/4" thick (including painting and lettering) 10 ft length	1 No	5.00	14,630.00
5	Jungle clearance and removing within 100 ft. light	1000 Sft	1,272,300.00	376.20

6	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	260.00	1,326.20
ii. Data Board:				
1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	24.50	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.50	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.00	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.70	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.65	4,334.75
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.65	7,379.10
8	Writing letter or figures per letter per inch height	1 No	500.00	30.50
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
	DPC	100 Cft	4.29	14,042.60
iii. RD Marks:				
1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	44.72	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	102.18	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	26.00	115.40
4	Placing boundary pillars in position, including digging pits.	1 Each	26.00	141.90
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	91.00	4,307.55
6	Writing letter or figures per letter per inch height (three figure each side).	1 No	260.00	30.50
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
ii	PCC 1:2:4	100 Cft	39.35	14,042.60
iv. Road Barrier:				
1	Earthwork excavation undressed lead upto a single throw of Kassi, phaorah or shovel: In ordinary soil.	1000 Cft	245.00	15,824.15
2	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate) Ratio 1: 2: 4	100 Cft	367.50	47,135.90
3	Providing, laying, cutting, jointing, testing and disinfecting G.I. pipeline in trenches, with socket joints, using G.I. pipes of B.S.S. 1387-1967 complete in all respects, with specials and valves. i) 4" i/d (100 mm) 3.65mm thick	1 Rft	560.00	1,788.00
4	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 300Km.(From Sakhi Sarwar)	100 Cft	323.40	14,095.10
Total Cost:				
v. Earth Work of New 1-L / Jarewala Drain (from RD 0+000 to 16+500)				

1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinery. (rates includes 100ft lead)	1000 Cft	3,676,695.00	4,640.70
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil Transportation of earth all types when the total distance, including the lead covered in the item of work.	1000 Cft	4,402,362.50	940.90
3	Lead 500 Feet	1000 Cft	137,177.50	1,073.20
	Lead 750 Feet	1000 Cft	898,790.00	1,743.95
	Lead 1750 Feet	1000 Cft	496,885.00	6,751.20
4	Borrowpit excavation undressed lead upto 100 ft (30 metre) in a) ordinary soil with Lead 500 feet	1000 Cft	1,780,642.50	11,606.80
7	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	170.00	1,326.20

vi. Data Board:

1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	98.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	24.50	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	97.50	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	39.00	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	81.70	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	230.65	4,334.75
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	230.65	7,379.10
8	Writing letter or figures per letter per inch height	1 No	500.00	30.50
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	4.29	14,042.60

vii. RD Marks:

1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	29.24	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	66.81	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	17.00	115.40
4	Placing boundary pillars in position, including digging pits.	1 Each	17.00	141.90
5	Preparing surface and painting with emulation paint 3 coat.	100 Sft	59.50	4,307.55
6	Writing letter or firgures per letter per inch height (three figure each side). Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.	1 No	170.00	30.50
ii	PCC 1:2:4	100 Cft	25.73	14,042.60

Total Cost:

viii. Remodelling of Existing 1-L / Jarewala Drain (Earth Work from RD 0+000 to 3+500)

1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinery. (rates includes 100ft lead)	1000 Cft	15,402.50	4,640.70
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	51,770.00	940.90
3	Transportation of earth all types when the total distance, including the lead covered in the item of work.			
4	Lead 500 Feet Borrowpit excavation undressed lead upto 100 ft (30 metre) in a) ordinary soil with Lead 500 feet	1000 Cft	1,360.00	1,073.20
5	Providing and erection at site of work:- iii) R.C.C. boundary pillar. (Complete in all respect including transportation, Cement concrete foundation, fixing, painting and lettering etc)	1 No	40.00	1,326.20

ix. Data Board:

1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	49.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	12.25	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	48.75	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	19.50	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	40.85	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	115.33	4,334.75
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	115.33	7,379.10
8	Writing letter or figures per letter per inch height	1 No	250.00	30.50
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
	DPC	100 Cft	2.15	14,042.60

x. RD Marks:

1	Precast reinforced cement concrete type "C" 1:2:4.	1 Cft	6.88	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	15.72	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	4.00	115.40
4	Placing boundary pillars in position, including digging pits.	1 Each	4.00	141.90
5	Preparing surface and painting with emulation paint 3 coat.	100 Sft	14.00	4,307.55
6	Writing letter or firgures per letter per inch height (three figure each side).	1 No	40.00	30.50
7	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi , etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
ii	PCC 1:2:4	100 Cft	6.05	14,042.60

Total Cost:

Total Cost:

xi. Construction of Link Channels of Jarewala Drain System

1	Earth Work in excavation of drains, irrigation channels through excavator/ drag lines in all kind of soil and conditions (dry, wet slush, daldal and under water) including its disposal and preperation of working pad for operation of machinery. (rates includes 100ft lead)	1000 Cft	4,410,982.06	4,640.70
2	Dressing and levelling of earthwork to designed section etc complete in ii) ordinary or hard soil soil	1000 Cft	1,949,662.13	940.90

3	Rehandling of earthwork lead upto 50ft (35% of excess cutting) Transportation of earth all types when the total distance, including the lead covered in the item of work.	1000 Cft	910,707.78	5,266.80
4	Lead 500 Feet	1000 Cft	147,378.58	1,073.20
	Lead 1000 Feet	1000 Cft	224,897.50	2,414.70
	Lead 1500 Feet	1000 Cft	468,525.00	6,751.20
5	Borrowpit excavation undressed lead upto 100 ft (30 metre) in a) ordinary soil with Lead 250 feet	1000 Cft	140,702.29	10,936.05

xii. Data Board:

1	Excavation in foundation of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead upto one chain and lift upto 5 ft. in ordinary soil	1000 Cft	294.00	15,824.15
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	73.50	34,694.30
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	292.50	32,675.95
4	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with with 2 coats of bitumen: 1½" thick (40 mm).	100 Sft	117.00	11,851.70
5	Pacca brick work other than building upto 10 ft. height in cement sand mortar ratio 1:3	100 Cft	245.11	37,620.60
6	Cement plaster 1:4 upto 20 ft. height, 3/8" thick	100 Sft	691.95	4,334.75
7	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect white.	100 Sft	691.95	7,379.10
8	Writing letter or figures per letter per inch height	1 No	1,500.00	30.50
9	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area. DPC	100 Cft	12.87	14,042.60

xiii. RD Marks:

1	Precast reinforced cement concrete type "C" 1:2:4.	1	20.64	546.95
2	Fabrication of mild steel reinforcement for cement concrete including cutting bending laying in position etc. complete in all respect. (deformed bars) Grade 40	100 Kg	47.16	30,006.10
3	Carriage of consignment job upto 5 KMs Average	1 No	12.00	115.40
4	Placing boundary pillars in position, including digging pits.	1 Each	12.00	141.90
5	Preparing surface and painting with emulsion paint 3 coat.	100 Sft	42.00	4,307.55
6	Writing letter or figures per letter per inch height (three figure each side). Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any othermeans owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.	1 No	120.00	30.50
7	PCC 1:2:4	100 Cft	18.16	14,042.60

Total Cost:

xiv. Pump House No: 7 (1-L / Jarewala Drain at RD 3+750)

1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	125,135.85	12,735.60
2	Extra for slush or Daldal including dewatering. Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)	1000 Cft	125,135.85	12,038.40
3	a) Nominal mix ratio 1:4:8	100 Cft	1,808.13	34,694.30
4	b) Nominal mix ratio 1:2:4	100 Cft	577.90	47,135.90

5	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	129,118.01	30,376.90
6	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects.	1	18,946.31	817.55
7	Type B (nominal mix 1:1.5:3) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects.	1	9,746.58	670.50
8	Type B (nominal mix 1:1.5:3) Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	9,774.58	1,645.10
9	Single layer of tiles 9"x4½"x1½" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.m bitumen coating sand blinded.	100 Sft	1,394.28	13,179.60
10	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	1,394.28	11.00
11	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	282.00	514.90
12	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	12.00	849.70
13	Making top khurra on roof 2' x 2' x 6".	1 No	6.00	1,159.65
14	Providing and fixing windows consisting of M.S. box section frame 2"x1½", (50x40mm) leaves frame 1½"x1" (40x25mm) box section frame for glazing 3/8"x3/8" (10x10mm) using 16 SWG sheet 'U' shaped rubber supported with 1"x1/8" (25x3mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section ½"x½" (13x13mm) of 16 SWG for fixing 24 SWG wire gauze on outer side by means of ¾"x1/8" (20x3mm) M.S. flat and screws including grill of M.S. flat ½"x1/8" (13x3mm) or ¼"x¼" (6x6mm) square bar with independent frame of ½"x½" (13x13mm) box section of 16 SWG i/c all C.P. fitting and painting 3 coats complete in all respect.	1 Sft	463.92	2,180.70
15	Making and fixing steel grated door with 1/16" thick 1.5mm) sheeting, including angle iron frame 2"x2"x3/8" (50x50x10 mm) and ¾" (20 mm) square bars 4" (100 mm)	1 Sft	184.00	2,767.00
16	Distempering:- 2 coats	100 Sft	4,838.90	1,212.35
17	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	6,169.19	7,379.10
18	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	344.00	3,052.40
19	Providing and fixing 1¼"x1¼"x3/16" (31x31x5 mm) angle" iron step, in manhole chambers, including carriage and setting the same in work to correct lines and levels.	1 No	150.00	680.75
20	Providing/fixing stair railing consisting of M.S. Box section size 1-1/2"x3" of 16 SWG welded with M.S. flat 1"x1/8" continuously and welded over M.S. square bars 5/8"x5/8" punched in M.S. flat 2 ¾' high @ 5½" c/c fixed in steps of stair I/C painting 3 coats complete.	1 Rft	40.00	1,125.20
21	Providing and fixing trash rack as per drawing	1 Sft	696.00	603.00

22	Providing and laying Tuff Pavers, having 7000PSI ,crushing strength of approved manufa cturer, over 2"to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope . complete in all respect. (50% Grey / 50% Coloured) 60-mm thick	1 Sft	2,220.23	205.40
23	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	585.60	18,017.60
24	1½"(40 mm) thick mosaic flooring, consisting of ½ " mosaic topping of one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over 1"(25 mm) thick floor of 1:2:4 cement concrete, including rubbing and polishing complete with finishing :-using grey cement	100 Sft	1,394.28	29,658.50
25	Mosaic dado or skirting with one part of cement and marble powder in the ratio of 3:1 and two parts of marble chips, laid over ½"(13 mm) thick cement plaster 1:3, including rubbing and polishing, complete with finishing:(a) using grey cement: i) 1/2"(13 mm) thick	100 Sft	93.35	19,146.85
26	Providing and fixing marble strip of any shade for dividing the mosaic flooring into panels(a) Size 1½" x 3/8" (40 x 10 mm)	1 Rft	723.40	39.60
27	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	312.94	809.40
28	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.			
	a) 20mm (3/4") i/d.	1 Rft	350.00	112.25
	b) 25 mm (1") i/d	1 Rft	250.00	133.60
29	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only)			
	(a) 250/440 volts, P.V.C. insulated.			
	a) 3/0.74mm (3/0.029").	1 Rft	1,000.00	35.70
	b) 7/0.74mm (7/0.029").	1 Rft	500.00	56.30
30	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.			
	b) 17.5 x 10 cm (7" x 4").	1 Each	10.00	522.75
31	Supply and erection of switches 5 amp. Piano Type.	1 Each	50.00	102.70
32	Supply and erection of backlite button holder shade, large size.	1 Each	15.00	178.75
33	Supply and erection of ceiling rose, bakelite.	1 Each	15.00	96.30
34	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire completb) Double Pole(iii) 6-63 Amp (10 KA)	1 No	1.00	5,616.25
35	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaidd DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	10.00	1,453.75
36	Providing and fixing Pakistan Energy Label NEECA approved Copper winded wall bracket Fan i/c the cost of necessary cable and hardware for connection as approved and directed by Engineer Incharge.ii) 24" Sweep dia	1 Each	10.00	11,398.45
37	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii)single rod (40 watts) with one choke and one starter.	1 No	15.00	1,995.30
	Stone Pitching Work			
47	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	5,141.14	6,849.00
48	Providing & laying graded bajri ½" to ½" gauge on slope (including carriage).	100 Cft	812.42	18,564.10

49	Providing & laying graded bajri ½" to 2" gauge on slope (including carriage).	100 Cft	812.42	18,564.10
50	Providing & laying graded bajri ⅛" to ½" gauge on level (including carriage).	100 Cft	147.40	18,017.60
51	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	147.40	18,017.60
52	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	2,461.88	11,511.00
53	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	446.68	10,570.50
54	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 300Km.(From Sakhi Sarwar)	100 Cft	36,777.20	14,095.10
				Total Cost
xv. Construction of Bridge Cum Outlet at RD 0+000 New 1-L Jarewala				
1	Dismantling brick work in lime or cement mortar	100 Cft	803.25	2,633.40
2	Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000 Cft	8,700.00	4,640.70
3	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft.	1000 Cft	6,543.01	12,735.60
4	In ordinary soil (above 5 ft depth) Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	435.94	34,694.30
5	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars).Deformed Bars (Grade 60)	100 Kg	20,607.39	30,376.90
6	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.) a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3) b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)			-
a	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	1 Cft	4,517.97	817.55
b	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Cft	1,972.18	670.50
7	Plain wood work for regulation karries or needles, etc. including sawing, planning, wroughting wood and providing and fixing steel parts of karries i.e. end strip and rods, etc. b) Shisham wood	100 Sft	2,183.81	1,645.10
8		1 Rft	6.00	514.90
9		1 Cft	143.55	17,752.20
Stone Pitching Work				
1	Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000 Cft	2,700.32	4,640.70
2	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	2,700.32	6,849.00
3	Formation dressing and preparing subgrade, on slope	100 Sft	785.33	2,265.10
4	Formation dressing and preparing subgrade, in bed.	100 Sft	136.00	1,660.50
5	Providing & laying graded bajri ⅛" to ½" gauge on slope (including carriage).	100 Cft	259.16	18,564.10
6	Providing & laying graded bajri ½" to 2" gauge on slope (including carriage).	100 Cft	259.16	18,564.10

7	Providing & laying graded bajri 1/8" to 1/2" gauge on level (including carriage).	100 Cft	54.33	18,017.60
8	Providing & laying graded bajri 1/2" to 2" gauge on level (including carriage).	100 Cft	54.33	18,017.60
9	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	785.33	11,511.00
10	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	164.64	10,570.50
11	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 300Km.(From Sakhi Sarwar)	100 Cft	10,655.63	14,095.10
12	Credit to old material Brick batts	100 Cft	803.25	(4,100.00)
				Total Cost

xvi. Construction of Canal Cum Canal Aquaduct Cum Bridge at Jarewala Main Drain

1	Dismantling and removing road pavement, etc.,including screening and stacking of byproducts upto one chain lead (30 metre).	100 Cft	1,155.00	4,017.80
2	Dismantling brick work in lime or cement mortar	100 Cft	507.94	2,633.40
3	Dismantling cement concrete reinforced, separating reinforcement from concrete, cleaning and straightening the same.	100 Cft	422.50	27,086.40
4	Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000 Cft	32,500.00	4,640.70
5	Barrow pit excavation undressed lead up to 100 ft in ordinary soil.	1000 Cft	40,500.00	10,533.60
6	Rehandling of earthwork:Upto a lead of 50 ft. (15 m).	1000 Cft	40,500.00	5,266.80
7	Providing and laying R.C.C. pipe sewers, moulded with cement concrete 4000 psi conforming to Specification C-76-20, Class II. Wall B, including carriage of pipe from factory to site of work, lowering in trenches to correct alignment and grade, jointing with rubber ring,cutting pipes where necessary, testing, etc., complete. 24 inch internal dia	1 Rft	112.00	2,150.35
8	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth) Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)	1000 Cft	2,658.10	12,735.60
9	a) Nominal mix ratio 1:4:8	100 Cft	531.56	34,694.30
10	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars).Deformed Bars (Grade 60)	100 Kg	27,968.82	30,376.90
11	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			-
a	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	6,010.66	817.55
b	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	2,797.92	670.50
12	Providing and embedding 10"(250mm) wide PVC water stopper in expansion joints of RCC structures (Retaining walls, water tanks, Slabs) complete in all respect. 10mm thick	1 Rft	51.34	809.40
13	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	2,047.12	1,645.10

14	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	6.00	514.90
15	Providing and laying sub-base course of stone product of approved quality and grade, including placing, mixing, spreading and compaction of sub-base material to required depth, camber, grade to achieve 100% maximum modified AASHO dry density, including carriage of all material to site of work except gravel and aggregate. Crushed stone aggregate.	100 Cft	825.00	10,003.50
16	Providing and laying base course of crushed stone aggregate of approved quality and grade, and supply and spreading of stone screening, including placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHO dry density, including carriage of all materials to site of work except gravel and aggregate.	100 Cft	825.00	13,527.40
17	Providing and laying road edging of 3" (75 mm) wide and	1 Rft	200.00	64.20
18	Providing surface treatment of roads, including supply of bitumen and bajri/crushed stone aggregate of approved quality, including cleaning of road surface, heating, spraying bitumen, spreading bajri and rolling etc. complete including carriage of all material to site of work except bajri/crushed stone aggregate for which supply within 3 miles (5.0 km) is included in the rate.			
a	1st coat 35 lbs. bitumen, and 4 Cft. bajri of nominal size 1" (25 mm) per 100 sq. feet or 1.72 Kg bitumen and 0.017 cu. metre bajri per square metre..	100 Sft	1,650.00	4,549.95
b	2nd coat 18 lbs. bitumen, and 2 Cft. bajri of nominal size ½" (13 mm) per %sft or 1.23 Kg bitumen and 0.008 cu. metre bajri per sq. metre.	100 Sft	1,650.00	2,639.45
c	3rd coat 14 lbs. bitumen, and 1.5 Cft. bajri of nominal size ¼" (6 mm) per %sft or 0.69 Kg bitumen and 0.005 cubic metre bajri per sq. metre.	100 Sft	1,650.00	1,960.75
Stone Pitching Work				
19	Earthwork in excavation of drains in irrigation channels through excavator / draglines in all kind of soil and conditions	1000 Cft	967.13	4,640.70
20	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excluding carriage)	100 Cft	967.13	6,849.00
21	Formation dressing and preparing subgrade, on slope	100 Sft	614.72	2,265.10
22	Formation dressing and preparing subgrade, in bed.	100 Sft	96.00	1,660.50
23	Providing & laying graded bajri ⅛" to ½" gauge on slope (including carriage).	100 Cft	202.86	18,564.10
24	Providing & laying graded bajri ½" to 2" gauge on slope (including carriage).	100 Cft	202.86	18,564.10
25	Providing & laying graded bajri ⅛" to ½" gauge on level (including carriage).	100 Cft	31.68	18,017.60
26	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	31.68	18,017.60
27	Providing and laying stone pitching for top layer only on slope (excluding carriage)	100 Cft	614.72	11,511.00
28	Providing and laying stone pitching for top layer only on level (excluding carriage)	100 Cft	96.00	10,570.50
29	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 300 Km. (From Sakhi Sarwar)	100 Cft	11,198.25	14,095.10
30	Credit to old material			
a	Steel	1 Kg	1,267.50	(170.00)
b	Brick batts	100 Cft	507.94	(4,100.00)
				Total Cost

xvii. Construction of Bridge at New 1-L / Jjarwewala Drain at RD 4+000

1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft.	1000 Cft	19,789.77	12,735.60
	In ordinary soil (above 5 ft depth)			
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-

	a) Nominal mix ratio 1:4:8	100 Cft	358.89	34,694.30
	b) Nominal mix ratio 1:2:4	100 Cft	100.31	47,135.90
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	12,287.59	30,376.90
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			-
a	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1	2,130.79	817.55
b	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1	1,739.10	670.50
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	978.12	1,645.10
6	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	6.00	514.90
	Stone Pitching Work			
7	Earthwork in excavation of drains in irrigation channels through excavator / draglines in all kind of soil and conditions	1000 Cft	967.13	4,640.70
8	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	967.13	6,849.00
9	Formation dressing and preparing subgrade, on slope	100 Sft	594.53	2,265.10
10	Formation dressing and preparing subgrade, in bed.	100 Sft	96.00	1,660.50
11	Providing & laying graded bajri ⅛" to ½" gauge on slope (including carriage).	100 Cft	196.20	18,564.10
12	Providing & laying graded bajri ½" to 2" gauge on slope (including carriage).	100 Cft	196.20	18,564.10
13	Providing & laying graded bajri ⅛" to ½" gauge on level (including carriage).	100 Cft	31.68	18,017.60
14	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	31.68	18,017.60
15	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	594.53	11,511.00
16	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	96.00	10,570.50
17	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 300Km.(From Sakhi Sarwar)	100 Cft	5,817.78	14,095.10
Total Cost				

xviii. Construction of Bridge at New 1-L / Jjarwewala Drain at RD 9+500

1	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	23,091.93	12,735.60
2	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)			-
	a) Nominal mix ratio 1:4:8	100 Cft	358.89	34,694.30
	b) Nominal mix ratio 1:2:4	100 Cft	100.31	47,135.90
3	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars). Deformed Bars (Grade 60)	100 Kg	15,546.38	30,376.90

4	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			-
a	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1	3,157.12	817.55
b	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1	1,739.10	670.50
5	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	1,471.48	1,645.10
6	Providing, laying, cutting, jointing, testing and disinfecting PVC/ uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	6.00	514.90
	Stone Pitching Work			
7	Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000 Cft	967.13	4,640.70
8	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	967.13	6,849.00
9	Formation dressing and preparing subgrade, on slope	100 Sft	594.53	2,265.10
10	Formation dressing and preparing subgrade, in bed.	100 Sft	96.00	1,660.50
11	Providing & laying graded bajri ⅛" to ½" gauge on slope (including carriage).	100 Cft	196.20	18,564.10
12	Providing & laying graded bajri ½" to 2" gauge on slope (including carriage).	100 Cft	196.20	18,564.10
13	Providing & laying graded bajri ⅛" to ½" gauge on level (including carriage).	100 Cft	31.68	18,017.60
14	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	31.68	18,017.60
15	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	594.53	11,511.00
16	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	96.00	10,570.50
17	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 300Km.(From Sakhi Sarwar)	100 Cft	6,679.90	14,095.10
Total Cost				
Total Cost:				
xix. Culverts				
1	Dismantling brick work in lime or cement mortar	100 Cft	803.25	2,633.40
2	Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000 Cft	8,700.00	4,640.70
3	Excavation in foundation of building, bridges and other structures, including dagbelling, dressing, refilling around structure with excavated earth, watering and ramming lead up to one chain and lift upto 5 ft. In ordinary soil (above 5 ft depth)	1000 Cft	6,543.01	12,735.60
4	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate) a) Nominal mix ratio 1:4:8	100 Cft	435.94	34,694.30
5	Providing and fabrication of mild steel reinforcement for cement concrete, including cutting , bending, laying in position, making joints and fastening, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars).Deformed Bars (Grade 60)	100 Kg	20,607.39	30,376.90

6	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)			-
a	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Type B (nominal mix 1:1.5:3)	1 Cft	4,517.97	817.55
b	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect: Type B (Nominal Mix 1:1.5:3)	1 Cft	1,972.18	670.50
7	Bitumen coating to plastered or cement concrete surface. 14 lbs per 100 Sft (6.35 Kg. per Sq.m)	100 Sft	2,183.81	1,645.10
8	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	6.00	514.90
9	Plain wood work for regulation karries or needles, etc. including sawing, planning, wroughting wood and providing and fixing steel parts of karries i.e. end strip and rods, etc. b) Shisham wood	1 Cft	143.55	17,752.20
<u>Stone Pitching Work</u>				
9	Earthwork in excavation of drains in irrigation channels through excavater / draglines in all kind of soil and conditions	1000 Cft	2,700.32	4,640.70
10	Providing and laying stone pitching/filling, dry hand packed, as filling behind retaining walls or in pitching and aprons as per drawing. (excuding carriage)	100 Cft	2,700.32	6,849.00
11	Formation dressing and preparing subgrade, on slope	100 Sft	785.33	2,265.10
12	Formation dressing and preparing subgrade, in bed.	100 Sft	136.00	1,660.50
13	Providing & laying graded bajri ⅛" to ½" gauge on slope (including carriage).	100 Cft	259.16	18,564.10
14	Providing & laying graded bajri ½" to 2" gauge on slope (including carriage).	100 Cft	259.16	18,564.10
15	Providing & laying graded bajri ⅛" to ½" gauge on level (including carriage).	100 Cft	54.33	18,017.60
16	Providing & laying graded bajri ½" to 2" gauge on level (including carriage).	100 Cft	54.33	18,017.60
17	Providing and laying stone pitching for top layer only on slope (excuding carriage)	100 Cft	785.33	11,511.00
18	Providing and laying stone pitching for top layer only on level (excuding carriage)	100 Cft	164.64	10,570.50
19	Carriage of 100 Cft of all material like stone aggregate, spawl, kankar, lime (unsoaked) surkhi etc by truck or by any other means owned by the contractor, lead 300Km.(From Sakhi Sarwar)	100 Cft	10,655.63	14,095.10
20	Credit to old material			
a	Brick batts	100 Cft	803.25	(4,100.00)
Total Cost				

xx. Tubewell Rooms

1	Excavation in foundation of building, bridges, and other structures, including dag belling, dressing refilling around structure with excavated earth, watering and ramming lead upto one chain (30m)and lift upto 5' (1.5 m) (b) in ordinary soil.1)By Manual	1000 Cft	2,724.46	15,824.15
2	Spraying termite proofing by using liquid FMC / Biflex/ Terminex Exin/Ms Hextaror equivalent@specified suspension concentraterate (SC), MixingAbility-HEXTAR with Ratio (1:250)= 540 Sft or equivalent approved liquid applying with shower and certificate will be provided by the contractor for10-years complete in all respect.as approved by the Engineer Incharge.	1 Sft	2,542.50	12.55
3	Cement concrete plain including, placing, compacting, finishing and curing complete (including screening and washing of stones aggregate)		-	-

	a) Nominal mix ratio 1:4:8	100 Cft	528.06	34,694.30
4	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	100 Cft	1,575.20	32,675.95
5	Providing and laying damp proof course of cement 1:2:4 (using cement, sand and shingle), including bitumen coating with one coat of bitumen and one coat polythene sheet 500 gauge 1½" thick (40 mm).	100 Sft	322.50	11,460.20
6	Providing and laying vertical damp proof course with cement sand plaster and bitumen coating with one coat of bitumen and one coat of polythene sheet 500 gauge-Ratio 1:3 a) ½ " thick (13 mm)	100 Sft	600.00	7,607.35
7	Filling watering ramming earth under floors with surplus earth from foundation etc.	1000 Cft	750.00	7,547.75
8	Pacca brick work in ground floor. Cement sand mortar Ratio 1:4.	100 Cft	1,454.50	35,830.60
9	Providing and laying reinforced cement concrete (including prestressed concrete), using Sulphate resisting cement ; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete 2) Plastering done under soffit of R.C.C. (but excluding the cost of steel reinforcement, its fabrication and placing in position etc.)		-	
	a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects.	1	770.83	741.85
	Type B (nominal mix 1:2:4)			
10	b) Reinforcement cement concrete in slab of rafts/strip foundation, base slab of column and retaining walls, etc and other structural members not requiring form work(i.e horizontal shuttering) complete in all respect:	1	92.04	595.00
	Type B (Nominal Mix 1:2:4)			
11	Providing and Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, 13 making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars):- Deformed bars (Grade-60).	100 Kg	5,177.21	30,376.90
12	Providing and fixing windows consisting of M.S box section frame 2" x 1½" (50 x 40mm) Leaves frame 1½" x 1" (40 x 25 mm) box section frame for glazing 3/8" x 3/8" (10 x 10 mm) using 16 SWG sheet 'U' shaped rubber supported with 1" x 1/8" (25 x 3 mm) M.S. flat for fixing 3/16" (5 mm) thick glass panes M.S. box section 1/2" x 1/2" (13 x 13 mm) of 16 SWG for fixing 24 SWG wire gauge on outer side by means of 3/4" x 1/8" (20 x 3 mm) M.S. flat and screws including grill of M.S. flat 1/2" x 1/8" (13 x 3 mm) or 1/4" x 1/4" (6 x 6 mm) square bar with independent frame of 1/2" x 1/2" (13 x 13 mm) box section of 16 SWG i/c all C.P fitting and painting 3 coats complete in all respect.	1 Sft	160.00	2,180.70
13	Providing and fixing mild steel chowkat of doors windows C. windows etc. including holdfast making and threading 18 holes for hinges etc. complete 1½" x 1½" x 1/4" (40 x 40 x 6 mm) welded with M.S. flat 2" x 1/4" (50 m M.S. angle iron).	1 Sft	200.00	457.10
14	Making and fixing steel grated door with 1/16" thick sheeting, including angle iron frame 2" x 2" x 3/8" and 3/4" square bars 4" centre to centre. with locking arrangement (Two No.).	1 Sft	245.00	2,767.00
15	Providing and laying single layer of tile 9" x 4½" x 1½" laid over 4" earth and 1" thick mud plaster without bhoosa, grouted with cement mud (1:3) on top of R.C.C. roof, slab, provided with 34 lbs. per % Sft. Or 1.72 Kg./Sq.m. bitumen coating sand blinded.	100 Sft	477.81	13,179.60
16	Providing and laying polythene sheet under floor or roof complete 500 gauge.	1 Sft	497.81	11.00
17	Supplying and filling sand under floor or plugging in wells.	100 Cft	204.69	3,987.00
18	Providing and laying watering and ramming brick ballast 1½" to 2" (40 mm to 50 mm) mixed with 25% sand for floor foundation complete in all respect.	100 Cft	244.69	12,801.20
19	Cement concrete plain including, placing, compacting, finishing and curing complete		-	-
	(including screening and washing of stones aggregate)			
	b) Nominal mix ratio 1:2:4	100 Cft	229.30	47,135.90

20	Cement plaster 1:4 upto 20' (6.00 m) height 1/2" (13 mm) thick.	100 Sft	2,841.53	4,614.10
21	Cement plaster 3/8" (10 mm thick under soffit of R.C.C. roof slabs only, upto 20' height (Ratio 1:3).	100 Sft	572.60	5,264.65
22	Cement pointing struck joints on wall upto 20' (6m) height (a) Ratio 1:2 including extra cost of labour and material for red oxide pigment in cement pointing to match with the colour of bricks.	100 Sft	2,449.38	5,012.65
23	Providing, laying, cutting, jointing, testing and disinfecting PVC/uPVC pipe line with 'B' Class working pressure complete in all respects:- 4" i/d (100 mm)	1 Rft	65.00	514.90
24	Providing and installing P.V.C. bends, of B.S.S.b) 4" i/d (100 mm)	1 No	10.00	849.70
25	Making top khurra on roof 2' x 2' x 6".	1 No	5.00	1,159.65
26	Distempering:- 3 coat	100 Sft	2,551.35	1,548.20
27	Providing and applying weather shield paint of approved quality on external surface of building including preparation of surface, application of primer complete in all respect:	100 Sft	862.78	7,379.10
28	Preparing surface and painting of doors and windows any type (including edges):-	100 Sft	445.00	3,052.40
29	Fabrication of heavy steel work, with angle, tees, flat iron round iron and sheet iron for making trusses, girders, tanks, etc., including cutting, drilling, rebitting, handling, assembling and fixing, but excluding erection in position.	100 Kg	1,674.79	37,098.85
30	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc. complete with all specials.		-	-
	a) 20mm (3/4") i/d.	1 Rft	300.00	112.25
	b) 25 mm (1") i/d	1 Rft	150.00	133.60
	c) 50 mm (2") i/d	1 Rft	75.00	231.55
31	Supply and erection of single core PVC insulated copper conductor cables, in prepaid P.V.C. pile/M.S. conduit/G.I. pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only)		-	-
	(a) 250/440 volts, P.V.C. insulated.			
	a) 3/0.74mm (3/0.029").	1 Rft	900.00	35.70
	b) 7/0.74mm (7/0.029").	1 Rft	300.00	56.30
32	Supply and erection of copper conductor cable for service connection in prepaid pipe/G.I. wire/trenches, etc. (rate for cable only)	1 Rft	200.00	237.65
	(a) PVC insulated, PVC sheathed, twin core, 250/440 volts 7/0.44" (7/1.12mm).			
33	Supply and connection of M.S. sheet box of 16 SWG, 10 cm (4") deep with 4.75 mm thick (3/16") bakelite sheet top, for recessed wiring, including making holes for regulators switches, plugs etc.		-	-
	a) 10 x 10 cm (4" x 4").	1 Each	5.00	382.30
	b) 17.5 x 10 cm (7" x 4").	1 Each	5.00	522.75
	c) 22.5 x 10 cm (9" x 4").	1 Each	5.00	668.80
34	Supply and erection of switches 5 amp. Piano Type.	1 Each	100.00	102.70
35	Supply and erection of ceiling rose, bakelite.	1 Each	20.00	96.30
36	Supply and erection of wall socket with 3 pin 5 amp shoe.	1 Each	10.00	204.70
37	Supply and erection of 3 pin switch and plug combined recessed type (ii) 10/15 amp.	1 Each	5.00	213.10
38	P/F wall mounted DB (Distribution Board) made with 16SWG Sheet (Recessed/Surface mounted Type), Powder coated Paint, i/c the cost of Lock, Indication lights,Thimble, Copper Comb, Wiring, Netural & Earth Bar, Door Earthing, Digital Voltmeter,Digital Ammeter,Volt Selector Switch,Ammeter selector switch,Current Transformers and Controles Complete in all respect as approved and directed by the Engineer Incharge (Breakers will be Paid Separately)(a) 6" deep (i) 20~60A	1 No	5.00	24,422.65
39	Suppling,Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/ GE U.S.A / SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND in prelaid DBs and Panels i/c the cost of screws,necessary wire complet Single Pole(iii) 6-63 Amp (10 KA)	1 No	30.00	1,453.75

40	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker) of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (with fixed Thermal-Magnetic Trip) in pre-laid DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the Engineer in charge. a) Triple Pole (ii) 15-100 Amp (10 KA, 15KA)	1 No	10.00	13,796.30
41	Supplying, Installation and commissioning of MCCB (Moulded Case Circuit Breaker) of specified rating made of LEGRAND FRANCE /GEU.S.A/ SCHNEIDER GERMANY/ TERASAKI JAPAN/ SIEMEN/ ABBS WITZERLAND or approved equivalent manufacturer (with fixed Thermal-Magnetic Trip) in pre-laid DB sand Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the Engineer in charge. a) Triple Pole With Adjustable Thermal-Magnetic Trip /Electronic Trip (60-100%) (i) 25-100 Amp	1 No	5.00	19,859.40
42	Supply and erection of tube light, including rod, choke, starter with frame, flexible wire, including connection from ceiling rose, etc., complete ii) single rod (40 watts) with one choke and one starter.	1 No	15.00	1,995.30
43	Supply and erection of bakelite button holder shade, large size	1 No	15.00	178.75
44	Carriage of 100 Cf t. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cf t. (4.25 cu.m) timber, by truck or by any other means owned by the contractor from Sakhi Sarwar Quarry to site 275 Km including first 11KM hilly area.			
i	PCC 1:4:8	100 Cft	506.94	14,042.60
ii	PCC 1:2:4	100 Cft	201.78	14,042.60
iii	RCC 1:2:4	100 Cft	759.32	14,042.60
iv	DPC 1:2:4	100 Cft	35.48	14,042.60

Total Cost:

Total Cost for Section -13 (Evaporation Ponds)

20. Installation of Pumps, Motors and Allied accessories (Mechanical Works for Jarewala Drain) PS-7

1	Providing installation, testing and commissioning of horizontal centrifugal pump having discharge capacity of 10 cusec against 40 ft - 45 ft head including pump, motor, bowl assembly, column set, pre-lubrication tank, foundation fixing and alignment, MCCB/control panel with all electrical cables, accessories and connections from transformer to pump including earthing and protection devices, complete suction piping inside the chamber (SS/MS/CI) and delivery piping up to the outlet basin (40-50 ft) of approved material (Fibre reinforced cement/upvc of suitable internal diameter size as approved by E-in-C) with all bends, flanges, valves, gaskets, supports and accessories, and carrying out all works necessary for energizing, testing and full-load commissioning of the complete pump set in all respects.. Pump shall have min. 82% efficiency which should be verified according to ISO 9906-1B standard. Material of pump casing shall be Gray cast iron EN-GJL-250 having impeller in Stainless Steel grade 1.4408. Pump shall be coated internally with epoxy paint. Material of pump shall be verified according to material test certificate EN 10204-3.1. Motor shall be of reputed manufacturer having min. IE3 efficiency class. Rating of motor to be 45 KW (60HP, 950 rpm)/6 pole, 3 phase, 50 Hz, 380/400 Volts. Manufacturer shall have its own testing facility to verify pumps hydraulic performance testing. Manufacturer shall have its own material testing lab to verify metallurgical testing. [including transportation and all overhead charges]	Job	6.00	4,140,119.00
2	Providing, installation, testing and commissioning of 5 Ton capacity Gantry Crane, with girder bridge type arrangement, fitted with electric motor for its operation and mobility, electric wiring and fixing in position, complete in all respect.	No.	1	1,315,342.00
3	GNSS (Topographical) Surveying instrument with Base, Rover, Controller complete in all respect	No	1	1,829,000.00
4	Providing and supplying a complete aerial topographic survey package consisting of a professional RTK-enabled survey drone, high-resolution photogrammetry camera, licensed processing software, additional 8 batteries with charging hub, Ground Control Point (GCP) sets/markers, High graded RTK base station kit with tripod and pole, and 5 TB rugged NVMe SSD storage, complete in all respects (Equivalent: DJI Matrice 350 RTK Drone, Zenmuse P1c etc)	No	1	4,250,000.00

5	Providing and supplying a Total Station with angle accuracy $\leq 5''$, EDM reflectorless range ≥ 500 m, prism range ≥ 1500 m, distance accuracy $\pm(2$ mm + 2 ppm), 30× telescope, dual-axis compensator, rechargeable batteries with charger, prism set with pole, tripod, data storage/USB/Bluetooth interface, carrying case, calibration certificate, and all accessories complete.	No	1	1475000
6	Providing and supplying an automatic self-leveling Auto-Level with minimum 32× magnification, ± 2 mm/km accuracy, dual-axis compensator, tripod, 2.5 m leveling staff, carrying case, calibration certificate, and all accessories complete.	No	4	129800
7	Providing and supplying a high-performance workstation laptop with Intel Core i9-14900HX / AMD Ryzen 9 7940HX or higher, 64GB DDR5 RAM, 2TB NVMe Gen-5 M.2 SSD, dedicated NVIDIA RTX 4080 (12GB) or higher GPU, Windows 11 Pro, full-size keyboard with numeric pad, complete with premium laptop bag, wireless headphones (Sennheiser/Beats/Sony/Anker or equivalent), USB 3.2 Gen-2 (10Gbps) flash drive, and Logitech MX Master 3S wireless mouse or equivalent, complete in all respects.	No	2	850000

Total:

21. Installation and Solarization of Pumps

1	Providing installation, testing, and commissioning of a 64 kW Solar PV system capable of operating a horizontal centrifugal pump with discharge 10 cusec against 40 - 45 ft head , pump minimum 82% efficiency verified as per ISO 9906-1B standard, including Tier-1 Bloomberg-certified mono/ bi-facial N-type solar panels (JINKO / LONGI / JA / Canadian / AKCome / TW / Trina, 700+ W/panel, 23.5% efficiency), solar pump inverter INVT suitably rated for system capacity, mounted on 12 ft high L2/L3/L4 galvanized steel structure (14 gauge) with complete mechanical and civil works, DC and AC cabling using XLPE/PVC insulated tin-coated copper wires, combiner boxes, AC & DC breakers, SPDs (A+ grade), all distribution/protection boxes (12"×18"×18" SWG or equivalent), PVC pipes, flexible pipes (1–1.5"), thimbles (O-type, U-type with shrouds), Rawl bolts, nuts and bolts, complete earthing system, lightning arrestor, all civil works, foundations, and supports, electrical connections for net metering with meter, transportation of all materials from warehouse to site, testing, commissioning, and manufacturer-provided maintenance/after-sales service for 2 years, complete in all respects as directed by the Engineer-in-Charge.	No	6	5,061,388
---	--	----	---	-----------

Total:

22. Environmental Monitoring Cost

1	For Construction Phase			
a	Surface water Monitoring	Lump Sump		
b	Groundwater Monitoring	Lump Sump		
c	Ambient Air Quality Monitoring	Lump Sump		
2	For Operational Phase			
a	Surface water Monitoring	Lump Sump		
b	Groundwater Monitoring	Lump Sump		
3	Drinking Water & Groundwater Monitoring near disposal Pit			
a	Drinking Water Monitoring	Lump Sump		
b	Groundwater Monitoring	Lump Sump		
4	Training			
a	Training Session	Lump Sump	5.00	100,000.00
5	Emergency Plan	Lump Sump	1.00	
6	Environmental Audit Cost	Lump Sump	3.00	500,000.00
7	Site Visits by Regulatory Authorities	Lump Sump	1.00	
8	Traffic Management Cost			
a	Sign Board	Lump Sump	1.00	
b	Barricading Fence along Access Roads	Lump Sump	1.00	
c	Temporary Speed Breakers	Lump Sump	1.00	
d	Controlling Dust Pollution	Lump Sump	1.00	
e	Relocation of amenities and localized widening of road and barrier	Lump Sump	1.00	
Total Cost				

IAN

BOQ

Amount
(PKR)

24,248,830

2,860,933.54

164,012.98

22,150.85

7,171.66

58,714.56

8,202.71

127,893.00

401,942.51

793,514.00

118,758.82

1,550.77

8,500.10

31,859.05

4,622.16

30,737.21

9,998.10

17,019.89

15,250.00

602.43

30,104.13

37,735.67

3,692.80

	4,540.80
	4,824.46
	9,760.00
	6,801.56
	4,780,893.76
	81,585.78
	125,246.42
	3,645,446.71
	2,089,854.01
	968,202.00
	45,071.79
	4,101.30
	48,016.80
	64,931.52
	7,704.00

	43,679.52
	25,338.72
	18,823.20
	38,570.88
	68,257.73
	34,128.86
	48,666.03
	471,859.67
	82,233.47
	10,110.67
	7,921,829.10
	23,785.58
	22,483.46
	89,232.00
	16,026.21
	1,855,719.60
	1,035,764.40
	515,892.76
	12,359.23

28,581.60
153,381.30
96,670.00
21,067.20
34,672.19
4,201.55
240,200.81
4,150,037.86
2,211.02
32,631.38
16,656.81
2,166.95
45,049.50
45,049.50
7,760.18
7,760.18
84,648.44
13,794.50
236,229.95
493,958.41
74,429.35
607,392.19
-
408,676.89
4,545.00
39,079.66
33,686.03

206,433.60
83,155.25
(13,940.00)
1,443,457.97
34,489.81
25,526.70
146,565.99
411,769.25
29,567.32
36,515.28
4,528.65
416,924.86
457,471.59
43,810.59
1,258,140.33

279,129.60
73,136.00
542,332.00
50,379.02
4,380.75
6,528.71
25,058.35
86,466.09
104,888.64
24,116.31
98,222.88
26,774.80
6,797.60
4,638.60
31,600.00
50,932.02
10,866.54
497,063.34
26,940.00
16,032.00
13,893.00
-

25,704.00
13,512.00
38,024.00
1,529.20
2,091.00
2,675.20
8,216.00
1,540.80
1,637.60
852.40
97,690.60
34,890.00
110,370.40
79,437.60
23,943.60
2,145.00
56,950.02
22,668.58
85,303.05
3,985.29
5,458,652.97

24,248,830.08
7,167,775
2,739,984.74
105,391.15
4,352.55
8,379.68
136,928.29
8,717.94
116,902.62
38,633.75
493,527.00
67,742.33
3,720,560.05
1,550.77
8,500.10
31,859.05
4,622.16
30,737.21
9,998.10
17,019.89
15,250.00
602.43
120,139.71
16,933.57
21,226.32
2,077.20
2,554.20
2,713.76
5,490.00

3,825.88
54,820.92
1,649.77
24,348.20
15,440.28
2,092.23
41,758.09
41,758.09
7,491.72
7,491.72
78,465.88
13,318.83
203,493.70
437,308.50
64,487.80
41,131.39
105,619.20
17,244.90
12,763.35
73,283.00
205,884.63
14,783.66
18,257.64
2,264.33
208,462.43

	228,735.80
	21,905.30
	629,070.16
	139,564.80
	36,568.00
	271,166.00
	25,189.51
	2,190.38
	3,264.36
	12,529.17
	43,233.05
	52,444.32
	12,058.15
	49,111.44
	13,387.40
	3,398.80
	2,319.30

15,800.00
25,466.01
5,433.27
248,531.67
13,470.00
8,016.00
6,946.50
12,852.00
6,756.00
19,012.00
764.60
1,045.50
1,337.60
4,108.00
770.40
818.80
426.20
48,845.30
17,445.00
55,185.20

39,718.80
11,971.80
1,072.50
28,475.01
11,334.29
42,651.53
1,992.64
2,729,326.49
7,167,774.87
4,272,820
944,496.15
246,586.84
4,000.35
9,190.62
814,908.88
531,879.79
703,755.10
416,111.00
66,587.40
1,550.77
-
8,500.10
31,859.05
4,622.16
30,737.21
9,998.10

17,019.89
15,250.00
602.43
16,933.57
21,226.32
2,077.20
2,554.20
2,713.76
5,490.00
3,825.88
3,912,476.76
1,450.50
21,407.23
11,894.55
2,150.35
32,169.73
32,169.73
7,700.72
7,700.72
60,446.56
13,688.80
169,564.40
360,343.29
4,272,820.05
80,014,634
9,792,805.14
640,310.68
8,819.02
396,211.05

523,133.86
183,863.00
173,052.00
1,550.77
-
8,500.10
31,859.05
4,622.16
30,737.21
9,998.10
17,019.89
15,250.00
602.43
21,637.34
27,122.51
2,654.20
3,263.70
3,467.58
7,015.00
4,888.62
11,908,383.41
3,507,688.80
602,109.94
5,977,125.00
256,529.30
1,647,959.23
202,033.04

4,457,043.63
4,457,043.63
723,426.46
723,426.46
8,374,755.53
1,286,112.74
21,389,978.86
53,605,232.61
18,058.48
17,069.88
48,607.58
8,013.10
1,371,763.27
869,086.47
296,516.89
9,064.68
14,290.80
145,853.88
69,050.00
10,533.60
18,887.07
2,100.77
177,558.42
3,076,454.90

455,672.17
631,839.52
425,126.00
2,272.50
89,430.26
190,911.74
103,216.80
104,011.78
(130,560.00)
1,871,920.78
60,357.16
44,671.73
256,490.49
720,596.19
51,742.80
63,901.74
7,925.14
729,618.51

800,575.29
76,668.54
2,201,745.58
488,476.80
127,988.00
949,081.00
88,163.29
7,666.31
11,425.25
43,852.11
151,315.67
183,555.13
42,203.54
171,890.03
46,855.90
11,895.80
8,117.55

55,300.00
89,131.04
19,016.45
869,860.84
47,145.00
28,056.00
24,312.75
44,982.00
23,646.00
66,542.00
2,676.10
3,659.25
4,681.60
14,378.00
2,696.40
2,865.80
1,491.70
170,958.55
61,057.50
193,148.20

139,015.80
41,901.30
3,753.75
99,662.53
39,670.01
149,280.34
6,974.26
9,552,642.70
80,014,634.41
191,236,611
69,721,586.76
13,680.62
14,427.83
1,988,909.70
1,393,488.00
1,053,360.00
1,550.77
-
8,500.10
31,859.05
4,622.16
30,737.21
9,998.10
17,019.89
15,250.00

602.43
132,646.31
166,272.80
16,271.40
20,007.90
21,257.76
43,005.00
29,969.38
74,735,023.18
18,970.95
45,796.48
1,459,002.51
877,231.15
354,024.00
15,529.74
1,822.80
103,216.80
56,881.44

28,440.72
17,794.78
188,850.50
3,167,561.87
22,618.43
25,500.31
1,137,893.62
18,557,539.83
11,235,810.39
128,736.00
11,362.50
21,934.00
319,642.09
289,859.90
688,112.00
210,073.50
284,075.40
127,398.60
3,202,633.64

(4,020,081.80)
32,243,108.41
772,278.53
730,000.77
724,327.86
548,839.11
35,557,518.86
13,211,649.39
6,605,801.87
99,395.51
231,717.65
19,339.69
74,145.60
10,196.40
6,957.90
1,325,691.14
542,332.00
71,794.71
395,150.44

10,866.54
67,394.25
824,904.00
562,539.25
133,045.56
521,442.07
21,605.31
35,650.30
383,250.90
56,125.00
40,080.00
35,700.00
28,150.00
5,227.50
5,135.00
2,681.25
1,444.50
5,616.25
14,537.50
113,984.50
29,929.50

1,280,342.12
749,653.19
137,235.98
9,874.33
371,587.25
371,587.25
35,389.77
35,389.77
697,419.26
62,858.54
6,689,817.65
74,267,601.72
43,112.26
31,908.38
183,207.49
514,711.56
36,959.15
45,644.10
5,660.81
521,156.08
571,839.49
54,763.24

1,572,675.41
348,912.00
91,420.00
677,915.00
62,973.78
5,475.94
8,160.89
31,322.94
108,082.62
131,110.81
30,145.39
122,778.60
33,468.50
8,497.00
5,798.25
39,500.00
63,665.03
13,583.18
621,329.17
33,675.00
20,040.00
17,366.25

32,130.00
16,890.00

47,530.00

1,911.50
2,613.75
3,344.00
10,270.00
1,926.00
2,047.00
1,065.50

122,113.25

43,612.50

137,963.00

99,297.00

29,929.50

2,681.25

71,187.52
28,335.72
106,628.82
4,981.61

6,823,316.21
191,236,611.39
55,469,916
47,125,136.72
3,921,610.04
107,754.65
17,286.90
59,311.07
221,569.40
537,091.72
372,203.05
1,348,856.50
87,093.00
632,016.00
1,550.77
-
8,500.10
31,859.05
4,622.16
30,737.21
9,998.10
17,019.89
15,250.00
602.43
79,964.09
100,235.38
9,809.00
12,061.50
12,814.96
25,925.00

18,066.65
54,808,945.33
460,164.22
200,806.56
660,970.78
55,469,916.12
240,105,775
89,940,088.00
11,747.00
5,077,194.00
517,218.00
1,550.77
8,500.10
31,859.05
4,622.16
30,737.21
9,998.10
17,019.89
15,250.00
602.43
36,689.41
45,990.35
4,500.60
5,534.10
5,879.81
11,895.00

8,289.40
95,785,165.38
219,408.54
207,397.20
508,072.87
88,144.13
13,520,576.87
8,466,065.61
3,004,549.05
101,961.27
157,198.80
1,153,702.57
621,450.00
115,869.60
197,417.95
23,108.50
1,750,077.68
30,135,000.66
1,162,454.88
500,118.33

21,589,464.29

14,654,305.78

3,866,103.00

277,292.13

18,228.00

48,016.80

64,931.52

10,272.00

43,679.52

25,338.72

18,823.20

38,570.88

101,122.56

285,671.23

	194,327.12
	2,794,499.08
	82,233.47
	10,110.67
	45,785,563.19
	567,966.57
	536,873.71
	337,156.08
	236,469.50
	19,376,644.99
	7,441,078.48
	3,401,651.20
	87,095.24
	131,471.53
	10,972.92
	57,153.90
	5,098.20
	6,957.90
	802,323.14
	486,992.00

43,421.58
287,527.22
10,256.06
43,568.00
80,856.87
221,904.00
345,637.01
75,488.34
295,854.84
13,804.88
20,558.34
191,552.60
16,837.50
20,040.00
17,850.00
16,890.00
2,613.75
3,594.50
1,787.50
963.00
5,616.25
7,268.75

68,390.70
19,953.00
359,599.99
49,073.91
29,750.68
71,632.55
113,397.13
184,671.17
270,591.34
4,567.20
2,032.54
47,043.66
694,296.14
84,648.01
10,480.41
229,006.74
229,006.74
37,527.06
37,527.06
430,303.05
66,716.77
4,634,830.96
42,884,843.16
223,765.51
605,249.66
85,016.96
999,958.54

1,943,418.54
552,156.75
2,916,751.97
305,796.84
25,701.98
235,177.18
22,288.66
377,538.81
846,422.34
9,139,243.74
103,469.42
76,580.10
439,697.98
1,235,307.75
88,701.95
109,545.84
13,585.95
1,250,774.58

1,372,414.78
131,431.78
3,774,420.99
837,388.80
219,408.00
1,626,996.00
151,137.06
13,142.25
19,586.14
75,175.05
259,398.28
314,665.93
72,348.93
294,668.63
80,324.40
20,392.80

	13,915.80
	94,800.00
	152,796.07
	32,599.63
	1,491,190.01
	80,820.00
	48,096.00
	41,679.00
	77,112.00
	40,536.00
	114,072.00
	4,587.60
	6,273.00
	8,025.60
	24,648.00
	4,622.40
	4,912.80
	2,557.20
	293,071.80
	104,670.00
	331,111.20

238,312.80
71,830.80
6,435.00
170,850.05
68,005.73
255,909.16
11,955.87
16,375,958.91
240,105,775.04
56,729,160
21,859,158.82
2,071,731.25
18,531.48
172,406.00
1,550.77
-
8,500.10
31,859.05
4,622.16
30,737.21
9,998.10
17,019.89
15,250.00

602.43
12,229.80
15,330.12
1,500.20
1,844.70
1,959.94
3,965.00
2,763.13
24,281,560.15
81,966.96
77,479.75
183,786.12
32,052.41
4,924,733.83
3,097,291.28
1,083,212.87
37,654.13
57,163.20
419,269.20
220,960.00
42,134.40

	71,412.35
	8,403.09
	637,448.15
	10,974,967.74
	464,024.13
	176,940.93
	8,198,846.82
	5,687,531.84
	1,367,820.00
	126,797.73
	6,835.50
	18,006.30
	24,349.32
	3,852.00
	16,379.82
	9,502.02

7,058.70
14,464.08
33,707.52
110,392.13
68,752.57
1,061,243.09
30,837.55
3,791.50
17,431,133.55
1,249.51
18,440.93
10,888.11
2,092.23
29,448.23
29,448.23
7,491.72
7,491.72
55,332.23
13,318.83
153,277.16
328,478.89
55,616.45
160,768.53
22,671.19
266,655.61
511,377.53

144,828.00
766,864.84
65,064.62
6,741.50
62,468.58
5,943.64
99,261.52
180,093.92
2,348,355.94
8,622.45
6,381.68
36,641.50
102,942.31
7,391.83
9,128.82
1,132.16
104,231.22
114,367.90
10,952.65

314,535.08
69,782.40
18,284.00
135,583.00
12,594.76
1,095.19
1,632.18
6,264.59
21,616.52
26,222.16
6,029.08
24,555.72
6,693.70
1,699.40
1,159.65
7,900.00
12,733.01
2,716.64
124,265.83
6,735.00
4,008.00
3,473.25

6,426.00
3,378.00

9,506.00

382.30
522.75
668.80
2,054.00
385.20
409.40
213.10

24,422.65

8,722.50

27,592.60

19,859.40

5,985.90

536.25

14,237.50
5,667.14

21,325.76
996.32
1,364,663.24
56,729,159.52
92,113,523
10,152,815.33
1,512,635.39
1,880.78
29,568.67
684,192.09
316,743.10
1,550.77
-
8,500.10
31,859.05
4,622.16
30,737.21
9,998.10
17,019.89
15,250.00
602.43
12,229.80
15,330.12
1,500.20
1,844.70
1,959.94
3,965.00
2,763.13
12,857,567.97

157,862.99
149,220.91
489,445.50
88,144.13
10,907,201.46
6,341,030.54
2,824,553.33
77,117.83
157,198.80
889,320.16
524,780.00
115,869.60
190,180.06
23,108.50
1,411,807.35
24,346,841.16
375,929.19
266,452.22
8,915,298.15

5,486,561.70
2,059,776.00
107,544.79
9,569.70
30,010.50
40,582.20
3,852.00
27,299.70
15,836.70
11,764.50
24,106.80
42,134.40
162,638.78
103,533.28
1,153,979.19
51,395.92
6,319.17
18,894,584.90

318,399.56
300,969.04
254,540.88
203,879.74
12,370,425.44
4,703,645.16
2,210,130.70
57,019.76
85,506.94
7,136.61
23,685.40
3,398.80
4,638.60
592,975.94
486,992.00
30,655.49
174,312.86
5,128.03

19,061.00
110,952.00
291,188.68
49,096.16
192,419.16
10,228.25
15,434.10
140,260.93
11,225.00
13,360.00
8,925.00
11,260.00
1,568.25
2,054.00
893.75
481.50
5,616.25
2,907.50
45,593.80
9,976.50
112,693.61

15,379.08
21,744.85
45,584.35
86,005.10
117,518.02
205,227.72
3,231.64
1,438.17
28,812.81
425,235.23
58,663.44
8,711.98
158,669.22
158,669.22
31,195.67
31,195.67
298,137.20
18,301.76
2,941,529.18
27,543,886.71
193,197.06
600,514.31
85,016.96
999,958.54
1,891,912.89

534,053.25
2,834,734.34
181,491.80
24,859.30
233,337.20
22,288.66
366,922.61
502,355.47
8,470,642.38
92,113,523.12
93,766,768
7,758,796.26
1,541,995.90
11,233.72
41,793.76
13,878.49
2,880,166.07
172,406.00
1,550.77
-
8,500.10
31,859.05
4,622.16
30,737.21
9,998.10
17,019.89
15,250.00

	602.43
	12,229.80
	15,330.12
	1,500.20
	1,844.70
	1,959.94
	3,965.00
	2,763.13
	12,580,002.80
	196,068.39
	185,334.79
	619,301.93
	112,183.44
	13,672,741.76
	7,925,523.50
	3,559,821.95
	95,790.06
	200,071.20
	1,111,937.53
	649,070.00
	147,470.40

	240,637.36
	29,410.82
	1,769,773.62
	30,515,136.76
	270,049.83
	195,849.32
	6,737,330.18
	4,198,152.91
	1,513,989.00
	80,762.58
	6,835.50
	35,012.25
	47,345.90
	6,420.00

31,849.65
18,476.15
13,725.25
24,106.80
67,415.04
130,684.06
76,099.66
872,067.17
59,961.90
7,372.37
14,393,505.52
272,590.12
257,667.39
255,393.84
203,879.74
12,381,784.88
4,737,262.82
2,188,131.59
57,405.80
85,506.94
7,136.61

23,685.40
3,398.80
4,638.60
592,975.94
486,992.00
30,655.49
174,312.86
5,128.03
19,061.00
110,952.00
291,188.68
49,096.16
192,419.16
10,228.25
15,434.10
142,915.76
11,225.00
13,360.00
8,925.00
11,260.00
1,568.25
2,054.00

893.75
481.50
5,616.25
2,907.50
45,593.80
9,976.50
147,838.29
20,175.20
21,744.85
45,584.35
86,005.10
117,518.02
205,227.72
3,231.64
1,438.17
28,812.81
425,235.23
78,307.01
8,711.98
211,795.96
211,795.96
31,195.67
31,195.67
397,964.05
18,301.76
3,088,978.80
27,894,761.77

188,154.29
600,514.31
85,016.96
999,958.54
1,891,912.89
534,053.25
2,834,734.34
159,665.74
24,859.30
233,337.20
22,288.66
366,922.61
441,942.59
8,383,360.67
93,766,767.51
21,217,048
1,425,903.29
369,566.84
28,331.17
1,268,538.02
39,786.00

1,550.77
-
8,500.10
31,859.05
4,622.16
30,737.21
9,998.10
17,019.89
15,250.00
602.43
2,822.26
3,537.72
346.20
425.70
452.29
915.00
637.65
3,261,401.86
24,825.89
23,466.82
159,171.38
32,052.41
2,769,609.65

	1,439,797.16
	856,932.53
	16,224.63
	57,163.20
	172,871.65
	124,290.00
	42,134.40
	61,847.99
	8,403.09
	358,492.99
	6,147,283.79
	142,144.07
	87,429.64
	3,242,211.59
	2,084,556.29
	675,864.00
	47,457.84

4,101.30
60,673.54
33,971.86
419,665.68
6,798,075.81
74,826.88
241,152.79
34,006.78
399,983.41
767,066.29
217,242.00
1,150,297.26
60,384.02
10,112.26
93,702.88
8,915.46
148,892.28
167,138.36
3,373,720.68
689.14
10,170.77
9,575.26

2,092.23
25,896.92
25,896.92
7,491.72
7,491.72
48,660.45
13,318.83
120,619.05
271,903.00
8,622.45
6,381.68
36,641.50
102,942.31
7,391.83
9,128.82
1,132.16
104,231.22
114,367.90
10,952.65
314,535.08

69,782.40
18,284.00
135,583.00
12,594.76
1,095.19
1,632.18
6,264.59
21,616.52
26,222.16
6,029.08
24,555.72
6,693.70
1,699.40
1,159.65
7,900.00
12,733.01
2,716.64
124,265.83
6,735.00
4,008.00
3,473.25
6,426.00
3,378.00

9,506.00
382.30
522.75
668.80
2,054.00
385.20
409.40
213.10
24,422.65
8,722.50
27,592.60
19,859.40
5,985.90
536.25
14,237.50
5,667.14
21,325.76
996.32
1,364,663.24
21,217,048.38
294,349,621
in System and Manthar

1,783,600
50,176,000
3,841,600
8,333,000
6,375,000
730,800
449,250
599,000
250,600
104,000
92,000
9,800
590,250
478,800
13,530,000
87,343,700
4,378,000
2,533,800
2,002,835
11,453,600
658,560
5,833,100
3,773,700
1,457,400
787,200
99,000
2,737,500
238,500
545,000
11,825,000
675,700
1,389,960
822,660
51,211,515
4,880,000
2,445,000
313,000
109,760
842,400
8,590,160
16,263,340
5,598,490
1,034,832
22,896,662
8,064,000
8,064,000
42,000,000
42,000,000
2,000,000
2,000,000
222,106,037
id Manthar Drain
286340
15786
99000
74997

54750
228473
35200
16173
25500
14364
43890
10486
13050
20000
938009
187602
45000
40000
1210611
286,340
15,786
33,000
24,999
54,750
7,350
35,200
10,782
11,970
4,494
13,050
10,000
507,721
101,544
15,000
40,000
664265
286340
15786
33000
49998
54750
93100
35200
10782
25500
7182
23940
5992
13050
20000
674,620
134,924
15,000
40,000
864544
286340
15786
132000
83330
54750
276850
35200
21564
25500
14364
47880
11984
13050
20000
1,038,598
207,720
60,000

40,000
1346318
904422
24290
23650
33332
54750
12250
35200
10782
62600
84240
15960
5992
97500
10000
1,374,968
274,994
15,000
40,000
1821742
286340
15786
33000
49998
54750
93100
35200
10782
25500
7182
23940
5992
43500
20000
705,070
141,014
15,000
40,000
901084
904422
24290
33000
23650
33332
54750
12250
35200
10782
62600
84240
15960
5992
195000
10000
1,505,468
301,094
30,000
156,780
1993342
286340
15786
33000
49998
54750
71050
35200

10782
25500
7182
23940
5992
87000
10000
716,520
143,304
15,000
40,000
914824
4750000
121450
591250
99996
164250
36750
35200
14376
93900
126360
59850
29960
975000
35000
7,133,342
1,426,668
15,000
156,780
8731790
18448519
34250928
32645
178934
243647
50666
591840
287249
13206568
3348038
1604550

53,795,064
294,349,621
272,635,552
160,955,550
7033367
130240
8613.6
13910890
2633068
17167038
2651420
1382135
169904
1217122.252
8666258.4
1709492.5
1337197.76
623589.12
52762000
277666.5
272,635,552

109,394,699

104,036,352

3886124

1472223

109,394,699

39,798,176

11,658,372.00

8,178,639.00
1,472,223.00
7,772,248.00
1,472,223.00
7,772,248.00
1,472,223.00
39,798,176

37,602,575

12,349,350

8,787,425

8,232,900

8,232,900

37,602,575

169,663,050

72155550
97,507,500
169,663,050
157,218,842
1,147,751.93
1,114,141.15
4,006,818.25
14,495,273.62
1,012,406.60
667,277.94
239,070.23
17,124,916.38
16,116,268.40

19,797,625.13

7,143,973.20

1,747,036.20

2,441,684.70

4,461,932.99

376,407.28

295,840.98

1,166,074.11

6,621,370.23

2,690,905.96

900,900.00

839,107.40

5,222,453.51

1,111,712.45

1,547,088.97

2,312,605.88

3,272,268.70

609,126.70

154,645.40
105,528.15
119,546.70
233,325.46
373,559.55
126,439.95
596,668.80
734,297.20
4,685,590.00
309,290.80
864,227.00
572,845.00
396,305.00
132,650.70
1,384,028.10
-
125,580.00
146,510.00
94,185.00
181,927.20
1,021,475.00
607,880.00
974,610.00
512,330.00
4,325,230.00
69,578.60
190,281.00
60,860.80
327,099.50

97,597.50
52,579.80
37,255.40
38,784.20
2,222,461.15
511,078.75
529,165.00
7,621.25
984,201.40
60,392.15
1,089,433.80
9,081,800.00
1,556,898.40
219,986.46
2,684,593.83
136,459.25
157,218,842.13
256,928,072
19,649,063.04
1,611,746.63
75,129.37
52,209.50
73,150.00
478,639.26

344,812.00
1,550.77
-
8,500.10
31,859.05
4,622.16
30,737.21
9,998.10
17,019.89
15,250.00
602.43
24,459.60
30,660.23
3,000.40
3,689.40
3,919.87
7,930.00
5,526.27
3,876.92
173,224.43
1,001,280.00
45,583.55
23,708,040.18

17,062,438.49
4,142,182.88
147,218.89
1,567,444.82
3,354,570.01
20,667,561.37
225,454.00
1,550.77
-
8,500.10
31,859.05
4,622.16
30,737.21
9,998.10
17,019.89
15,250.00
602.43
15,992.82
20,047.08
1,961.80
2,412.30
2,562.99
5,185.00
3,613.33
47,338,785.49

71,478.38
48,710.39
1,459.55
531,243.24
53,048.00

775.38
-
4,250.05
15,929.53
2,311.08
15,368.60
4,999.05
8,509.95
7,625.00
301.21

3,763.02
4,716.96
461.60
567.60
603.06
1,220.00
850.20
778,191.85
48,116,977.33

20,470,044.45
1,834,437.10

4,796,515.71
158,166.69
543,059.99
3,163,105.98
1,538,727.22

4,652.30
-
25,500.31
95,577.15
13,866.49
92,211.62
29,994.30
51,059.68
45,750.00
1,807.28

11,289.05
14,150.88
1,384.80
1,702.80
1,809.17
3,660.00
2,550.59
32,901,023.56

1,593,680.13
1,506,435.41
627,319.20
272,396.48

39,222,047.53

15,489,555.74

6,535,082.02

160,801.53

183,759.95

15,337.03

145,201.80

10,196.40

6,957.90

1,011,670.34

509,128.00

58,664.34

455,231.02

10,500.26

102,112.50

45,008.00

419,688.00

456,034.22

105,511.07

413,521.23

17,873.58

28,646.64

253,293.64

39,287.50

33,400.00

35,700.00

28,150.00

5,227.50

5,135.00

2,681.25

1,444.50

5,616.25

14,537.50

113,984.50

29,929.50

352,116.68

150,818.46

150,818.46
26,557.94
26,557.94
283,387.01
47,216.31
5,183,782.45
76,192,002.71
21,152.79
40,374.09
83,329.16
151,246.33
6,259,885.98
3,693,666.37
1,322,346.69
35,925.89
3,089.40
2,548,328.31
12,531.38
184,944.92
17,788.57
2,258.28
48,110.69
48,110.69

9,789.18
9,789.18
90,399.66
17,403.27
1,501,921.39
(32,933.25)
16,069,458.96
46,405.59
13,376.03
114,440.04
150,822.75
426,610.80
213,305.40
240,839.20
33,852.50
184,421.02
8,496,060.40
4,914,015.08
1,876,005.36
41,554.60
33,677.22

	3,089.40
	82,528.88
	111,601.05
	12,840.00
	75,074.18
	43,550.93
	32,352.38
	4,488.16
	66,238.73
	13,924.12
	1,594.08
	37,658.96
	37,658.96
	5,707.98
	5,707.98
	70,760.93
	10,147.68
	1,578,404.49
	(215,475.00)
	(20,825.54)
	18,742,414.33
	252,034.59

	124,514.37
	47,282.02
	3,732,590.18
	1,742,027.36
	1,166,066.55
	16,091.09
	3,089.40
	4,488.16
	66,238.73
	13,466.76
	1,594.08
	36,421.99
	36,421.99
	5,707.98
	5,707.98
	68,436.67
	10,147.68
	820,021.86
	8,152,349.45
	294,089.58
	124,514.37
	47,282.02
	4,722,507.02

2,581,103.46
1,166,066.55
24,207.32
3,089.40
4,488.16
66,238.73
13,466.76
1,594.08
36,421.99
36,421.99
5,707.98
5,707.98
68,436.67
10,147.68
941,538.14
10,153,029.89
18,305,379.34
21,152.79
40,374.09
83,329.16
151,246.33
6,259,885.98

	3,693,666.37
	1,322,346.69
	35,925.89
	3,089.40
	2,548,328.31
	12,531.38
	184,944.92
	17,788.57
	2,258.28
	48,110.69
	48,110.69
	9,789.18
	9,789.18
	90,399.66
	17,403.27
	1,501,921.39
	(32,933.25)
	16,069,458.96
	43,112.26
	31,908.38
	-

183,207.49
514,711.56
36,959.15
45,644.10
5,660.81
521,156.08
571,839.49
54,763.24
1,572,675.41
348,912.00
91,420.00
677,915.00
62,973.78
5,475.94
8,160.89
31,322.94
-
108,082.62

131,110.81
30,145.39
122,778.60
33,468.50
8,497.00
5,798.25
39,500.00
63,665.03
13,583.18
621,329.17
-
33,675.00
20,040.00
17,366.25
-
32,130.00
16,890.00
47,530.00
-
1,911.50
2,613.75
3,344.00
10,270.00
1,926.00
2,047.00
1,065.50
122,113.25
43,612.50

137,963.00
99,297.00
29,929.50
2,681.25
71,187.52
28,335.72
106,628.82
4,981.61
6,823,316
256,928,072
35,929,256
24840714
1315342
1829000
4250000

1475000
519200
1700000
35929256
30,368,325
30,368,325.00
30,368,325
9,000,000
1,300,000.00
700,000.00
500,000.00
500,000.00
500,000.00
250,000.00
250,000.00
500,000.00
1,500,000.00
1,500,000.00
500,000.00
125,000.00
100,000.00
100,000.00
175,000.00
500,000.00
9,000,000.00